

Appendix 5

Geotechnical Test Results

LABORATORY TEST RESULTS

ADDRESS: 11 ROSSLYN HILL, FARNSTED, LONDON N43

Bore hole	Sample name	Depth m	Grain size				L ₅₀ -d ₅₀		Liquid Consistency					Soluble (SO ₄)				Remarks
			Coarse mm %	Medium mm %	Mass %	Unit Content %	D ₅₀ mm	L ₅₀ mm	Type	Plastic limit LP ₁	Flow limit LP ₂	Shrink value LV ₁	Atterberg liquidity index LV ₂	Swelling value LV ₃	SO ₄ mg/l	mg/l + 25	g/l	
B42	U1A	1.80				34												SOIL CLASSIFICATION = EV 0% retained on 425µm sieve
	U2A	2.10				32												
	U2B	2.40				30												
	U2C	2.70				30												
	U3A	3.00				27												
	U3B	3.30				30												
	U3C	3.60				31												
	U4A	4.00				28												
	B5	2.00 - 2.50				28									3622		7.0	
	M1	2.95														3235	7.2	
	U1	3.00 - 3.50	76	25	53	33	1.95	1.46	9	28	50	66	0					
	B4	3.50				30									5943		7.6	
	U2	4.00 - 4.40				34	1.93	1.44	9	37	70	69	0					
	B5	4.50				30												

AQUARIUS PATENT 2:1 WATER:SOIL

U - UNDISTURBED SAMPLE
D - DISTURBED SAMPLE
B - BULK SAMPLE
W - WATER SAMPLE
C.C. - CONSOLIDATED UNDRAINED
C.U. - CONSOLIDATED DRAINED
Q. - IMMEDIATE UNDRAINED
Q.N. - IMMEDIATE UNDRAINED MULTISTAGE

13469

GROUND ENGINEERING

L I M I T E D

1st Floor, 100, 101, 102, 103, 104, 105, 106, 107, 108, 109, 110, 111, 112, 113, 114, 115, 116, 117, 118, 119, 120, 121, 122, 123, 124, 125, 126, 127, 128, 129, 130, 131, 132, 133, 134, 135, 136, 137, 138, 139, 140, 141, 142, 143, 144, 145, 146, 147, 148, 149, 150, 151, 152, 153, 154, 155, 156, 157, 158, 159, 160, 161, 162, 163, 164, 165, 166, 167, 168, 169, 170, 171, 172, 173, 174, 175, 176, 177, 178, 179, 180, 181, 182, 183, 184, 185, 186, 187, 188, 189, 190, 191, 192, 193, 194, 195, 196, 197, 198, 199, 200, 201, 202, 203, 204, 205, 206, 207, 208, 209, 210, 211, 212, 213, 214, 215, 216, 217, 218, 219, 220, 221, 222, 223, 224, 225, 226, 227, 228, 229, 230, 231, 232, 233, 234, 235, 236, 237, 238, 239, 240, 241, 242, 243, 244, 245, 246, 247, 248, 249, 250, 251, 252, 253, 254, 255, 256, 257, 258, 259, 260, 261, 262, 263, 264, 265, 266, 267, 268, 269, 270, 271, 272, 273, 274, 275, 276, 277, 278, 279, 280, 281, 282, 283, 284, 285, 286, 287, 288, 289, 290, 291, 292, 293, 294, 295, 296, 297, 298, 299, 300, 301, 302, 303, 304, 305, 306, 307, 308, 309, 310, 311, 312, 313, 314, 315, 316, 317, 318, 319, 320, 321, 322, 323, 324, 325, 326, 327, 328, 329, 330, 331, 332, 333, 334, 335, 336, 337, 338, 339, 340, 341, 342, 343, 344, 345, 346, 347, 348, 349, 350, 351, 352, 353, 354, 355, 356, 357, 358, 359, 360, 361, 362, 363, 364, 365, 366, 367, 368, 369, 370, 371, 372, 373, 374, 375, 376, 377, 378, 379, 380, 381, 382, 383, 384, 385, 386, 387, 388, 389, 390, 391, 392, 393, 394, 395, 396, 397, 398, 399, 400, 401, 402, 403, 404, 405, 406, 407, 408, 409, 410, 411, 412, 413, 414, 415, 416, 417, 418, 419, 420, 421, 422, 423, 424, 425, 426, 427, 428, 429, 430, 431, 432, 433, 434, 435, 436, 437, 438, 439, 440, 441, 442, 443, 444, 445, 446, 447, 448, 449, 450, 451, 452, 453, 454, 455, 456, 457, 458, 459, 460, 461, 462, 463, 464, 465, 466, 467, 468, 469, 470, 471, 472, 473, 474, 475, 476, 477, 478, 479, 480, 481, 482, 483, 484, 485, 486, 487, 488, 489, 490, 491, 492, 493, 494, 495, 496, 497, 498, 499, 500, 501, 502, 503, 504, 505, 506, 507, 508, 509, 510, 511, 512, 513, 514, 515, 516, 517, 518, 519, 520, 521, 522, 523, 524, 525, 526, 527, 528, 529, 530, 531, 532, 533, 534, 535, 536, 537, 538, 539, 540, 541, 542, 543, 544, 545, 546, 547, 548, 549, 550, 551, 552, 553, 554, 555, 556, 557, 558, 559, 560, 561, 562, 563, 564, 565, 566, 567, 568, 569, 570, 571, 572, 573, 574, 575, 576, 577, 578, 579, 580, 581, 582, 583, 584, 585, 586, 587, 588, 589, 590, 591, 592, 593, 594, 595, 596, 597, 598, 599, 600, 601, 602, 603, 604, 605, 606, 607, 608, 609, 610, 611, 612, 613, 614, 615, 616, 617, 618, 619, 620, 621, 622, 623, 624, 625, 626, 627, 628, 629, 630, 631, 632, 633, 634, 635, 636, 637, 638, 639, 640, 641, 642, 643, 644, 645, 646, 647, 648, 649, 650, 651, 652, 653, 654, 655, 656, 657, 658, 659, 660, 661, 662, 663, 664, 665, 666, 667, 668, 669, 670, 671, 672, 673, 674, 675, 676, 677, 678, 679, 680, 681, 682, 683, 684, 685, 686, 687, 688, 689, 690, 691, 692, 693, 694, 695, 696, 697, 698, 699, 700, 701, 702, 703, 704, 705, 706, 707, 708, 709, 710, 711, 712, 713, 714, 715, 716, 717, 718, 719, 720, 721, 722, 723, 724, 725, 726, 727, 728, 729, 730, 731, 732, 733, 734, 735, 736, 737, 738, 739, 740, 741, 742, 743, 744, 745, 746, 747, 748, 749, 750, 751, 752, 753, 754, 755, 756, 757, 758, 759, 760, 761, 762, 763, 764, 765, 766, 767, 768, 769, 770, 771, 772, 773, 774, 775, 776, 777, 778, 779, 780, 781, 782, 783, 784, 785, 786, 787, 788, 789, 790, 791, 792, 793, 794, 795, 796, 797, 798, 799, 800, 801, 802, 803, 804, 805, 806, 807, 808, 809, 810, 811, 812, 813, 814, 815, 816, 817, 818, 819, 820, 821, 822, 823, 824, 825, 826, 827, 828, 829, 830, 831, 832, 833, 834, 835, 836, 837, 838, 839, 840, 841, 842, 843, 844, 845, 846, 847, 848, 849, 850, 851, 852, 853, 854, 855, 856, 857, 858, 859, 860, 861, 862, 863, 864, 865, 866, 867, 868, 869, 870, 871, 872, 873, 874, 875, 876, 877, 878, 879, 880, 881, 882, 883, 884, 885, 886, 887, 888, 889, 890, 891, 892, 893, 894, 895, 896, 897, 898, 899, 900, 901, 902, 903, 904, 905, 906, 907, 908, 909, 910, 911, 912, 913, 914, 915, 916, 917, 918, 919, 920, 921, 922, 923, 924, 925, 926, 927, 928, 929, 930, 931, 932, 933, 934, 935, 936, 937, 938, 939, 940, 941, 942, 943, 944, 945, 946, 947, 948, 949, 950, 951, 952, 953, 954, 955, 956, 957, 958, 959, 960, 961, 962, 963, 964, 965, 966, 967, 968, 969, 970, 971, 972, 973, 974, 975, 976, 977, 978, 979, 980, 981, 982, 983, 984, 985, 986, 987, 988, 989, 990, 991, 992, 993, 994, 995, 996, 997, 998, 999, 1000

LABORATORY TEST RESULTS

CONTRACT 11 ROSSLYN HILL, HAMPSHIRE, LONDON NW3

Borehole	Sample	Depth (m)	Consolidation			Density		Tensile Compression				Sulphate (SO ₄)				Remarks
			Initial	Final	Applied	Moisture Content	W _u (g/m ³)	W _u (%)	Unconf. Strength	Unconf. Strength	Unconf. Strength	Unconf. Strength	Unconf. Strength	Unconf. Strength	Unconf. Strength	
BH-1	U8	10.90 - 11.60				20	1.96	1.53	0	205	200	107	U			
	U9	12.60 - 12.80				29	1.97	1.53	0	202	220	101	0			
	U10	14.00 - 14.50				20	1.98	1.55	0	115	250	58	0			
	U11	15.50 - 16.00				31	1.97	1.50	0	157	280	79	0			
	U12	17.00 - 17.50				30	1.95	1.50	0	227	310	114	0			
	U13	18.50 - 19.20				28	1.96	1.53	0	279	350	160	0			
	U14	19.60 - 19.90				26	1.93	1.49	0	151	350	75	0			

aqueous Extract 2:1 Water:Soil

C.C. - CONSOLIDATED UNDRAINED
C.D. - CONSOLIDATED DRAINED
D. - IMMEDIATE UNDRAINED
Q.M. - IMMEDIATE UNDRAINED Q.M. (STAGE)

U - UNDISTURBED SAMPLE
D - DISTURBED SAMPLE
B - BULK SAMPLE
W - WATER SAMPLE

GROUND ENGINEERING

I I M T F D

Tel: 01733 566566
www.groundengineering.co.uk

13469

LABORATORY TEST RESULTS

ADDRESS: 31 ROSSLYN HILL, HAMPSHIRE, LONDON SW3

Borehole	Depth (m)	Consolidation				Density		Triaxial Compression					Seismicity (V _s)			Remarks
		Initial Pressure (kPa)	Pressure (kPa)	Moisture Ratio (%)	Moisture Content (%)	Area (mm ²)	Dry Density (kg/m ³)	Type	Principal Stress Difference (kPa)	Conf. Pressure (kPa)	Final Strain (mm)	Applied Stress (kPa)	Soil Unit Weight (kN/m ³)	Consolidation Pressure (kPa)	Water Content (%)	
MS1	D1	0.90			33											
	D4	1.20			31											
	U1A	1.50			30											
	U1B	1.80			31											
	U2A	2.10			31											
	U2B	2.40			30											
	U2C	2.70			28											
	U3A	3.00			29											
	U3B	3.40			30											
	U3C	3.70			31											
MS2	U4A	4.00			30											
	U4B	4.50			33											
	D3	0.90			33											
	D4	1.20			29											
	U1A	1.50			30											
	U1B	1.80			35											

Aqueous Extract 2:1 Water:Soil

U - UNDISTURBED SAMPLE
D - DISTURBED SAMPLE
B - BULK SAMPLE
W - WATER SAMPLE
C.O. - CONSOLIDATED UNPAIRED
C.P. - CONSOLIDATED PAIRED
O. - IMMEDIATE UNPAIRED
O.X. - IMMEDIATE UNPAIRED MULTISTAGE

LABORATORY TEST RESULTS

CONTINUED 11 RD55, YH HILL, HAMPSTEAD, LONDON N13

Borehole	Sample	Depth m	Identification			Density		Index Properties				Sulphate SO ₄				Remarks
			Time min	Moisture %	Plasticity Index	Moisture Content	W _{max} Mg m ⁻³	W _p Moist	Shrinkage Ratio	Swelling Pressure kPa	Swelling Ratio	Free Water mg/l	Bound Water mg/l	Free Water mg/l	Free Water mg/l	
MS2	L2A	2.50				32										
	L2B	2.40				29										
	L2C	2.70				33										
	L2A	5.00				29										
	L2B	3.40				31										
	L2C	3.70				32										
	L4A	4.00				34										
	L4B	4.50				31										
	L4C	1.20				36										
	L1A	1.50				28										
MS3	L1B	1.80				29										
	L2A	2.10				50										
	L2B	2.40				30										
	L2C	2.70				32										
	U3A	3.00				29										
	U3B	3.40				31										

Aqueous Extract 2:1 Water:Soil

U - UNDISTURBED SAMPLE
 A - DISTURBED SAMPLE
 B - BULK SAMPLE
 W - WATER SAMPLE
 C.U. - CONSOLIDATED UNDRAINED
 C.D. - CONSOLIDATED DRAINED
 O. - IMMEDIATE UNDRAINED
 O.M. - IMMEDIATE UNDRAINED MULTISTAGE

LABORATORY TEST RESULTS

CONTINUED: 1 ROSSLYN HILL, HAMPSHIRE, LONDON N4J

Borehole	Sample	Depth m	Grain size			Density		Index Properties					Soilschem 2004			Remarks	
			Gravel mm	Sand mm	Fine mm	Moisture Content	Void Ratio	Per mm ³	Free Water	Atterberg Limits	Shrinkage mm	Consistency Index	Angle of Shear Resistance degrees	TC _u mm	TC _u mm		Volume mm ³
MS3	U3C	3.70					31										
	U4A	4.10					29										
	U4B	4.50					31										
	U3A	3.40					35										
	U3B	3.70					36										
MS5	U4C	6.00					25										
	U4B	6.50					57										
	U2a	2.90					93										
	U2A	2.95					34										
	U3A	5.30					35										
MS6	U5B	5.60					31										
	U3C	3.90					31										
	U4A	4.20					33										
	U4B	4.40					37										
	U2A	2.10					29										
MS7	U2B	2.40					31										

Aqueous Extract 2:1 Water:Soil

U - UNDISTURBED SAMPLE
D - DISTURBED SAMPLE
R - BULK SAMPLE
W - WATER SAMPLE

C.U. - CONSOLIDATED UNCRUSHED
C.D. - CONSOLIDATED CRUSHED
O. - IMMEDIATELY UNCRUSHED
O.M. - IMMEDIATELY UNCRUSHED MULTISTAGE

GROUND ENGINEERING

Tel: 01733-366556
www.groundengineering.co.uk

LABORATORY TEST RESULTS

CONTRACT 11 ROSGLEN HTL, HARTSTED, LONDON MW3

Borehole	Sample	Depth m	Classification				Density		Grain Characteristics					Soil Water (30%)				Remarks
			Log ₁₀ C.C.	Plastic Limit %	Plasticity Index %	Maximum Dry Density %	Bulk Ug m ³	Ug m ³	Grain Size Distribution %	Grain Number 10% 10%	Grain Number 10% 10%	Grain Number 10% 10%	Grain Number 10% 10%	Grain Number 10% 10%	Grain Number 10% 10%	Grain Number 10% 10%	Grain Number 10% 10%	
MS7	U2C	2.70				31												
	U3A	3.00				28												
	U3B	3.30				31												
	U3C	3.50				32												
	U3A	3.30				34												
MS8	U3A	3.30				32												
	U3B	3.60				32												
	U3C	3.90				32												
	U4	4.20				35												
	U1A	1.50				29												
MS9	U1B	1.80				29												
	U2A	2.10				29												
	U2B	2.40				31												
	U2C	2.70				31												
	U2D	3.00				31												

Aqueous Extract 2:1 Water:Soil

U - UNDISTURBED SAMPLE
D - DISTURBED SAMPLE
H - BULK SAMPLE
W - WATER SAMPLE
C.C. - CONSOLIDATED UNGRAINED
C.L. - CONSOLIDATED GRAINED
Q. - IMMEDIATE UNGRAINED
Q.N. - IMMEDIATE UNGRAINED MULTISTAGE

LABORATORY TEST RESULTS

CONTINUED 1: ROSSLYN HILL, HAMPSHIRE, LONDON W3

Trial pit	Sample	Depth m	COMPOSITION				Density		Test & Compression				Sedimentation				Remarks
			Loose Limit ρ_s	SHrink Limit ρ_{sh}	Plasticity Index I_p	Moisture Content w	ILN $Mg \cdot m^{-3}$	IPN $Mg \cdot m^{-3}$	Type	Preval Shrinkage u_s	Swamp Pressure MPa	Swamp Strength MPa	Adjusted Shrinkage Moisture w_{adj}	Total Solids ρ_{ts}	Settle Value m^3	pH	
TP1	M1	2.40													486	7.8	SOIL CLASSIFICATION = CL 2% retained on 475µm sieve
	M10	2.50														7.6	
TP5A	B7	2.20				30								2601			
	B8	2.50				31											
	B9	2.80				31											
	B10	3.10				31											
*P4	B3	0.90												2004		7.2	
	B4	1.20	78	27	51												
	M1	2.43													469	8.4	
Adipic Acid 2:1 Water:50:1																	

U = UNDISTURBED SAMPLE
D = DISTURBED SAMPLE
B = BULK SAMPLE
W = WATER SAMPLE
C.U. = CONSOLIDATED UNDRAINED
C.D. = CONSOLIDATED DRAINAGE
Q.U. = UNCONSOLIDATED UNDRAINED
Q.M. = IMMEDIATE UNCONSOLIDATED MULTISTAGE

TEST CERTIFICATE**One-Dimensional Consolidation
Properties**

(Tested in accordance with BS1377 (Part 5) 1990)

Client: Ground Engineering Ltd
 Client Address: Newark Road
 Peterborough
 Cambridgeshire
 Postcode: PE1 5JA
 Contact: Simon Weatherley
 Site Name: 11 Rosslyn Hill
 Site Address: London NW3

Newark Road Peterborough
 01733 666566 / 01733 315280
 e: admin@groundengineering.co.uk
 Certificate Number: PL4882-1-9/73
 Client Reference Number: C13469
 Date Sampled: Unknown
 Date Received: 16.01.2015
 Date Tested: 19.01.2015
 Sampling Certificate No: N/A
 Certificate of Sampling: N/A
 Sampled By: Client


Test Details

Location: BH2
 Sample Ref: L1
 Sample: Firm brown orange brown grey slightly
 Description: silty CLAY with rare sericite crystals
 Particle Density (Mg/m^3): 2.74 Assumed
 Mean Lab Temp ($^{\circ}C$): 22
 Variations from Standard: None
 Lab Reference: PL4882-1-9
 Depth (m): 3.00 m

Specimen Details

	INITIAL	FINAL
Height (mm):	18.67	16.33
Bulk Density (Mg/m^3):	1.87	2.08
Moisture Content (%):	31	27
Dry Density (Mg/m^3):	1.43	1.64
Voids Ratio:	0.914	0.674
Degree of Saturation (%):	92.4	110.5
Diameter (mm):	74.98	N/A
Swelling Pressure (kPa):	80	N/A
Method of time fitting used:	Log Time	N/A

Voids Ratio against logarithm of Applied Pressure



Applied Pressure (kPa)	Coefficient of Compressibility m_v (mm/MN)	Coefficient of Consolidation c_v (mm/year)
40		
150	0.38	0.61
300	0.22	0.29
600	0.14	0.26
1200	0.08	0.29
600	0.03	---

Comments:

Approved: [x] V. Farnup - Laboratory Manager
 Signatory: [x] L. Perch - Team Leader

Signed

for and on behalf of Ground Engineering Ltd

Date Reported: 30/01/2015

Opinions and interpretations expressed herein are outside the scope of the UKAS Accreditation.
 This report may not be reproduced other than in full without the prior written approval of the issuing laboratory.

Registered in England/Wales
 Reg Number 692957a
 Reg Office: Ground Engineering Ltd
 Newark Rd
 Peterborough PE1 5JA

TEST CERTIFICATE**One-Dimensional Consolidation****Properties**

(Tested in accordance with BS1377 : Part 5 : 1990)

Client: Ground Engineering Ltd
 Client Address: Newark Road
 Peterborough
 Cambridgeshire
 Postcode: PE1 5UA
 Contact: Simon Weatherley
 Site Name: 11 Rosslyn Hill
 Site Address: London NW3

Newark Road Peterborough
 01733 566666 01733 315280
 e. admin@groundengineering.co.uk

Certificate Number: PL4882-1-11-731
 Client Reference Number: C13469
 Date Sampled: Unknown
 Date Received: 16.01.2015
 Date Tested: 19.01.2015
 Sampling Certificate No: N/A
 Certificate of Sampling: N/A
 Sampled By: Client


Test Details

Location: BH2
 Sample Ref: U2
 Sample Description: Firm brown orange brown grey slightly silty CLAY with occasional fine selenite crystals
 Particle Density (Mg/m^3): 2.74 Assumed
 Mean Lab Temp ($^{\circ}\text{C}$): 22
 Variations from Standard: None
 Lab Reference: PL4882-1-11
 Depth (m): 4.00 m

Specimen Details

	INITIAL	FINAL
Height (mm)	15.04	16.90
Bulk Density (Mg/m^3)	1.90	2.08
Moisture Content (%)	32	29
Dry Density (Mg/m^3)	1.44	1.62
Voids Ratio	0.900	0.695
Degree of Saturation (%)	96.2	113.9
Diameter (mm)	74.96	N/A
Swelling Pressure (kPa)	98	N/A
Method of time fitting used	Log Time	N/A

Voids Ratio against logarithm of Applied Pressure



Applied Pressure (kPa)	Coefficient of Compressibility (α_v) (mm^3/MN)	Coefficient of Consolidation (c_v) (mm^2/year)
99		
150	0.34	0.65
300	0.18	0.40
600	0.12	0.43
1200	0.08	0.44
2400	0.03	---

Comments:

Approved: (x) M. Harcup - Laboratory Manager
 Signatory: (x) J. Leitch - Team Leader

Signed

for and on behalf of Ground Engineering Ltd

Date Reported: 30/01/2015

Opinions and interpretations expressed herein are outside the scope of the UKAS Accreditation.
 This report may not be reproduced other than in full without the prior written approval of the issuing laboratory.

Registered in England Wales
 Reg Number: 6920374
 Reg Office: Ground Engineering Ltd
 Newark Rd
 Peterborough PE1 5UA

TEST CERTIFICATE**One-Dimensional Consolidation
Properties**

(Tested in accordance with BS1377 Part 5:1990)

Newark Road Peterborough

t 01733 566566 f 01733 315280

e admin@groundengineering.co.uk

Client: Ground Engineering Ltd

Client Address: Newark Road

Peterborough

Cambridgeshire

Postcode: PE1 5UA

Contact: Simon Weatherley

Site Name: 11 Roslyn Hill

Site Address: London NW3

Certificate Number: PL4852-1-13731

Client Reference Number: G13469

Date Sampled: Unknown

Date Received: 16.01.2015

Date Tested: 19.01.2015

Sampling Certificate No: N/A

Certificate of Sampling: N/A

Sampled By: Client


Test Details

Location: BH2
 Sample Ref: U3
 Sample Description: Firm brown orange-brown grey slightly silty CLAY with occasional selenite crystals
 Particle Density (Mg/m^3): 2.74 Assumed
 Mean Lab Temp ($^{\circ}C$): 22
 Variations from Standard: None
 Lab Reference: PL4852-1-13
 Depth (m): 5.00 m

Specimen Details

	INITIAL	FINAL
Height (mm):	18.59	16.38
Bulk Density (Mg/m^3):	1.83	2.07
Moisture Content (%):	33	32
Dry Density (Mg/m^3):	1.38	1.66
Voids Ratio:	0.992	0.755
Degree of Saturation (%):	91.9	117.2
Diameter (mm):	75.06	N/A
Swelling Pressure (kPa):	62	N/A
Method of linear fitting used:	Lug Line	N/A

Voids Ratio against logarithm of Applied Pressure



Applied Pressure (kPa)	Coefficient of Compressibility (m_v , mm/MN)	Coefficient of Consolidation (c_v , mm/year)
62	0.48	0.52
100	0.34	0.51
200	0.21	0.33
400	0.12	0.22
800	0.05	---
400		

Comments:

Approved: J. M. Harrop - Laboratory Manager
 Signatory: C. J. Petch - Team Leader

Signed:

for and on behalf of Ground Engineering Ltd

Date Reported: 29.01.2015

Opinions and interpretations expressed herein are outside the scope of the UKAS Accreditation.
 This report may not be reproduced other than in full without the prior written approval of the issuing Laboratory.

Registered in England & Wales
 Reg Number: 6929574
 Reg Office: Ground Engineering Ltd
 Newark Rd
 Peterborough PE1 5UA

TEST CERTIFICATE

One-Dimensional Consolidation
Properties

(Tested in accordance with BS1377 : Part 5 : 1990)

Newark Road Peterborough

01733 565556 01733 315280

admin@groundengineering.co.uk

Client: Ground Engineering Ltd

Client Address: Newark Road

Peterborough

Cambridgeshire

Postcode: PE1 5UA

Contact: Simon Weatherley

Site Name: 11 Rosslin Hill

Site Address: London NW3

Certificate Number: PL4882-1-25731

Client Reference Number: C13460

Date Sampled: Unknown

Date Received: 16/01/2015

Date Tested: 19/01/2015

Sampling Certificate No: N/A

Certificate of Sampling: N/A

Sampled By: Client

Test Details


Location: BH3
Sample Ref: J1
Sample: Firm brown orange-brown grey slightly
Description: silty CLAY with rare selenite crystals

Particle Density (Mg/m^3): 2.74 Assumed
Mean Lab Temp. ($^{\circ}C$): 22
Variations from Standard: None
Lab Reference: PL4882-1-25
Depth (m): 1.90 m

Specimen Details

	INITIAL	FINAL
Height (mm):	18.69	16.59
Bulk Density (Mg/m^3):	1.94	2.13
Moisture Content (%):	32	28
Dry Density (Mg/m^3):	1.47	1.66
Voids Ratio:	0.855	0.655
Degree of Saturation (%):	101.5	118.9
Diameter (mm):	75.00	N/A
Swelling Pressure (kPa):	135	N/A
Method of time filling used:	Log Time	N/A

Voids Ratio against logarithm of Applied Pressure



Applied Pressure (kPa)	Coefficient of Compressibility (α_v per 24N)	Coefficient of Consolidation (c_v per year)
135	0.28	0.29
200	0.15	0.25
400	0.10	0.24
800	0.06	0.25
1600	0.03	...
800		

Comments

Approved: (x) M Hindrup - Laboratory Manager
Signatory: (x) J.L. Peto - Team Leader

Signed

[Signature]

For and on behalf of Ground Engineering Ltd

Date Reported: 29/01/2015

Opinions and interpretations expressed herein are outside the scope of the UKAS Accreditation. This report may not be reproduced other than in full without the prior written approval of the issuing laboratory.

Registered in England & Wales
Reg Number 6928574
Reg Office: Ground Engineering Ltd
Newark Rd
Peterborough PE1 5UA

TEST CERTIFICATE

**One-Dimensional Consolidation
 Properties**

(Tested in accordance with BS1377 Part 5:1990)

Newark Road Peterborough

Tel: 01733 566565 Fax: 01733 316280

e: admin@groundengineering.co.uk

Client: Ground Engineering Ltd
 Client Address: Newark Road
 Peterborough
 Cambridgeshire
 Postcode: PE1 5UA
 Contact: Simon Weatherley
 Site Name: 11 Rosslyn Hill
 Site Address: London NW3

Certificate Number: PL4882-1-27/731
 Client Reference Number: C13469
 Date Sampled: Unknown
 Date Received: 16.01.2015
 Date Tested: 19.01.2015
 Sampling Certificate No: N/A
 Certificate of Sampling: N/A
 Sampled By: Client


Test Details

Location: BH3
 Sample Ref: U2
 Sample Description: Firm brown/orange-brown grey slightly silty CLAY with occasional selenite crystals
 Particle Density (Mg/m^3): 2.74 Assumed
 Mean Lab Temp. ($^{\circ}C$): 22
 Variations from Standard: None
 Lab Reference: PL4882-1-27
 Depth (m): 3.00 m

Specimen Details

	INITIAL	FINAL
Height (mm)	18.50	16.08
Bulk Density (Mg/m^3)	1.87	2.10
Moisture Content (%)	33	29
Dry Density (Mg/m^3)	1.41	1.62
Voids Ratio	0.943	0.689
Degree of Saturation (%)	94.8	117.3
Diameter (mm)	75.00	N/A
Swelling Pressure (kPa)	88	N/A
Method of time fitting used	Log Time	N/A

Voids Ratio against logarithm of Applied Pressure



Applied Pressure (kPa)	Coefficient of Compressibility (m_v) (at 100 kPa)	Coefficient of Consolidation (c_v) (m/year)
88		
150	0.40	0.23
300	0.23	0.20
600	0.15	0.23
1200	0.09	0.20
600	0.04	—

Comments

Approved: [x] V Hartup - Laboratory Manager
 Signatory: [] L. Patch - Team Leader

Signed:

[Signature]

for and on behalf of Ground Engineering Ltd

Date Reported: 29/01/2015

Opinions and interpretations expressed herein are outside the scope of the UKAS Accreditation.
 This report may not be reproduced other than in full without the prior written approval of the issuing Laboratory.

Registered in England and Wales
 Reg Number 0929574
 Reg Office: Ground Engineering Ltd
 Newark Rd
 Peterborough PE1 5UA

TEST CERTIFICATE

One-Dimensional Consolidation Properties

(Tested in accordance with BS1377 - Part 5:1990)

Newark Road Peterborough

LE1733 56556G t:01733 315280

e: admin@groundengineering.co.uk

Client: Ground Engineering Ltd
Client Address: Newark Road
Peterborough
Cambridgeshire
Postcode: PE1 5JA
Contact: Simon Weatherley
Site Name: 11 Rosslyn Hill
Site Address: London NW3

Certificate Number: PL4882-1-201731
Client Reference Number: C13459
Date Sampled: Unknown
Date Received: 16.01.2015
Date Tested: 19.01.2015
Sampling Certificate No: N/A
Certificate of Sampling: N/A
Sampled By: Client


Test Details

Location: BH3
Sample Ref: U3
Sample Description: Firm brown orange-brown grey slightly silty CLAY with occasional selenite crystals
Particle Density (Mg/m^3): 2.74 Assumed
Mean Lab Temp. ($^{\circ}C$): 22
Variations from Standard: None
Lab Reference: PL4882-1-29
Depth (m): 4.00 m

Specimen Details

	INITIAL	FINAL
Height (mm):	18.93	16.84
Bulk Density (Mg/m^3):	1.86	2.08
Moisture Content (%):	31	50
Dry Density (Mg/m^3):	1.42	1.60
Void Ratio:	0.929	0.715
Degree of Saturation (%):	91.5	115.0
Diameter (mm):	74.98	N/A
Swelling Pressure (kPa):	48	N/A
Method of time fitting used:	Log Time	N/A

Voids Ratio against logarithm of Applied Pressure



Applied Pressure (kPa)	Coefficient of Compressibility (m_v , unitless)	Coefficient of Consolidation (c_v , min/year)
48	0.41	0.52
100	0.27	0.55
200	0.18	0.51
400	0.12	0.34
800	0.05	---
400		

Comments:

Approved: [x] V Hartup - Laboratory Manager
Signatory: [x] L Patch - Team Leader

Signed:


[Signature]

for and on behalf of Ground Engineering Ltd

Date Reported: 29/01/2015


Opinions and interpretations expressed herein are outside the scope of the UKAS Accreditation. This report may not be reproduced other than in full without the prior written approval of the issuing laboratory.

Registered in England/Wales
Reg Number: 0909574
Reg Office: Ground Engineering Ltd
Newark Rd
Peterborough: PE1 5JA



Moisture Content % vs Depth below ground level (m).

SITE		11 ROSSLYN HILL, HAMPSTEAD, LONDON NW3	
CLIENT		ANDREW & ELIZABETH JEFFREYS	Contract Number 13469
GROUND ENGINEERING		Date 11/03/15	Figure 1
T I V I T L O		www.groundengineering.co.uk	



Apparent Cohesion (kPa) vs Depth below ground level (m).

SITE 11 ROSSLYN HILL, HAMPSTEAD, LONDON NW3

CLIENT ANDREW & ELIZABETH JEFFREYS

Contract Number 13489

GROUND ENGINEERING

Technical Services

Date 11/03/15


Figure 2

LIMITED

www.groundengineering.co.uk

NORTH

SOUTH



KEY TO LEGENDS

- MADE GROUND
- MADE GROUND
- LONDON CLAY
- Groundwater Encountered
- Groundwater Rise
- Level on Completion
- Level Casing Withdrawn
- Standpipe Level

SITE 11 ROSSLIN HILL, HAMPSTEAD, LONDON N19

Contract No. 13465

CLIENT ANDREW & ELIZABETH JEFFREYS

Soil Profile

Vertical Scale 1:100

GROUND ENGINEERING LIMITED, PETERBOROUGH Tel 01733 566555

Date 11/03/15

Fig No. 1

Appendix 6

Chemical Test Results



Final Report

Report Number: 15-00688 Issue-1

Initial Date of Issue: 19-Jan-15

Client: Ground Engineering Limited

Client Address: Newark Road
Peterborough
Cambridgeshire
PE1 5UA

Contact(s): Simon Weatherley

Project: SW/C13469 11 Rosslyn Hill, Hampstead

Quotation No.:

Date Received: 15-Jan-15

Order No.: SW/C13469

Date Instructed: 15-Jan-15

No. of Samples: 10

Results Due: 19-Jan-15

Turnaround:
(Weekdays) 3

Date Approved: 19-Jan-15

Approved By:

Details: Darrell Hall, Laboratory Director



Results Summary - Soil

Project: SW/C13489 11 Rosalyn Hill, Hampstead

[illegible]



Results Summary - Water

Project: SW/C13469 11 Rosalyn Hill, Hartpstead

Client	Chemical Job No.	Job Date
Quotation No.: _____	Chemical Sample ID.: _____	8/17/2024
Order No. SW-2024-0123	Client Sample Ref: _____	W1
_____	Client Sample ID.: _____	W2
_____	Sample Type: WATER	WATER
_____	Top Depth (m): 0.50	0.50
_____	Bottom Depth (m): _____	_____
Date In Hand	Accord.	\$ Cost
pH	U	10.00
Boron (Dissolved)	U	1450 µg/L
Sulfate	U	1200 mg/L
Cyanide (Free)	U	1300 mg/L
Cyanide (Total)	U	1300 mg/L
Sulfide	U	1300 mg/L
Arsenic (Dissolved)	L	1450 µg/L
Chromium (Dissolved)	L	1450 µg/L
Chromium (Dissolved)	L	1450 µg/L
Copper (Dissolved)	L	1450 µg/L
Manganese (Dissolved)	L	1450 µg/L
Nickel (Dissolved)	L	1450 µg/L
Lead (Dissolved)	L	1450 µg/L
Mercury (Dissolved)	L	1450 µg/L
Zinc (Dissolved)	L	1450 µg/L
Acetophenone	N	1700 µg/L
Acetylcholine	N	1700 µg/L
Adipic acid	N	1700 µg/L
Benzo(a)anthracene	N	1700 µg/L
Benzo(b)fluoranthene	N	1700 µg/L
Benzo(k)fluoranthene	N	1700 µg/L
Benzo(e)pyrene	N	1700 µg/L
Benzo(g,h,i)perylene	N	1700 µg/L
Benzo(j,k,l,m,n,o,p,q,r,s,t,u,v,w,x,y,z)	N	1700 µg/L
Chrysene	N	1700 µg/L
Dibenz(a,h)anthracene	N	1700 µg/L
Dibenz(a,j,k,l,m,n,o,p,q,r,s,t,u,v,w,x,y,z)	N	1700 µg/L
Fluorene	N	1700 µg/L
Indeno(1,2,3-cd)pyrene	N	1700 µg/L
Naphthalene	N	1700 µg/L
Phenanthrene	N	1700 µg/L
Perylene	N	1700 µg/L
Total PAHs	N	1930 µg/L
Total Phenols	N	1930 µg/L

Project: SW/C13489 11 Rosslyn Hill, Hampstead

Client: Ground Engineering Limited	Chemist Job No.:	15-00858
Collection No.	Chemist Sample ID.:	80-77
Order No: SW/C13489	Client Sample Ref.:	W1
	Client Sample ID.:	W55
	Sample Type:	WATER
	Tap Depth (m):	0.80
	Bottle Description:	
	Date Sampled:	07-Jun-15
Determinand	Accred.	SOP
Hardness	U	14.15 mg/l
		1500

Report Information

Key

-
- U UKAS accredited
 - M MCERTS and UKAS accredited
 - N Unaccredited
 - S This analysis has been subcontracted to a UKAS accredited laboratory that is accredited for this analysis
 - SN This analysis has been subcontracted to a UKAS accredited laboratory that is not accredited for this analysis
 - T This analysis has been subcontracted to an unaccredited laboratory
 - IS Insufficient Sample
 - US Unsuitable sample
 - NE not evaluated
 - < "less than"
 - > "greater than"

Comments or interpretations are beyond the scope of UKAS accreditation

The results relate only to the items tested

Uncertainty of measurement for the determinands tested are available upon request

None of the results in this report have been recovery corrected

All results are expressed on a dry weight basis

The following tests were analysed on samples as received and the results subsequently corrected to a dry weight basis TPH, BTEX, VOCs, SVOCs, PCBs, Phenols

For all other tests the samples were dried at < 37 °C prior to analysis

All Asbestos testing is performed at our Coventry laboratory

Issue numbers are sequential starting with 1 all subsequent reports are incremented by 1

Sample Deviation Codes

-
- A - Date of sampling not supplied
 - B - Sample age exceeds stability time (sampling to extraction)
 - C - Sample not received in appropriate containers
 - D - Broken Container

Sample Retention and Disposal

All soil samples will be retained for a period of 60 days from the date of receipt

All water samples will be retained for 14 days from the date of receipt

Charges may apply to extended sample storage

If you require extended retention of samples please email your requirements to:
customer.services@chemtest.co.uk

Appendix 7

Classification of Aggressive Chemical Environment for Buried Concrete

TABLE C1 – AGGRESSIVE CHEMICAL ENVIRONMENT FOR CONCRETE

(ACEC) CLASSIFICATION FOR NATURAL GROUND LOCATIONS^a

Table C1. Aggressive Chemical Environment for Concrete (ACEC) Classification for Natural Ground Locations ^a						
Sulfate Design Sulfate Class for location	2:1 water/soil extract ^b	Groundwater	Total potential sulfate ^c	Groundwater		ACEC Class for location
1	2 [SO ₄ mg/l]	3 [SO ₄ mg/l]	4 [SO ₄ %]	5 [pH]	6 [pH]	7
DS-1	< 500	< 400	< 0.24	> 10	> 9.5 ^d	AC-1.6
					> 9.0 ^d	AC-1.7
DS-2	500-1500	400-1400	0.24-0.6	> 10	> 9.0-9.5	AC-2.1
					> 8.5	AC-2.2
				9.0-9.5		AC-2.3
DS-3	1500-5000	1400-5000	0.7-1.2	> 9.5	> 8.5-9.5	AC-3.1
					> 8.0	AC-3.2
				9.5-10		AC-3.3
DS-4	5000-50000	5000-50000	1.3-7.4	> 9.5	> 7.5-9.5	AC-4.1
					> 7.0	AC-4.2
				9.5-10		AC-4.3
DS-5	> 50000	> 50000	> 2.4	> 9.5	> 2.5-9.5	AC-5.1
				9.5-10	> 2.5	AC-5.2


Notes:

- a. All ACEC Classifications are based on compressed air and water-saturated concrete in contact with groundwater for a minimum of 28 days at 23°C (73°F).
- b. The 2:1 water/soil extract is based on water extracted from the soil using distilled water for leaching and analyzed by test 117.
- c. Aggressive locations above 0.6% are expected to sulfate concrete and cause the greatest deterioration of concrete exposed to sulfate attack.
- d. Locations with water that is collected, aggressive to concrete having pH < 9.0, pH up to 9.0, and locations with water that is collected with a pH < 9.0, pH up to 9.0, are classified as AC-5.1 and AC-5.2.

Explanation of suffix symbols to ACEC Class

- Sulfate based on potential exposure (see Table C1.1.1.1).
- Concrete placed in a location that is not likely to be exposed to sulfate attack for a minimum of 28 days at 23°C (73°F) is classified as AC-5.1 or AC-5.2.

Appendix F Existing groundwater flows



1. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL RELEVANT ARCHITECTS AND ENGINEERS DRAWINGS AND THE SPECIFICATION.

KEY.

- CONTOUR IN TOP OF LONDON CLAY
- GROUND WATER FLOWS.

— 24/3/15 ISSUED FOR PLANNING FU

NO.11 ROSSLYN HILL,
NW3

EXISTING GROUND WATER FLOWS
PLAN

drawn
RWA

date
MARCH 15

checked
FU

scale (original)
1:200

Alan Baxter

75 Cowcross Street London EC1M 6EL
tel 020 7250 1555
email aba@alanbaxter.co.uk

www.alanbaxter.co.uk


fig. no.

1693/01/SK03

rev.

EXISTING GROUND WATER FLOWS
& CONTOUR MAP OF TOP OF CLAY

Appendix G Proposed groundwater flows



PROPOSED
GROUND WATER FLOWS
AS EXISTING. TOP OF
BASEMENT SET AT
LEVEL OF THE CLAY.
REFER TO DRAWING
1693/01/SK03 FOR DETAILS

EXISTING GROUND WATER FLOWS
& CONTOUR MAP OF TOP OF CLAY

DINING ROOM TO BE
FOUNDED ON PILES
& SLAB SET ABOVE
GROUND TO ALLOW
GROUND WATER FLOWS
UNDER.

1000

1. THIS DRAWING IS TO BE READ IN
CONJUNCTION WITH ALL RELEVANT
ARCHITECTS AND ENGINEERS DRAWINGS
AND THE SPECIFICATION.

KEY.

- CONTOUR IN TOP OF LONDON CLAY
- GROUND WATER FLOWS.
- PROPOSED DEVELOPMENT

24/3/15 ISSUED FOR PLANNING AD

NO. 11 ROSSLYN HILL,
NW3

PROPOSED GROUND WATER FLOWS
PLAN

drawn
RWa
MARCH 15

checked
FJ
scale (original - A3)
1:200

Alan Baxter

75 Cowcross Street London EC1M 6EL
tel 020 7250 1555
email ab@alanbaxter.co.uk

www.alanbaxter.co.uk

fig. no.
1693/01/SK04

REV.

Appendix H Proposed structure drawings

GROUND BEAMS SUPPORTED ON INTERNAL PILES TO SUPPORT POOL TANK

A-A 105

B-B 106

R.C. COLUMN

CONTIGUOUS PILED WALL 600 Ø RC PILES TO PERIMETER OF EXCAVATION.

CONTIGUOUS PILED WALL / 600mm Ø RC PILES TO CREATE SECOND LEVEL "BASEMENT"

RC LINING WALL

200mm RC THICK WALL

SECANT PILED WALL 600 Ø RC PILES TO PERIMETER OF EXCAVATION.

RC LINING WALL WITHIN NEW LIGHTWELL.

BOUNDARY WALL ABOVE

IN-SITU STAIRS

ROOT PROTECTION BONES

PILED FOUNDATIONS FOR EXTENSIONS

SITE BOUNDARY SHOWING THIS ---

R.C. COLUMNS TO SUPPORT R.C. SLAB ABOVE AT GROUND FLOOR LEVEL

MASS CONCRETE UNDERPINNING TO EXISTING FOUNDATIONS


CONTIGUOUS PILED WALL 450 Ø RC PILES TO PERIMETER OF EXCAVATION.

NEW PROFILED RC LINING WALL WITHIN LIGHTWELL

CENTRAL LINE OF PILES TO SUPPORT BASEMENT SLAB.

FOUNDATION TO EXISTING ADJACENT PROPERTIES NOT TO BE DISTURBED

fig. no. 1693/01/100	rev. A
--------------------------------	------------------



notes
1. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL RELEVANT ARCHITECT'S AND ENGINEER'S DRAWINGS AND THE SPECIFICATION.

C	25.3.15	ISSUED FOR PLANNING, NOTES ADDED.	PN
B	24.3.15	ISSUED FOR INFORMATION.	PN
A	17.3.15	ISSUED FOR COMMENT, OPENINGS ADDED.	PN
-	17.3.15	ISSUED FOR COMMENT.	PN

11 ROSSLYN HILL,
N16 3



PROPOSED STRUCTURE
GROUND FLOOR PLAN

drawn RG	checked FN
date MAR'15	scale (A3) 1:100

Alan Baxter

75 Cowcross Street London EC1M 6EL
tel 020 7250 1555
email aba@alanbaxter.co.uk
www.alanbaxter.co.uk

015.00 1693/01/101	rev. C
------------------------------	------------------



A	25.9.15	ISSUED FOR PERMANENT	RG
-	2/3/15	ISSUED FOR COMMENT	RG

11 ROSSLYN HILL,
NW3



PROPOSED STRUCTURE
SECTION A-A

Drawn RG	Checked FX
Date MAR'15	Scale (original - A1) 1:100

Alan Baxter

75 Cowcross Street London EC1M 6EL
tel 020 7250 1555
email ab@alanbaxter.co.uk
www.alanbaxter.co.uk

dep. no. 1693/01/105	rev. A
--------------------------------	------------------



B	26/3/15	ISSUED FOR PLANNING	EW
A	27/3/15	ISSUED FOR PLANNING	FW
-	19/3/15	ISSUED FOR COMMENT	FW

11 ROSSLYN HILL,
NW3

PROPOSED STRUCTURE
SECTION B-B


Drawn RG	Checked FW
Date MAR'15	Scale (overall - All) 1:100

Alan Baxter

75 Cowcross Street London EC1M 6EL
tel 020 7250 1555
email aba@alanbaxter.co.uk
www.alanbaxter.co.uk


Dwg. No. 1693/01/106	Rev. B
-------------------------	-----------

Appendix I Sequence of construction drawings




OCCUPANTS OF THE HOUSE WILL NOT BE IN RESIDENCE DURING THE WORKS.

① SITE SET UP




② PILING & UNDERPINNING

NOTE: THIS STEP ③ SHOWS A TOP-DOWN SEQUENCE FOR A SMALL SECTION OF THE EAST BASEMENT WHICH INVOLVES FORMING THE ROOF SLAB EARLY IN THE CONSTRUCTION STAGE TO MAINTAIN CONSTRUCTION ACCESS ONTO SITE. ALTERNATIVELY, A BOTTOM-UP SEQUENCE CAN BE ADOPTED HERE. THIS MEANS THAT A TEMPORARY DECK WOULD BE NEEDED TO MAINTAIN THE CONSTRUCTION ACCESS INTO SITE.



③ FORM AREA OF ROOF SLAB



④ EXCAVATION

- Notes
- THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL RELEVANT ARCHITECTS AND ENGINEERS DRAWINGS AND THE SPECIFICATION.
 - THE CONTRACTOR SHALL ENSURE THAT THE STABILITY OF THE BUILDING AND ADJOINING PREMISES IS MAINTAINED AT ALL STAGES OF CONSTRUCTION. HE SHALL DESIGN, INSTALL AND MAINTAIN ALL NECESSARY TEMPORARY WORKS AND PROGRAMME THE WORKS ACCORDINGLY.
 - THIS DRAWING SHOWS THE SEQUENCE OF CONSTRUCTION ASSUMED IN FORMULATING THE STRUCTURAL DESIGN. THE CONTRACTOR SHALL PREPARE HIS OWN PROPOSALS FOR SEQUENCE AND METHODOLOGY OF CONSTRUCTION, INCLUDING ALL TEMPORARY WORKS, FOR WHICH HE SHALL REMAIN ENTIRELY RESPONSIBLE. THESE PROPOSALS SHALL BE SUBMITTED TO THE CA PRIOR TO COMMENCEMENT OF WORK ON SITE.
 - WHERE THIS DRAWING SHOWS ITEMS OF STRUCTURE, EQUIPMENT OR PLANT WHICH DO NOT FORM PART OF THE PERMANENT STRUCTURE, THESE ARE ITEMS OF "TEMPORARY WORKS" OR "THINGS NOT FOR INCORPORATION BY THE WORKS". SUCH ITEMS ARE SHOWN PURELY TO INDICATE A POSSIBLE MEANS OF CONSTRUCTING SOME PARTS OF THE STRUCTURE AND MAKE NO REPRESENTATION AS TO THE AMOUNT AND/OR EXTENT OF SUCH WORKS OR ITEMS, NOR OF THE EQUIPMENT, PLANT OR MATERIALS NEEDED TO INSTALL AND MAINTAIN THEM.

C	30.3.15	STEP 3 ROOF SLAB UPDATED	FN
B	26.3.15	ISSUED FOR PLANNING. NOTES ADDED.	RM
A	25.3.15	ISSUED FOR PLANNING. NOTE ADDED.	FN
-	24/3/15	ISSUED FOR PLANNING	FN

NO. 11 ROSSLYN HILL
NW 3.


ASSUMED SEQUENCE OF
CONSTRUCTION.
SHEET 1 OF 2

REV. 15
DATE 15/03/15
SCALE 1:100 PLANS
1:100 SECTIONS


Alan Baxter

75 Cowcross Street, London EC1M 6EL
Tel 020 7250 1555
email aba@alanbaxter.co.uk
www.alanbaxter.co.uk


1693/01/SK05




⑤ EXCAVATION & PROPPING.



⑥ CONSTRUCTION OF BASEMENT SLAB.



⑦ EXCAVATE & CONSTRUCT POOL & DOUBLE BASEMENT.



⑧ CONSTRUCTION OF TOP SLAB.

1). REFER TO DRAWING 1693/01/SK05 FOR GENERAL NOTES.

A	2603.15	ISSUED FOR PLANNING NOTES ADDED	FW
A	2603.15	ISSUED FOR PLANNING	FW

No. 11 ROSLYN HILL
NW3

ASSUMED SEQUENCE OF CONSTRUCTIONS
SHEET 2 OF 2.

drawn: RHA
date: MARCH 15

checked: FWJ
scale (overall: All)
PLAN: 1:200
SECTION: 1:100

Alan Baxter

75 Cowcross Street London EC1M 6EL
tel 020 7250 1555
email aba@alanbaxter.co.uk
www.alanbaxter.co.uk

1693/01/SK06


A

Appendix J Calculations

DESIGN OF A BASEMENT RETAINING WALL AT PLANNING STAGE TO BS8002.

PART OF THE RETAINING WALL STRUCTURE TO THE BASEMENT WILL BE AN RC BORED CONTIGUOUS PILED WALL WITH A LINING WALL, AND PART AN RC BORED SEPARATE PILED WALL. REFER TO DRAWING 1693/D1/100 FOR LOCATIONS.

LOADING.



SOIL PROPERTIES - BASED ON INFORMATION IN THE SI REPORT


$\gamma_s = 19 \text{ kN/m}^3$ $\gamma_d = 15 \text{ kN/m}^3$

$k_0 = \frac{1 - \sin \phi}{1 + \sin \phi}$ where $\phi = 18^\circ$

≈ 1.5 ARE NORMALLY CONSOLIDATED CLAY

$k_a = \frac{1 - \sin \phi}{1 + \sin \phi} = 0.52$ USE k_a k_0 OVER CONSEQUENTIVE


MODEL BASED ON RETAINING WALL SPANNING BETWEEN SLABS
AND ACTING AS A SIMPLY SUPPORTED BEAM.



PRESSURE ACTING
AT BASE OF WALL.

$= 10 \times 6.7$ $= 15 \times 1 \times 0.6 + 0.6 \times (18 - 15) \times 7 + 10 \times 0.6$
 $= 47 \text{ kN/m}$ $= 45 \text{ kN/m}$ $= 6 \text{ kN/m}$

QSE RESULTS.



MAX BENDING MOMENT = kNm/m

MAX SHEAR FORCE = 1.5 kN/m

FB = kN/m. FORCE IN BASEMENT SLAB

Fg = kN/m FORCE IN TOP SLAB

HAND CALCULATION CHECK.

MODEL TO LOADS AS A UDL OVER THE WHOLE LENGTH

$$\text{AVERAGE UDL} = \left(\frac{0 + 45}{2} \right) + \left(\frac{0 + 47}{2} \right) + 6 = 56.5 \text{ kN/m}$$

$$M = \frac{wL^2}{8} = \frac{56.5 \times 4.7^2}{8} = 156 \text{ kNm} \checkmark \therefore \text{ok}$$

DESIGN PILES FOR A MOMENT OF 160 kNm/m.

Date	14/04/15	Job no.	1693/01	Sheet	A.4
Engineer	R.W.				
Checked by	OF				
Project	No. 11 Rosslyn Hill				

PILE DESIGN TO BS8110


DESIGN PILES TO RESIST AN UNFACTORED MOMENT OF
160 kNm.

CHARACTERISTIC ANGLE OF FRICTION, $\phi' = 26^\circ$ (SI REPORT)

USE A FACTOR OF SAFETY OF 1.6 (CONSERVATIVE AS CAN
USE 1.2 FOR HYDROSTATIC PRESSURES)

DESIGN MOMENT = $160 \times 1.6 = 192 \text{ kNm/m}$

TRY 600 ϕ PILE WITH 100mm GAPS BETWEEN.



DESIGN MOMENT/PILE = $192 \times \frac{700}{1000} = 134 \text{ kNm}$

Project Spreadsheets to BS 8110

Client Advisory Group

Location Columns at A1, A2 etc

COLUMN CHART FOR CIRCULAR COLUMNS TO BS 8110:2005

Originated from 'RCC54.xls' v3.1 on CD

© 2006 TCC



The Concrete Centre

The Concrete Centre

Made by	Date	Page
RMW	19-Mar-15	124
Checked	Revision	Job No
chg	-	R68


MATERIALS

fcu	<u>35</u>	N/mm ²	ym	<u>1.15</u>	steel	Cover	<u>87</u>	mm
fy	<u>500</u>	N/mm ²	ym	<u>1.5</u>	concrete	h agg	<u>20</u>	mm
steel class	<u>A</u>							
SECTION	<u>600</u>	mm	with	<u>6</u>	bars			

BAR ARRANGEMENTS

Type	Bar Ø	Asc %	Link Ø	Bar c/c	Nbal (kN)	Nuz (kN)	Checks
H	40	2.67	10	191.6	1457	7581	ok
H	32	1.71	8	197.9	1638	6443	ok
H	25	1.04	8	201.6	1744	5655	ok
H	20	0.67	6	206.3	1805	5210	ok
H	16	0.43	6	208.4	2037	4926	ok
H	12	0.00	6	210.5			ok

N:M INTERACTION CHART for 600 diameter column, grade C35, 87 mm cover and 6 bars



KEY

6H40

6H32

6H25

6H20

6H16

6H12

LOADCASES


Load case	N (kN)	M (kNm)	
<u>1</u>		<u>192</u>	<u>6 H25</u>
<u>2</u>			No Fit
<u>3</u>			No Fit

Load case	N (kN)	M (kNm)	
<u>4</u>			No Fit
<u>5</u>			No Fit
<u>6</u>			No Fit

Provide 6H25

Date	MARCH 15	Job no.	1693/01	Sheet	AG
Engineer	RWA				
Checked by	DE				
Project	No. 11 Roslyn Hill				

RC WALL DESIGN TO BS 8110



DESIGN MOMENT 1m LENGTH OF WALL = 80.4(k) kNm/m

TRY 275mm THICK WALL.

$$d = 275 - \underset{\text{INSIDE COVER}}{25} - 12 - \frac{20}{2} = 228 \text{ mm}$$

$$k = \frac{m}{f_{cu} b d^2} = \frac{80.4 \times 10^6}{33 \times 1000 \times 228^2} = 0.043 \text{ (or } 0.052 \text{ (A))}$$

$$z = 0.95d = 216 \text{ mm}$$

$$A_{sreqd} = \frac{m}{0.87 f_y z} = \frac{80.4 \times 10^6}{0.87 \times 500 \times 216} = 852 \text{ mm}^2/\text{m}$$

PROVIDE

$$B12 @ 200 \text{ c/c} = 1005 \text{ mm}^2$$

DEFLECTION:

$$\frac{SPAN}{d} = \frac{4700}{228} = 20 \rightarrow \text{OK}$$

SHEAR

$$V = 60 \text{ kN/m UNFACTORED} \approx 60 \times 1.6 = 96 \text{ kN/m FACTORED CONSERVATION}$$

$$v = \frac{V}{bd} = \frac{62 \times 10^3}{1000 \times 228} = 0.27 \text{ N/mm}^2$$

$$\frac{100 A_s}{bd} = \frac{100 \times 2293}{1000 \times 228} \approx 1$$

Alan Baxter

75 Cowcross Street
London EC1M 6EL
t: 020 7250 1555
f: 020 7250 3522
email: ab@alanbaxter.co.uk
www.alanbaxter.co.uk

Date	11/2/15	Job no.	1693/01	Sheet	A.7
Engineer	R. Wain				
Checked by	AS				
Project	No. 11 Rosslyn Hill				

FROM TABLE 3.8 (BS8110) $\sqrt{c} \approx 0.4 \text{ N/mm}^2$

NO SHEAR REINFORCEMENT REQD.


Date	MARCH 16	Job no.	1693/81	Sheet	A.8
Engineer	KLW				
Checked by	OK				
Project	No. 11 ROSSELYN HILL				

BASEMENT SLAB DESIGN TO BS8110.

MODEL AS SIMPLY SUPPORTED SPANNING BETWEEN BASEMENT WALLS

LOAD CASE

- SURCHARGE = ALLOW FOR FIRE TENDER
- HYDROSTATIC FORCES - ACCIDENTAL LOAD CASE (1m BELOW GL)
- SOIL PRESSURE.
- Dead weight



$$w = \underset{a}{10 \text{ kN/m}} + \underset{b}{(0)} + \underset{c}{(18 \times 1.25)} + \underset{d}{(0.8 \times 21)} + \underset{e}{(0.5)} = 47.4 \text{ kN/m}^2 \text{ of } \underset{f}{71 \text{ kN/m}^2 \text{ of}}$$

NOTE TOP OF
BASEMENT SET AT 1m BELOW
GL.

e = ceiling finishes
d = concrete & ceiling screed

DESIGN MOMENT FOR A m STRIP

$$M = \frac{wL^2}{8} = 568 \text{ kNm}$$

$$\delta = 425 - 25 - \underset{\text{cover}}{\frac{20}{e}} = 390 \text{ mm}$$

$$f_{cu} = 40 \text{ N/mm}^2$$

Date	17/11/15	Job no.	1693/01	Sheet	A.9
Engineer	RWA				
Checked by	OE				
Project	No. 11 Rosslyn Hill				

$$I_c = \frac{m}{f_{cu} b d^2} = \frac{568 \times 10^6}{1401 \times 1000 \times 390^2} = 0.09$$

$$z = 0.95d = 370.5 \text{ mm}$$

$$A_s = \frac{m}{0.87 f_y z} = \frac{568 \times 10^6}{0.87 \times 500 \times 370.5} = 3240 \text{ mm}^2$$

Provide B20s @ 200 c/c $\rightarrow 1577 \text{ mm}^2/\text{m}$
 B25s @ 200 c/c $\rightarrow 2454 \text{ mm}^2/\text{m}$
4031 mm}^2/\text{m}

SHEAR

$$V = \frac{w_c}{2} = 284 \text{ kN}$$

$$100 \times A_s / b d = \frac{100 \times 4031}{1000 \times 390} = 1.0$$

$$V = \frac{V}{b d} = \frac{284 \times 10^3}{1000 \times 390} = 0.727 \text{ N/mm}^2$$

$$V_c = 0.62 \quad [\text{TABLE 3.8}]$$

$$V > V_c \therefore \text{OK}$$

GROUND MOVEMENT PREDICTION IN ACCORDANCE WITH CIRIA C580 TO ACCOMPANY THE DIA FOR THE PROPOSED TREATMENT AT NO. 11 ROSLYN HILL, HAINSTED, LONDON

* See below GROUND CONDITION = LONDON CLAY


ESTIMATE MOVEMENTS USING EMPIRICAL RELATIONSHIP AS PER
CIRIA C580 - EMBEDDED RETAINING WALLS.

MOVEMENT DUE TO THE PILE INSTALLATION

(BASED ON FIGURE 2.8 - CIRIA C580)
ATTACHED ON FOLLOWING PAGE

WALL TYPE - CONTIGUOUS TIED WALL

PILE DEPTH $\approx 18m$



DISTANCE FROM FACE OF WALL (m)	MOVEMENT DUE TO PILE INSTALLATION	
	HORIZONTAL (mm)	VERTICAL (mm)
0	7.2	7.2
1	7.2	7.02
5	5.4	6.3
10	3.6	3.4
15	2.7	3.0

↑ THESE DISTANCES WILL ENABLE A CURVE PLOT TO
BE ESTABLISHED TO DETERMINE THE GROUND MOVEMENT
OF THE SURROUNDING BUILDINGS. BUILDINGS BEYOND
30m NOT CONSIDERED. SEE SHEET 3

Alan Baxter

75 Cowcross Street
London EC1M 6EL
tel: 020 7250 1555
fax: 020 7250 3022
email: aba@alanbaxter.co.uk
www.alanbaxter.co.uk

Date	MAR 15	Job no.	1692/01	Sheet	B.2
Engineer	RWA				
Checked by	JH				
Project					
No 11 Rosslyn Hill					

Bla





Figure 2.8 Ground surface movements due to bored pile wall installation in stiff clay

Date	16/03/01	Job no.		Sheet
Engineer	R. L. W.		16/03/01	B. 3
Checked by	J. H.			
Project	No 11 Rossmore Hill			

DISTANCE BEHIND WALL TO NEGLIGIBLE HORIZONTAL MOVEMENT
FROM TABLE 2.2 ATTACHED

$$= 1.5 \times d = 1.5 \times 18 = 27 \text{ m}$$

DISTANCE BEHIND WALL TO NEGLIGIBLE VERTICAL MOVEMENT

$$= 2 \times d = 2 \times 18 = 36 \text{ m. (NOTE BUILDINGS @ 5m, 15m AWAY
NEXT CLOSEST + 30m)}$$

THE BASEMENT WALL WILL BE FORMED IN PART BY RC CONTIG
PILES WITH A LINING WALL & IN PART BY RC SECANT PILES
WITH A LINING WALL. GROUND MOVEMENTS HAVE BE CONSIDERED
LOOKING AT THE CONTIG PILED WALL AS IT IS MORE CONSERVATIVE.

Table 2.2 Ground surface movements due to bored pile and diaphragm wall installation in stiff clay

Wall type	Horizontal movements		Vertical movements	
	Surface movement at wall (per cent of wall depth)	Distance behind wall to negligible movement (multiple of wall depth)	Surface movement at wall (per cent of wall depth)	Distance behind wall to negligible movement (multiple of wall depth)
Bored piles				
Contiguous	0.04	1.5	0.04	2
Secant	0.08	1.5	0.05	2
Diaphragm walls				
Planar	0.05	1.5	0.05	1.5
Counterfort	0.1	1.5	0.05	1.5

Notes

1. Maximum surface movement occurs close to the wall and is calculated as a percentage of the pile depth/diaphragm wall trench depth, as appropriate.
2. Extent of movement is calculated non-dimensionally by dividing by the pile depth/diaphragm wall trench depth, as appropriate

From Figure 2.11 (Using High Stiffness Values)

Distance from face of wall (m)	Movement due to excavation	
	Horizontal (mm)	Vertical (mm)
0	8.25	1.65
1	7.7	3.3
5	6.05	4.6
10	4.95	2.2
15	2.75	1.65

TOTAL GROUND SURFACE MOVEMENTS DUE TO EXCAVATION:

COMBINE MOVEMENTS DUE TO WALL INSTALLATION & EXCAVATION

Distance from face of wall	TOTAL MOVEMENT	
	Horizontal (mm)	Vertical (mm)
0	15.5	8.85
1	14.7	10.3
5	11.5	10.7
10	8.6	7.6
15	5.5	5.25

Date	16/01/15	Job no. 1693/01	Sheet
Engineer	RW		B. 5
Checked by	JH		
Project Nell Rosslyn Hill			




Figure 2.11 Ground surface movements due to excavation in front of wall in stiff clay

Date	MARCH '15	Job no.	1693/01	Sheet	B, 6
Engineer	RWA	Checked by	JH		
Project	No 11 Roslyn Hill				

ESTIMATE OF GROUND SURFACE MOVEMENTS DUE TO EXCAVATION

FROM TABLE 23, THE BASEMENT WILL BE GENERALLY OF A HIGH SUPPORT STIFFNESS. TEMPORARY PROPS WILL BE INSTALLED BEFORE THE PERMANENT PROPS AT HIGH LEVELS.

DEPTH OF EXCAVATION = 5.5m

FROM TABLE 24: ATTACHED

DISTANCE BEHIND WALL TO NEGLIGIBLE HORIZONTAL MOVEMENT
= $4 \times 5.5 = 22 \text{ m}$

DISTANCE BEHIND WALL TO NEGLIGIBLE VERTICAL MOVEMENT
= $3.5 \times 5.5 = 19.25 \text{ m}$

NOTE THE INFORMATION GIVEN IN TABLE 24 IS DERIVED FROM EMPIRICAL EVIDENCE FROM EXCAVATIONS 8-31m DEEP. GIVEN THE PROPOSED BASEMENT IS ONLY 5.5m DEEP THE CALCULATION IS CONSERVATIVE.

Table 2.3 Support stiffness categories (Carder, 1995)

Support stiffness	Description/examples
High	Top-down construction, temporary props installed before permanent props at high level
Moderate	Temporary props of high stiffness installed before permanent props at low level
Low	Cantilever walls, temporary props of low stiffness or temporary props installed at low level

Table 2.4 summarises the magnitude and extent of the monitored ground surface movements due to excavation in front of bored pile, diaphragm and sheet pile walls wholly embedded in stiff clay under conditions of good workmanship. The case history data, upon which Table 2.4 is based, relate to excavations that range in depth from 8 m to 31 m, have a factor of safety against base heave in excess of 3 and where walls are wholly embedded in stiff clay.

Table 2.4 Ground surface movements due to excavation in front of bored pile, diaphragm wall and sheet pile walls wholly embedded in stiff clays

Movement type	High support stiffness (high propped wall, top-down construction)		Low support stiffness (cantilever or low-stiffness temporary props or temporary props installed at low level)	
	Surface movement at wall (per cent of max excavation depth)	Distance behind wall to negligible movement (multiple of max excavation depth)	Surface movement at wall (per cent of max excavation depth)	Distance behind wall to negligible movement (multiple of max excavation depth)
Horizontal	0.15	4	0.4	4
Vertical	0.1	3.5	0.35	4

Notes

1. Maximum surface movement occurs close to the wall and is expressed as a percentage of maximum excavation depth in front of the wall.
2. Extent of movement is calculated non-dimensionally by dividing by maximum excavation depth.
3. Movements exclude those arising from wall installation effects.
4. Movements correspond to good workmanship and to walls wholly embedded in stiff clays retaining stiff clays or competent soils.
5. Movements will be greater where soft soils are encountered at formation level; see Appendix 2.

Date MAY 15	Job no. 1693/01	Sheet B, 8
Engineer R. Wilson		
Checked by JL		
Project No. 11 Rosslyn Hill		

BUILDING DAMAGE ASSESSMENT

FOLLOW METHOD SET OUT IN THE FLOW CHART IN
FIGURE 2.17.

DAMAGE TO ADJACENT BUILDINGS WILL BE DETERMINED BY
CALCULATING THE STRAINS THE BUILDINGS WILL EXPERIENCE
AS A RESULT OF THE MOVEMENTS. THIS IS IN ACCORDANCE
WITH BOX 2.5 & 7.19 IN CIRIA C580.

THE FOLLOWING STRUCTURES HAVE BEEN IDENTIFIED AS BEING
WITHIN THE INFLUENCE ZONES. THE DIMENSIONS (LENGTH &
HEIGHT) ARE SHOWN, AS SET OUT IN BOX 2.5.

CONTOUR

1m a) No 11 Rosslyn Hill

b) LYNDHURST HALL


5m c) GARAGES OFF HALLESTOCK HILL

10m N/A


15m N/A

L (m)	H (m)	Y/H
17	13	1.3
55	22	2.5
12	3	4


Date	Project 115	Job no.	1693/01	Sheet	B.9
Engineer	RWA				
Checked by	JH				
Project	No. 11 Rossmore Hill				



(a) Definition of deflection ratio.



(b) Influence of horizontal strain on $\Delta L / \epsilon_{lim}$ (after Burland, 2001)



(c) Relationship between damage category and deflection ratio and horizontal tensile strain for hogging for $(L/H) = 1.0$ (after Burland, 2001)

By adopting values of ϵ_{lim} associated with the various damage categories given in Table 2.5, Figure (b) can be developed into an interaction diagram showing the relationship between ΔL and ϵ_h for a particular value of L/H . Figure (c) shows such a diagram for $(L/H) = 1.0$.

Figure 2.18 Relationship between damage category, deflection ratio and horizontal tensile strain (after Burland, 2001)

Reinforced concrete-framed structures are more flexible in shear than are masonry structures and are consequently less susceptible to damage. Nevertheless, for the purposes of a stage 2 assessment of potential damage, all structures should be treated as masonry structures.


Box 2.5 Procedure for stage 2 damage category assessment

The following steps should be undertaken in making a stage 2 assessment of the damage to a structure:

- establish L and H for the structure (see Figure 2.18(a) for definitions of L and H)
- determine (L/H)
- determine relationship between (Δ/L) and ϵ_h for the required (L/H) from Figure 2.18(b) for ϵ_{lim} values from Table 2.5
- estimate vertical and horizontal ground surface movements in the vicinity of the structure from Figure 2.14
- determine (Δ/L) and $\epsilon_h (= \delta_h/L)$ where δ_h is the horizontal movement
- estimate damage category from the relationship between (Δ/L) and ϵ_h established from step (iii) above.

THE NEXT STAGE IS TO CALCULATE THE HORIZONTAL & VERTICAL STRAINS EXPERIENCED BY THE ADJACENT BUILDINGS.

HORIZONTAL STRAIN




HORIZONTAL STRAIN


$$\epsilon_h = \frac{\delta h_1 + \delta h_2}{L}$$

VERTICAL STRAINS

THE TOTAL VERTICAL DEFLECTION FOLLOWS THE FOLLOWING RELATIONSHIP



THE STRAINS CANNOT SIMPLY BE CALCULATED AS FOR THE HORIZONTAL STRAINS. THE BUILDING WILL DEFORM AS FOLLOWS



NOTE THE BUILDING IS ASSUMED TO DEFLECT TO FOLLOW THE SURFACE OF THE GROUND.


Alan Baxter

75 Cowcross Street
London EC1M 6EL
tel 020 7250 1555
fax 020 7250 3022
email: alabaxter@alanbaxter.co.uk
www.alanbaxter.co.uk

Date	10/01/15	Job no.	1693/01	Sheet	8.11
Engineer	RWM				
Checked by	JK				
Project	No.11 ROSSLYN HILL				

THE ABSOLUTE DEFLECTIONS HERE ARE NOT IMPORTANT. THE DIFFERENTIAL SETTLEMENT IS AS THIS CAN CAUSE CRACKING. STRAINS CAN BE RELATED TO $\Delta =$ GREATEST DIFFERENTIAL SETTLEMENT, AS SHOWN ON THE PREVIOUS PAGE.

THE FOLLOWING GRAPH SHOWS THE TOTAL VERTICAL DEFLECTIONS CALCULATED PREVIOUSLY. THE BUILDINGS HAVE BEEN DRAWN TO DETERMINE THEIR DIFFERENTIAL VERTICAL MOVEMENT. THEIR EXTENTS CLOSEST AND FURTHEST POSITIONS FROM THE FACTORY HAVE BEEN DETERMINED FROM THE CONTOUR MAP AND TABULATED ON THE FOLLOWING PAGE.



Alan Baxter

75 Cowcross Street
London EC1M 6EL
tel 020 7250 1555
fax 020 7250 3022
email ab@alanbaxter.co.uk
www.alanbaxter.co.uk

Date 16/02/15

Job no

Sheet

Engineer RWA

1602/01

B.12

Checked by JF


Project

No. 11 Rossmore Hill

STRUCTURE	CLOSEST CONTOUR (m)	FURTHER CONTOUR (m)	A (mm)	L (m)	A/L %
a) NO. 11 ROSSMORE HILL	10	15	4.5	17	0.026
b) LYNCHMERE HALL	1	20+	7.2	55	0.013
c) GARAGES ON HAVESFORD HILL	10	6	1.5	12	0.0125

HORIZONTAL STRAIN

GRAPH BELOW PROVIDED FROM TOTAL GROUND SURFACE MOVEMENT ON SHEET



Alan Baxter

75 Cowcross Street
London EC1M 6EL
tel: 020 7250 1555
fax: 020 7250 3022
email: ab@alanbaxter.co.uk
www.alanbaxter.co.uk

Date	11/01/15	Job no.	1693/01	Sheet	B.13
Engineer	RWC				
Checked by	JH				
Project	No.11 Rosslyn Hill				

STRUCTURE	CLOSEST CONTOUR	δh_1 (mm)	FURTHEST CONTOUR	δh_2 (mm)
11 ROSSLYN HILL	1	14.5	15	~5
LYNDHURST HALL	1	14.5	20+	2.5
CARAGES ON HAVERSLOCK HILL	1	14.5	6	10

$\Delta \delta h_1 - \delta h_2$	L	E_h (%)
19.5	17	0.056
12	55	0.022
4.5	6	0.075

VALUES FOR δh_1 & δh_2 HAVE BEEN FOUND FROM THE GRAPH ON THE PREVIOUS PAGE

$$\text{HORIZONTAL STRAINS} = \frac{\delta h_2 - \delta h_1}{L} = E_h$$

DAMAGE ASSESSMENT

THE HORIZONTAL & VERTICAL STRAIN WILL BE USED TO ASSESS THE BURLAND DAMAGE CATEGORY FOR EACH STRUCTURE FOR EACH STRUCTURE IN ACCORDANCE WITH THE LIMITING STRAIN FOR EACH CATEGORY OUTLINED IN TABLE 2.5 ON THE FOLLOWING PAGE & THE GRAPH IN FIGURE 2.18.

Date	16/04/15	Job no.	1693/01	Sheet	B. 14
Engineer	RWA				
Checked by	JH				
Project	No. 11 Roselyn Hill				

Table 2.5 Classification of visible damage to walls (after Burland et al, 1977, Boscardin and Cording, 1989; and Burland, 2001)

Category of damage	Description of typical damage (case of repair is underlined)	Approximate crack width (mm)	Limiting tensile strain ϵ_{lim} (per cent)
<u>0 Negligible</u>	Hairline cracks of less than about 0.1 mm are classed as negligible.	< 0.1	0.0–0.05
<u>1 Very slight</u>	<u>Fine cracks that can easily be treated during normal decoration.</u> Perhaps isolated slight fracture in building. Cracks in external brickwork visible on inspection.	< 1	0.05–0.075
<u>2 Slight</u>	<u>Cracks easily filled. Redecoration probably required.</u> Several slight fractures showing inside of building. Cracks are visible externally and <u>some repointing may be required externally</u> to ensure weathertightness. Doors and windows may stick slightly.	< 5	0.075–0.15
3 Moderate	<u>The cracks require some opening up and can be patched by a mason. Recurrent cracks can be masked by suitable linings. Repointing of external brickwork and possibly a small amount of brickwork to be replaced.</u> Doors and windows sticking. Service pipes may fracture. Weathertightness often impaired.	5–15 or a number of cracks > 3	0.15–0.3
4 Severe	<u>Extensive repair work involving breaking-out and replacing sections of walls, especially over doors and windows.</u> Windows and frames distorted, floor sloping noticeably. Walls leaning or bulging noticeably, some loss of bearing in beams. Service pipes disrupted.	15–25 but also depends on number of cracks	> 0.3
5 Very severe	<u>This requires a major repair involving partial or complete rebuilding.</u> Beams lose bearings, walls lean badly and require shoring. Windows broken with distortion. Danger of instability.	usually > 25 but depends on number of cracks.	

Notes

- In assessing the degree of damage, account must be taken of its location in the building or structure.
- Crack width is only one aspect of damage and should not be used on its own as a direct measure of it.

Alan Baxter

75 Cowcross Street
London EC1M 6EL
tel 020 7250 1555
fax 020 7250 3522
email: ab@alanbaxter.co.uk
www.alanbaxter.co.uk

Date	MARCH 15	Job no.	1653/01	Sheet	B.15
Engineer	RWA				
Checked by	JH				
Project No. 11 Rosslyn Hill					

STRUCTURE	Δ/L %	E_h %	yh	damage category of damage.
a) No. 11 Rosslyn Hill	0.026	0.06	1.3	(2)
b) Lyndhurst Hall	0.013	0.02	2.5	(1)
c) GARAGES ON HALLESBEEK HILL	0.0125	0.075	4	(2)

CALCULATIONS. LIMIT $E_{lim} = 0.15\%$ SLIGHT.

a) 1 Rosslyn Hill.

$$\frac{\Delta/L}{E_{lim}} = \frac{0.026}{0.15\%} = 0.41$$

$$\frac{E_h}{E_{lim}} = \frac{0.06}{0.15} = 0.173$$

FROM FIGURE 2.15.1 \rightarrow OK.

CALCULATION LIMIT $E_{lim} = 0.075\%$ VERY SLIGHT

b) Lyndhurst Hall

$$\frac{\Delta/L}{E_{lim}} = \frac{0.013}{0.075} = 0.173$$

$$\frac{E_h}{E_{lim}} = \frac{0.02}{0.075} = 0.26$$

FROM FIGURE 2.15.6 \rightarrow OK

Alan Baxter

75 Cowcross Street
London EC1M 6EL
tel 020 7250 1555
fax 020 7250 3022
email ab@alanbaxter.co.uk
www.alanbaxter.co.uk

Date	14/02/15	Job no	1692/01	Sheet	2 of 16
Engineer	RWA				
Checked by	JH				
Project	No. 11 Roselyn Hill				

CALCULATION LIMIT $E_{lim} = 0.15$ SLIGHT

c) GARAGES ON
HARESTOCK HILL

$$\frac{\Delta/L}{E_{lim}} = \frac{0.075}{0.15} = 0.5$$

$$\frac{E_h}{E_{lim}} = \frac{0.0125}{0.075} = 0.16$$

From figure 2.15b \rightarrow OK


ALL STRUCTURAL DAMAGE IS LIMITED TO A MAXIMUM
OF RUPLAND CATEGORY 2 \rightarrow SLIGHT \therefore OK.

Appendix K Arboriculturalist's Report

DRAFT 1 Airspade Root Investigation. 11 Rosslyn Hill.



BOWARD TREE SURGERY (OXFORD) LTD.
THE LOG QUARRY
CHURCH ROAD,
LONG HANBOROUGH,
WITNEY, OXON,
OX29 8JF
TEL: 01993 880500
VAT Reg No. 718 0487 29
EMAIL: boward.ox@btopenworld.com



DOCUMENTS TO VIEW:

- LANDSCAPE TRENCHES JPEG.
- AIRSPADE INVESTIGATION – PHOTOGRAPHIC EVIDENCE & ROOTING ZONES.
- EXCAVATION BOUNDARY CONDITIONS.
- PLAN A, BS: 5837 2012, 11 Rosslyn Hill, London
- For root diameters in each rooting zone see table 1. In appendix.

This report is an extension of the BS: 5837 2012 arboricultural report and impact assessment which found that the root protection area (the area which is predicted to be in use by a tree based upon a calculation derived from the stem diameter) of several trees was found to extend into the proposed basement area at 11 Rosslyn Hill, where the light-well, stairs, store room and kitchen are to be located. This includes the RPA of two mature category B Horse Chestnuts (tagged 3778 & 3776) and also a mature category C Sycamore (tagged 3777). Of these only tree 3776 is growing from the grounds of number 11 (See Plan A, BS:5837 2012 11 Rosslyn Hill, London).

Airspade works were carried out by Mr Michael Boys, Geoffery Finnermore and Matthew Jellings between the 18th and 21st of June 2013. The weather during this period was dry and suitable for carrying out trench digging using compressed air blown through a hollow lance, a method which removes the soil but leaves the stronger roots intact. The positioning of the three trenches was recommended by Stuart Hookham of Alan Baxter & Associates LLP, although slight modifications were made where necessary due to the presence of a previously unknown layer of concrete and drainage inspection chamber (See 'Exact landscape trenches jpg.')

The turf over the trenches was carefully removed in sections to allow it to be laid back onto the lawn. Outside of the predicted root protection area the trenches were excavated 30-35cm wide and taken to a depth of 1m using a mini-digger to produce a steep vertical soil profile which made the use of the air-spade more efficient. Soil was blown along the trench until it could be removed with the mini-digger or by hand, until either a root of significant size or dense rooting mat of thinner roots was discovered. The location of any roots above 1cm was recorded, and these were covered in damp hessian material to protect from desiccation. Any damaged roots were severed using secateurs to give the cleanest possible wound and reduce the likelihood of future root decay.

Trench 1.

Soil Type: Under the lawn there is a brown earth soil roughly 20cm deep, below which is a mixture of semi-loose soil and builder's rubble, with a horizon of flint and pebbles embedded in thick grey clay emerging around 60-100cm.

Root Content: As predicted, within the RPA of tree 3776 there were a number of significant roots, with larger roots closer to the base of the tree. The majority of the roots over 1cm in diameter were found in the top 20cm of soil however one was found at a depth of 46cm. Two important roots 6cm in diameter were found at the southern corner of the trench, and these lead towards the Horse Chestnut tree 3776.

Key Points: We would recommend that the major roots located to the south east of trench 1 are avoided.

Trench 2.

Soil Type: The soil make up under the lawn is the same as trench 1. The soil composition changes below the gravel matting, where there is a concrete surface 10-15cm deep which is joined to the main house, extending outwards from the property SW by 2m. The trench was dug along the edge of this concrete. Outside of the concrete surface there is a small man-made sand layer below the ground sheet which is mixed with a small dirt surface layer 10-20cm deep. Below this the soil horizon turns to orange/brown clay. Some builder's rubble was found in the layer around 50cm down.

Root Investigation: A dense rooting matt of fine and coarse roots (>1cm) were discovered in the top 20cm of the soil under the lawn between trench 1 and the gravel area, proving the trees are utilising this area heavily for water/nutrient uptake. Boward did not excavate deeper in this section of the trench for fear of damaging these surface roots. In the trench underneath the

gravel a small rooting area was discovered parallel to the decking area spreading up to 5m away from the step between the lawn and gravel. The largest root in this section of the trench branched into two in a south westerly direction, presumably this root is growing from the young Wisteria rather than the mature trees to the south.

Key Points: Note the presence of the drains at either end of the trench, which are surrounded by concrete and 2.2m deep. An old drain pipe was found roughly 40-50cm down to the South West of the trench. Whether this is in service is not known.

Trench 3.

Soil Type: This trench was the most difficult to dig using the air-spade with the soil made up of a highly compacted mixture of grey clay, flint and rubble.

Root Investigation: No fine roots discovered, only a single main root which flared out to the NW of the existing guest house.

Key Points: It is possible that the hard condition of the ground here made it cost-ineffective for the trees to develop fine rooting system in this predicted rooting area. As such, although a significantly sized root was discovered here in general this trench is not being utilised by roots.

APPENDIX

Table 1. Diameter of significant roots found in airspade investigation.

Map Label	Trench	Diameter of root/roots/mm
A	1	10, 16, 12, 22
B	1	14
C	1	30
D	1	28, 18, 12
E	1	19
F	1	12, 13
G	1	60, 65
J	2	21
K	2	15, 14, 18
L	2	21
M	3	29

RECOMMENDATIONS:

BASEMENT DESIGN:

GROUND FLOOR DESIGN:

Air-spade Root Investigation. 11 Rosslyn Hill.



BOWARD TREE SURGERY (OXFORD) LTD.
THE LOG QUARRY
CHURCH ROAD,
LONG HANBOROUGH,
WITNEY, OXON,
OX29 8JF
TEL: 01993 880500
VAT Reg No. 718 0487 29
EMAIL: boward.ox@btopenworld.com



DOCUMENTS TO VIEW:

- LANDSCAPE TRENCHES JPEG.
- AIRSPADE INVESTIGATION – PHOTOGRAPHIC EVIDENCE & LOCATIONS.
- EXCAVATION BOUNDARY CONDITIONS.
- PLAN A, BS: 5837 2012, 11 Rosslyn Hill, London
- For root diameters in each rooting zone see table 1. In appendix.

This report is an extension of the BS: 5837 2012 arboricultural report and impact assessment which found that the root protection area (RPA - the area which is predicted to be in use by a tree based upon a calculation derived from the stem diameter) of several trees was found to extend into the proposed basement area at 11 Rosslyn Hill, where the light-well, stairs, store room and kitchen are to be located. This includes the RPA of two mature category B Horse Chestnuts (tagged 3778 & 3776) and also a mature category C Sycamore (tagged 3777). Of these only tree 3776 is growing from the grounds of number 11 (See Plan A, BS:5837 2012 11 Rosslyn Hill, London).

Air-spade works were carried out by Mr Michael Boys, Geoffrey Finnimore and Matthew Jellings between the 18th and 21st of June 2013. The weather during this period was dry and suitable for carrying out trench digging using compressed air blown through a hollow lance, a method which removes the soil but leaves the root system intact. The positioning of the trenches was recommended by Stuart Hookham of Alan Baxter & Associates LLP, although slight modifications were necessary due to the presence of a previously unknown layer of concrete and a drainage inspection chamber (See 'Exact landscape trenches jpg.')

The turf over the trenches was carefully removed in sections to allow it to be laid back onto the lawn. Outside of the predicted root protection area the trenches were excavated 30-35cm wide and taken to a depth of 1m using a mini-digger to produce a steep vertical soil profile which made the use of the air-spade more efficient. Soil was blown along the trench until it could be removed with the mini-digger or by hand, until either a root of significant size or a dense rooting mat of thinner feeding roots was discovered. The location of any roots above 1cm in diameter was recorded, and were covered in damp hessian material to protect from desiccation. Any damaged roots were severed using secateurs to give the cleanest possible wound and reduce the likelihood of future root decay. After excavation, the soil was carefully placed back in to the trenches.

Trench 1

Soil Type: Under the lawn there is a brown earth soil roughly 20cm deep, below which is a mixture of semi-loose soil and rubble, with a horizon of flint and pebbles embedded in thick grey clay emerging around 60-100cm.

Root Content: As predicted, within the RPA of tree 3776 there were a number of significant roots, with larger roots closer to the base of the tree. The majority of the roots over 1cm in diameter were found in the top 20cm of soil however one was found at a depth of 46cm. Two important roots belonging to Horse Chestnut Tree 3776, of 6cm diameter were found at the southern corner of the trench.

Key Points: We would recommend that the existing RPA of tree 3776 is respected (see Excavation Boundary conditions).

Trench 2

Soil Type: Same as trench 1

Root Investigation: A dense rooting matt of fine and coarse roots (>1cm) were discovered in the top 20cm of the soil under the lawn between trench 1 and the gravel area, proving the trees are utilising this area for water/nutrient uptake. We did not excavate deeper in this section of the trench for fear of damaging these surface roots.

Key Points: Excavation around this part of the lawn should be avoided. It can be inferred that the roots discovered in this area could be attributed to the adjacent horse chestnut (3776), and hence the area located north of the trench line relating to the RPA of sycamore 3777 is potentially

negligible, however without an in-depth analysis of species identification on the roots, and an excavation to determine the depth of footing for the the patio, this hypothesis cannot be confirmed.

Trench 3

Soil Type: The soil composition changes below the gravel matting, where there is a concrete surface 10-15cm deep which is joined to the main house, extending outwards from the property SW by 2m. The trench was dug along the edge of this concrete. Outside of the concrete surface there is a small man-made sand layer below the ground sheet which is mixed with a small dirt surface layer 10-20cm deep. Below this the soil horizon turns to orange/brown clay. Some rubble was found in the layer around 50cm down.

Root Investigation: Underneath the gravel, some smaller roots were discovered parallel to the patio area spreading up to 5m away from the step between the lawn and gravel. The largest root in this section of the trench branched into two in a south westerly direction (K). The observed branching angles of this root suggest that this root is growing from the adjacent Wisteria rather than the mature trees to the south. Smaller roots were found at a depth just above the compacted clay at 40-50cm.

Key Points: Note the presence of the concrete drain access manholes at either end of the trench (See *Photographic Evidence and Locations*.) One was measured to an internal depth of 2.2m. An old drain pipe was found roughly 40-50cm down to the South West of the trench. Whether this is in service is not known. The RPA north of the trench is attributed to sycamore 3777. The north easterly side of the trench provided no evidence of root activity relating to the RPA's in question. No significant roots were discovered within this trench

Trench 4

Soil Type: This trench was the most difficult to dig using the air-spade with the soil made up of a highly compacted mixture of grey clay, flint and rubble.

Root Investigation: No fine roots discovered, only a single main root which flared out to the North of the existing guest house.

Key Points: It is possible that the hard condition of the ground here made it difficult for the adjacent tree (3778) to develop a fine rooting system in this predicted rooting area. As such, although a significant root was discovered here, in general this area is not being utilised by trees feeding roots.

RECOMMENDATIONS:

In light of the excavation, we suggest that the area marked for development to the south west of the main building is relocated outside of existing RPA's or otherwise removed from the development proposal. However the easterly proposed plans will not significantly affect existing root activity.

BS5837:2012 section 7.2.1 states in relation to RPA's that "Intrusion into the soil (other than for Piling), within the RPA is generally not acceptable", suggesting that with the assistance of a structural engineer, a development incorporating a 'no dig' strategy using pile foundations within the RPA may be approvable. However a basement level would require a strip retaining wall and is as such unsuitable within an RPA.


In conjunction with the above paragraph, BS5837:2012 section 7.4.2.3 states that new permanent hard surfacing should not exceed 20% of any existing surfaced ground. Implying that a development could sit on top of the ground within the RPA, provided that no excavation was required and that its total area of ground did not exceed 20% of the RPA.


The excavation highlighted areas that did not contain significant roots within the RPA. For a diagram showing zones within the nominal RPA that can and cannot be exploited for development See *Excavation Boundary Conditions*.

APPENDIX

Table 1; Diameter of significant roots found in air-spade investigation.

Map Label	Trench	Diameter of root/roots/mm
A	1	10, 16, 12, 22
B	1	14
C	1	30
D	1	28, 18, 12
E	1	19
F	1	12, 13
G	1	60, 65
J	3	21
K	3	60, branching to 30 and 25
L	3	20, 10, 23, 23, 10
M	4	29






BOWARD
OXFORD LTD.

**11 Rosslyn Hill, Camden,
Greater London, NW3 5UL**

SCALE : 1 : 50	DATE : 25/06/2013
MAP FILENAME : EXCAVATION BOUNDARY CONDITIONS	


Boward Oxford Ltd., The Log Quarry, Church Road, Long Hanborough,
Witney, Oxfordshire, OX28 3UG. 01993 880500, email: boward.ox@gmail.com
Maps based on Ordnance Survey MasterMap or 1:25000 Mid-scale data




N



DATE :
25/06/2013



**Boward Oxford Ltd., The Log Quarry, Church Road, Long Hanborough, Witney,
Oxfordshire, OX28 8JF Tel: 01993880500, email: Boward.ox@gmail.com**
Maps based on Ordnance Survey MasterMap or 1:25000 Mid-scale



Old Services?





Wisteria root



Wisteria



Drain access manhole

Old Services?

Weeping Mulberry



11 Rosslyn Hill, Camden,
Greater London, NW3 5UL

SCALE :
1 : 50 at A1


DATE :
25/06/2013



MAP FILENAME :
AIRSPADE INVESTIGATION -
Photographic evidence and locations

Boward Oxford Ltd., The Log Quarry, Church Road, Long Hanborough, Witney,
Oxfordshire, OX28 8JF Tel: 01993880500, email: Boward.ox@gmail.com
Maps based on Ordnance Survey MasterMap or 1:25000 Mid-scale data





**11 Rosslyn Hill, Camden,
Greater London, NW3 5UL**

SCALE :
1 : 50

DATE :
25/06/2013

MAP FILENAME :
EXCAVATION BOUNDARY CONDITIONS

Boward Oxford Ltd., The Log Quarry, Church Road, Long Hanborough,
Witney, Oxfordshire, OX28 3UG. 01993 880500, email: boward.ox@gmail.com
Maps based on Ordnance Survey MasterMap or 1:25000 Mid-scale data



Boward Oxford Ltd.

Tree Surgery | Surveying | Consultancy | Planting
TEL: 01993 880500
Email: boward.ox@btopenworld.com

E. Tree Protection Plan, 11 Rosslyn Hill,
London, NW3 5UL

SCALE :
1 : 700

DATE :
06/03/2015

MAP FILE REFERENCE :
Jinny Blom, Rosslyn Hill

Pear Technology Services Ltd, Email info@peartechnology.co.uk
Maps based on Ordnance Survey MasterMap or 1:25000 Mid-scale data



78.7m

Lyndhurst
Hall

WATERHOUSE CLOSE

Out-buildings
to be removed.

Ground
protection (Terram).

Heras protection
to be positioned
around magnolia.
Arrange as best
as possible over level
changes.

Heras tree protection
(back braced) To be extended
fully around the trees 3761 & 3764
once outbuildings demolished.

Ground
protection
along
entranceway
(TERRAM).

Heras tree
protection without
back bracing.

Potential storage area.

Guest house to
be demolished.
Small area of original
foundation to be left 1m
away from tree stem 3879.

Non-permeable
geotextile membrane
separating piles from soil.

Foundations of dining
room to be laid on piles to
north outside RPA being
utilised by 3776/77/78.

Ground
protection
with storage area.

ros3765 C
ros3766 C
ros3767 U
ros3768 C

Tree Stump
(0.8m wide)
ros3771 C
ros3770 B

Map Legend

Tree Canopy	Category B	Category C	Trees/hedge to be removed	Root Protection Area	Area to be paved	Foundation to be left	TYPF Heras Fencing	Storage Area	Ground Protection	Geotextile membrane

20 metres

1 to 26

16

Boward Oxford Ltd.

Tree surgery, surveying and planting

TEL: 01993 880500
Email: boward.ox@btopenworld.com

D Root Protection Area and Impact Map.
11 Rosslyn Hill, London, NW3 5UL

SCALE :

1 : 500

DATE :

03/04/2013

MAP FILE REFERENCE :



Jinny Blom, Rosslyn Hill

Pear Technology Services Ltd; Email info@peartechnology.co.uk

Maps based on Ordnance Survey MasterMap or 1:25000 Mid-scale data with



Map Legend



Legend

- Root Protection Area
- RPA with strong evidence of activity
- RPA with little evidence of activity
- RPAS with no evidence of root activity
- RPA in construction zone
- RPA under construction access route

Email: boward.ox@btopenworld.com

1 : 500

06/03/2015

MAP FILE REFERENCE :
Jinny Blom, Rosslyn Hill

Pear Technology Services Ltd; Email info@peartechology.co.uk
Maps based on Ordnance Survey MasterMap or 1:25000 Mid-scale data



WATERHOUSE CLOSE

1 to 26

78.7m



Proposed Basement Layer

Category

Category
U-Tree Cases

Root

Pool



20 metres

16

Boward Oxford Ltd.

Tree Surgery | Surveying | Consultancy | Planting

TEL: 01993 880500

Email: boward.ox@btoopenworld.com

B. Ground Floor, 11 Rosslyn Hill, London, NW3 5UL

SCALE :

1 : 500

DATE :


06/03/2015

MAP FILE REFERENCE :

Jinny Blom, Rosslyn Hill

Pear Technology Services Ltd; Email info@peartechnology.co.uk

Maps based on Ordnance Survey MasterMap or 1:25000 Mid-scale data





**11 Rosslyn Hill
London
NW3 5UL**

Impact Assessment

March 2015

Report compiled by:

Matthew Jellings
Boward Tree Surgery (Oxford) Limited
The Log Quarry
Church Road
Long Hanborough
Witney
Oxfordshire
OX29 8JF



4.0 Introduction

The purpose of this document is to provide details as to how any given proposed construction works will impact upon the existing treescape as shown in the attached arboricultural survey report.

The construction of a basement area is proposed to the East (front pool, sauna, toilet & stairs) and West (TV room) of the property. Further the guest house at the front is to be demolished and reconstructed, and the existing property is to be extended with a dining room to the south. Three outbuildings are to be removed, see **plan E**. These design proposals will impact on the local treescape.

An airspade investigation was carried out in the rear garden – see **Excavation boundary conditions** for a map highlighting rooting areas of different importance.

The impacts of the construction work at 11 Rosslyn Hill have been split into trees whose root protection area will be impacted, trees where crown lifting may be required, and trees which will need to be removed. There are two plans for the proposed construction works, see **plan B** for ground floor footprint and **plan C** for basement footprint. See **plan D** for where the construction will impact the trees on site.

ROOT PROTECTION AREAS

- ❖ There are a number of areas on the site where the proposed build will have a negative impact on the condition of the local trees unless protection measures are in place (see **plan D**).
- ❖ The root protection areas of 5 trees to be retained will be impacted (Table 2, see **plan D**) :

Tree ID	Category	Proportion of root protection area effected (%)
3751	B	11 (construction traffic)
3763	B	Minor infringement by TV room (1-2%)
3777 & 3778	B	Minor infringement beyond trench 3 for mini piles and stairs/toilet (1-3% each). Note trench 3 found no evidence of rooting.
3779	C	25% infringement by foundations of new guest house (note – the original foundations would be expected to be excluding root development in this space, so the predicted RPA shape is likely redundant here). The tree base is not in the grounds of 11 Rosslyn Hill.

Table 2. RPAs infringed because of proposed development.

The foundations of the dining room are to be based on the minipiles (300mm diameter) and concrete slabs in the RPA of 3776-78. The impact of these piles is to be alleviated, see **arboricultural method statement**. There is very little root infringement (1-2%) by the basement stairs and toilet beyond trench 3 which showed no evidence of rooting.

CROWN LIFTING

Two trees require crown lifting in order to permit access by construction vehicles.

The necessity of these crown lifting works should be decided upon at a later date, only when it becomes clear their canopies are going to interfere with construction works.

	Possible crown lifting required for tarmac removal				
	A	B	C	U	Tag Number
Entrance/exit from junction. Holly trees.			2		3757, 3755

Table 3. Trees to be crown lifted where necessary.

TREE REMOVAL

The category C Laburnum tree '3762' will need to be removed to allow vehicular access to the rear garden and also permit building of the TV room.

5.0 Please see table **Full BS5837:2012 Tree Details, 11 Rosslyn Hill** for tree details.

6.0 See **arboricultural survey report, general comments** document for a brief overview of the arboricultural implications.

7.0 See **Arboricultural Method statement** document which outlines the best mitigation to be used during the construction works on trees to be retained.



11 Rosslyn Hill
**Arboricultural
Method Statement**

March 2015

Report compiled by:

Matthew Jellings
Boward Tree Surgery (Oxford) Limited
The Log Quarry
Church Road
Long Hanborough
Witney
Oxfordshire
OX29 8JF



Re: Construction of a basement TV room, pool, sauna and toilet and ground level dining room and new guest house.

Arboricultural Method Statement:

All persons involved in the proposed construction works to be made aware of the importance of the retained trees at this site and to be familiar with the requirements of the works Method Statement and Tree Protection Measures.

The site to be subject to a visit from the Retained Arborist who will inspect for Arboricultural Method Statement compliance and correct implementation of the Tree Protection Measures as well as recording findings by means of photographs.

Site Specific Method Statement

The first phase of tree protection will include all the pre-construction works, including the erection of the tree protection fencing and demolition of the present guesthouse and 3 garden outbuildings. As many prominent, mature and high value trees are on site a high level of protection is required during all phases. The next phase of tree protection will be needed for the construction works of the basement and ground level buildings. Landscaping the paved area will be the final phase of protection.

Phase 1: Pre-Construction & Demolition – See plan E.

TREWORKS

1. Tree 3762 to be felled and removed providing council consent is given for this. The hedgeline along the right of the entranceway to be removed. The canopy of trees 3757 and 3755 may need lifting to 5 metres in order to provide good access to construction vehicles. The necessity of the lifting works is to be decided upon at a later date. All tree works to be carried out in accordance with BS: 3998 (2010) – Recommendations for Tree works, and to be done in such a way as that no damage is caused to any of the retained trees.

CONSTRUCTION EXCLUSION ZONE (CEZ)

2. Tree Protection Fencing (TPF) to be positioned as per **plan E**. This is to provide the upmost level of protection during the demolition phase. The fencing will exclude construction workers and machines from entering the Tree Protection Zone while removing the existing sheds. The type of fencing will be Heras supported with back braces where possible. Given the tight entrance way the fencing surrounding tree 3751 will have to be supported on blocks. The fencing around tree 3763 in the rear garden will have to be arranged as best as possible to protect the trees canopy and stay secure on the different garden levels. Please see Appendix 1 for Heras fencing details.
3. Tree protection fencing shall be maintained and retained for the full duration of the works, but can be removed for the soft landscaping workings on the paved area.
4. Potential areas for material storage are coloured yellow on **plan E**, and ground boards should be arranged under any area for material storage if on the grass area to the rear (can use plywood boards here for material storage). No activities or storage of materials whatsoever shall take place within the construction exclusion zone without the prior written

agreement of the LPA. Ground protection also needs to be laid over the RPA of the category B tree at the entranceway to help alleviate soil compaction from construction plant, and tree 3761 for the same purpose. An example of the quality of ground protection expected over the RPAs on site is shown in the appendix (Terram geocells). In the rear garden ground protection is needed to protect the root protection areas of the line of trees to the SE. The ground protection over RPAs must stay in place for the duration of the works, with the exception of when the paving is to take place in the rear garden.

5. All demolition works to take place from outside the RPAs of any of the retained trees on site.
6. Where the lower garden shed is over the RPA of the category B Lime 3764 care must be taken not to damage the tree's canopy or RPA. Removing the foundations with a pneumatic drill is required when working in the RPA of the tree.
7. To benefit the rooting area of tree 3879 the existing foundation under the guest house could be left 1m from the base of the tree. This would prevent most of the disturbance or damage to the tree which is growing from land not owned by 11 Rosslyn Hill. This would reduce potential damage to the RPA of 3879 by 80% (see **plan E**).
8. Prestart meeting that includes the Retained Arborist, Architect and the designated construction company management team to explain the requirements of the Arboricultural Method Statement (AMS) and the Tree Protection Plan (TPP) measures.

Phase 2: Construction Works

1. Tree protection fencing to be moved to fully surround tree 3761, 3763 and 3764 once the timber lean to and shed is removed.
2. Where laying the foundation of the guest house may have a detrimental impact to the root system of tree 3779 the impact must be minimised (see below, section 3. i – iii). The full extent of rooting here will not be known until the foundations of the original guest house are taken up (leaving a 1m zone around the tree base). The magnolia tag number 3763 has most of its RPA in the CEZ but the western edge of the RPA may be lightly effected by the TV basement room, and again the measures found in 3.i-iii should be followed when digging in the RPA here.
3. The exact location of 7 piles coloured red in **plan D** are beyond the scope of the airspade investigation and should be determined by hand digging the wells, if any roots are found greater than 25mm in diameter then another well should be dug until a clear spot is located for the pile. It is important no large diameter roots are severed close to the trees 3776-78, and so attention and care will be needed using spades/pick axes here. You may find this to be a very time consuming process if medium to large roots are common in the ground here, alternatively if no big roots are present then locating sites for piles will be simple. I would recommend hand digging to a depth of roughly 1m. The exterior walls of the mini piles will need a thin non-permeable geotextile to contain the cement. Concrete slabs will be laid on the mini piles and there will be an airgap between the concrete slabs and soil layer. The

exact size of the air gap is yet to be determined, we await to hear back from a tree officer, Chris Leyland, who has experience in these matters.

4. Where the RPAs are infringed specific measures are required to minimise disturbance to the trees root systems. These include;
 - i. Only hand digging with minimal disturbance and soil level change to take place within RPAs.
 - ii. Any roots that are uncovered up to 25mm in diameter to be chased back to a suitable root junction and severed by means of appropriate pruning tools.
 - iii. Any roots that are uncovered above 25mm in diameter to be worked around in consultation with the retained arborist. While exposed any uncovered roots to be retained to be covered with a suitable hessian type material and kept moist.
5. Concrete and the run-off from it is particularly damaging to plant roots. A non-permeable geotextile barrier could be applied along the outer edge of the piling in the RPA of tree 3777 and 3778 to prevent future contamination of the soil here (see **plan E**). Care to be taken by construction personal to prevent any spillage. Any accidental spillage to be cleared immediately and the Retained Arborist notified.

Phase 3: Landscaping

1. On completion of all construction works to the basement layer and ground floor tree protection fencing and ground boards can be removed to allow the laying of the paving in the rear garden.
2. Slabs to be laid using the following method to avoid damage to tree roots:
 - i. The ground layer to be removed using hand tools or plant with non-toothed bucket if such plant can be operated from outside of the root protection area and if there is no possibility of mechanical damage to lower canopy sections.
 - ii. The design and construction will not involve any change in the existing ground levels other than the scraping off of grass sward and ground layer plants. Any works that require the removal of woody shrubs with significant root systems will require root systems to be removed by means of hand grubbing or careful root grinding. All construction to be above existing ground levels (once the grass sward and ground layer plants have been removed) and to include any required edging.
 - iii. The design will be such as to resist deformation due to annular expansion of roots and stems and will provide a surface that will support the required loads without soil compaction or deformation.

- iv. The design to be such as to allow for suitable gaseous exchange.
3. On completion of all works any trees that die, become seriously damaged, or die within 5 years of this development shall be replaced the following year by trees of the same size and species.
4. The hedgeline which was removed to allow access for vehicles to be replaced with similar species of hedging.

Appendix 1

Planning Category rating:

Category ratings are allocated based on the current condition of a tree in its current surroundings assuming the recommendations of this report are carried out. No consideration is given to any specific development proposal when allocating category ratings. For a full break down of tree categorisation see below:

Category A trees are those which have high visual amenity value, are in good structural and physiological condition and are expected to contribute for at least another 40 years.

Category B trees are those which would be considered as category A trees but which are of lower value, poorer structural condition, or which are expected to contribute for less than 40 years.

Category C trees are those which have low amenity value, are in poor condition, or are expected to contribute for less than 20 years.

Category U trees are those which are expected to contribute for less than 10 years due to serious defects. As is common in risk management, where there is doubt, the precautionary principal may be applied.

In certain circumstances trees may be considered of higher value due to cultural or ecological reasons. If this is the case it will be made clear in the tree data tables.

Sub-categories:

Sub- categories of 1, 2 or 3 are included in the tree data tables and are defined as follows:

Sub-category 1 trees are those with 'other arboricultural value'


Sub-category 2 trees are those with 'landscape value'

Sub-category 3 trees are those with 'cultural or conservation value'

Suggested signage for tree protection fencing:



Required construction method of Tree Protection Fencing:



Market Sector Application Function Products Projects Downloads About Us Contact Us Search

Geocells

Tree Root Protection / Load Platform Geocell

Application Function
Ground Stabilisation / Compartment / Containment / Slope Control

Market Sectors
Highways / Roads & Waterways

Products
Terram Geocell (2010 & 2024)

The Terram geocell is a cellular reinforcement system that is used to protect tree roots from damage caused by heavy vehicles, particularly where a Tree Protection Order (TPO) is in place. Conventional construction would be invasive and trees are prone to disturbance.

The geocell is manufactured from one of the Terram geocell ranges which means that air and water are free to move across the root area from left to right. The geocell is supplied in the form of flat geocell panels which are expanded on site to form a mesh-like honeycomb grid of interconnected cells. The panels are secured to the ground using steel pins which are not available to purchase.

The road or parking area can be constructed once the roots have been covered by the geocell and filled with a granular material. The geocell ensures that any loads are spread laterally rather than applied vertically. This also minimises compaction beneath the roots line which would be harmful to the roots as they could become starved of oxygen and moisture. Without the cellular system, loads

We are looking to help provide you with the best possible value experience and to gather feedback, aggregated website usage data. You can find out more about the cookies we use and how to disable them in our [Cookie Policy](#). By using our website you agree that we may place cookies on the device used to access our website. [Close X](#)

An example of suitable ground protection within trees RPA would be the TERRAM Tree root protection geocell.

DRAFT

Prepared by Fred Nyberg and Robert Walton
Reviewed by Adam Sewell
Issued 24 March 2015

This document is for the sole use of the person or organisation for whom it has been prepared under the terms of an invitation or appointment by such person or organisation. Unless and to the extent allowed for under the terms of such invitation or appointment this document should not be copied or used or relied upon in whole or in part by third parties for any purpose whatsoever. If this document has been issued as a report under the terms of an appointment by such person or organisation, it is valid only at the time of its production. Alan Baxter & Associates LLP does not accept liability for any loss or damage arising from unauthorised use of this report.

If this document has been issued as a 'draft', it is issued solely for the purpose of client and/or team comment and must not be used for any other purpose without the written permission of Alan Baxter & Associates LLP.

Alan Baxter & Associates LLP is a limited liability partnership registered in England, number OC328839. Registered office: 75 Cowcross Street, London, EC1M 6EL.

© **Copyright** subsists in this document.

Prepared by Fred Nyberg and Robert Walton
Reviewed by Adam Sewell
Issued 24 March 2015

This document is for the sole use of the person or organisation for whom it has been prepared under the terms of an invitation or appointment by such person or organisation. Unless and to the extent allowed for under the terms of such invitation or appointment this document should not be copied or used or relied upon in whole or in part by third parties for any purpose whatsoever. If this document has been issued as a report under the terms of an appointment by such person or organisation, it is valid only at the time of its production. Alan Baxter & Associates LLP does not accept liability for any loss or damage arising from unauthorised use of this report.

If this document has been issued as a 'draft', it is issued solely for the purpose of client and/or team comment and must not be used for any other purpose without the written permission of Alan Baxter & Associates LLP.

Alan Baxter & Associates LLP is a limited liability partnership registered in England, number OC328839. Registered office: 75 Cowcross Street, London, EC1M 6EL.

© **Copyright** subsists in this document.