

T:\2332 Centre Point\02-Sheets\25 Series External Wall\2332(25)522_Ground-Mezzanine End Bay Mezzanine Detail.dgn
29/04/2013
2332
Conran

Double glazed unit
For performance specification of whole
glazing assembly refer to Wintech's
specification and window schedule

Existing floor finish to be retained

Galv steel fixing with mullion stub
connector fixed to RC slab

Bespoke Silver anodised cap for consistent
alignment of glass and capping with steel
below

EPDM by facade contractor bonded to concrete slab

2 hour floor-to-floor fire stopping in black
encasement

New granite cladding panel to match existing

Existing precast in-situ concrete
floor slab

OUTSIDE

INSIDE

EPDM by facade contractor bonded to concrete

Shadow gap detail between stone panel &
window frame maintained

Standard silver anodised aluminium box
section transom profile with pressure
plate fixing and silver anodised cap

Galv steel fixing with mullion stub
connector fixed to RC slab

Double glazed unit
For performance specification of whole
glazing assembly refer to Wintech's
specification and window schedule

1 CORE WINDOW GRANITE SPANDREL DETAIL 1:5

Notes

The cladding configuration shown is based on structural dimensions taken from the original design drawings
Structural dimensions are subject to confirmation by site survey
For floor build up details refer to drawing series (43) Floor Finishes

All dimensions must be checked on site and not scaled from this drawing. © Conran and Partners Limited

Rev	Date	Reason	By	Checked	Rev	Date	Reason	By	Checked
-	03.08.12	Stage D Draft	TG	AS					
A	31.08.12	Stage D	PG	AS					
B	30.04.13	Stage E	PG	AS					

Project: Centre Point
Client: Almacantar
Drawing title: Ground Floor and Mezzanine Details
Mezzanine Detail
Scale 1:5@A3 Date: August 2012 Drawn by: TG
Project number: 2332 Drawing No: (25)522 Rev: B
Status: STAGE E Checked by: AS

**CONRAN+
PARTNERS**
Architects Designers

LONDON OFFICE
Conran Building
22 Shad Thames,
London SE1 2YU
Telephone +44 (0) 20 7403 8899
Email cp@conran.com