

Appendix 1 – BS5837 Survey Key

BS 5837 Cat	Description
	Those of high quality and value: in such a condition as to be able to make a substantial contribution (> 40 years)
Α	
	Those trees of moderate quality and value: those in such a condition as to make a significant contribution (> 20 years)
В	
	Those trees of low quality and value: currently in an adequate condition to remain until new planting could be established (> 10 years)
С	
	Those in such a condition that any existing value would be lost within 10 years and which should, in the current context, be removed
U	regardless of development (< 10 years)

Note: Sub categories are denoted in the tree survey data (A1, B1, C2 etc.). You are referred to BS5837 for further detail if required.

Tree No.	T (tree), G (group), H (hedge), W (woodland) + Ref No.			
Species	Common Name			
Ht (m)	Measured height in metres			
DBH (m) Diameter at 1.5m above ground level				
No of stems	An indication of the trees form @1.5m (1 = single stem, m/s = multi-stemmed)			
Branch Spread	In m to cardinal points			
Cr Ht Clearance (m)	Overall height of lowest branches from the ground level on side of proposed development			
Life Stage Young, Semi-Mature, Early-Mature, Mature, Over-Mature				
General Observations	Observations on the condition of the tree(s)			
Tree Work Specification	Proposed tree works in accordance with BS3998			
BS Cat	See above			
Life Exp	Estimated remaining contribution in years.			
RPA Radius(m)	Radius of the trees Root Protection Area measured from the trunk to the edge of the RPA circle in metres			
RPA (m2)	Overall Root Protection Area in m2			



Appendix 2 – BS5837 Survey Key

Tree No.	Species	DBH (m)	No of Stems	Ht (m)	N W E S	BS Cat	Age Class	Life Expect	Cr Ht (m)	Observation	Recommendations	RPA (m2)	RPR (m)
T1	Box	0.21	1	7.6	2.9 1.8 1.6 1.8	C1	Μ	20-40	<1	Previous pruning wounds, very close to the building. Visually insignificant.to wider amenity.	Remove to facilitate development	18	2.4
T2	Acer	0.07	1	4	0.8 0.8 0.8 0.8	C1	Y	20-40	<2	Previously pruned. Small and visually insignificant to wider amenity.	Remove to facilitate development	2.5	1
ТЗ	Acer	0.09	M/S	3.4	1.8 1.8 1.8 1.8	C1	Μ	20-40	2	Pruned small and visually insignificant to wider amenity. Multi-stemmed from ground level.	No Works	3.7	1.1
T4	Cornus	0.07	1	3.1	1.2 1.2 1.2 1.2	C1	Y	20-40	2	Topped small and visually insignificant to wider amenity.	Remove to facilitate development	2.5	1
Τ5	Magnolia (grandiflora)	0.21	2	8.2	3 4.1 3 3.4	C1	Μ	20-40	2.2	Twin stemmed tree from 0.5m. Ivy and location hindered full inspection. Basal included union.	Remove to facilitate development	18	2.4
Т6	Ash	1.2	1	24	10 8 8 10	B1	Μ	<20	<4	Tree divides at 2.3m to 2 main stems. Decay pockets present in upper canopy. Inonotus hispidus noted and previous large branch lost in winter	Crown reduce by 3- 4m to reduce leverage on the areas of decay on the main stem.	651	14.4



Tree No.	Species	DBH (m)	No of Stems	Ht (m)	N W E S	BS Cat	Age Class	Life Expect	Cr Ht (m)	Observation	Recommendations	RPA (m2)	RPR (m)
										(2013) storms. Ivy covers lower stem hindering full inspection. Cable brace at 14/15m.	Monitor condition and fungal pathogen progress.		
Τ7	Lime	0.45	1	24	10 8 8 10	B1	Μ	20-40	<4	Previously topped with suppressed lean due to the presence of T6. Ivy hindered full inspection.	Monitor with a view to crown reduction by 2-3m within 5 years to address previous pruning wounds/ reduction	91.6	54
Т8	Lime	0.45	1	16	7 7 7 7	B1	Μ	20-40	<2	Previously topped with suppressed lean due to the presence of T6. Ivy hindered full inspection.	Monitor with a view to crown reduction by 2-3m within 5 years to address previous pruning wounds/ reduction	91.6	5.4
Т9	Sycamore	0.5	1	17.5	7 7 7 7	B1	Μ	20-40	<4	3 rd party tree unable to inspect	No Works	113	6
TG1	Irish Yew (x 2)	-	-	-	-	-	-	-	-	Below BS and CA size threshold	-	-	
TG2	Hornbeam (x 4)	0.10	4.3	4.3	1 1 1 1	C1	EM	20-40	<1	Topped/ pruned and managed as screen	No Works	4.5	1.2



Tree No.	Species	DBH (m)	No of Stems	Ht (m)	N W E S	BS Cat	Age Class	Life Expect	Cr Ht (m)	Observation	Recommendations	RPA (m2)	RPR (m)
SG1	Pittosporum x 1 & Privet x 1	0.13	M/S	5.8	2 2 2 2	C1	Μ	<20	<1	Shrubs	No Works	4.5	1.2



Appendix 3 – Tree Works Schedule

NOTE: All tree works to be undertaken in accordance with BS 3998:2010 'Tree work - Recommendations'.

Tree Surgery


Tree No.	Species	Proposed Tree Works	BS Cat
Т6	Ash	Crown reduce by 3-4m to reduce leverage on the areas of decay on the main stem. Monitor condition and fungal pathogen progress.	B1

Proposed Removal

Tree No.	Species	Proposed Tree Works	Observations	BS Cat
T1	Вох	Remove to facilitate development	Previous pruning wounds, very close to the building. Visually insignificant.to wider amenity.	С
Т2	Acer	Remove to facilitate development	Previously pruned. Small and visually insignificant to wider amenity.	С
T4	Cornus	Remove to facilitate development	Topped small and visually insignificant to wider amenity.	С
Т5	Magnolia (grandiflora)	Remove to facilitate development	Twin stemmed tree from 0.5m. Ivy and location hindered full inspection. Basal included union.	С



Appendix 4 - Tree Constraints Plan



	^{ance} A Tree No	Species	DBH (m)	No of Stems	Ht (m)	BS Cat	London NW3
	T1	Вох	0.21	1	7.6	Cat C1	William Carter Limited
	T2	Acer	0.07	1	4	C1	
	Т3	Acer	0.09	M/S	3.4	C1	
	T4	Cornus	0.07	1	3.1	C1	TITLE
	T5	Magnolia (grandiflora)	0.21	2	8.2	C1	Tree Constraints Plan (TCP)
Ground Floor	T6	Ash	1.2	1	24	B1	
	T7	Lime	0.45	1	24	B1	Job Scale DRG NO Revision 02008R 1:200 @ A3
	Т8	Lime	0.45	1	16	B1	Date Type 02008P -
	Т9	Sycamore	0.5	1	17.5	B1	31/01/14 TT.TCP.02008P.v1
	TG1	Irish Yew (x 2)	-	-	-	-	
	TG2	Hornbeam (x 4)	0.1	4.3	4.3	C1	
	SG1	Pittosporum x 1 & Privet x 1	0.13	M/S	5.8	C1	Tamla Trees consulting arborists