Project Title	42 Caversham Road
Location:	
Client:	
	S106 Estimate
Corresponden	
ce File:	Volker Highways

ESTIMATE	D/MEASURED BILL OF QUANTITIES				
ITEM	DESCRIPTION	QUANTITY	UNIT	SELECTED RATE	TOTAL
200.019	Take up or down and set aside for reuse				
	granite flat, edge or standard profile bus	25.00			
200.005	boarder kerb	35.00	m		
200.003	Take up or down and remove to Council Store off site precast concrete or york stone paving				
	slabs any size or type including steel reinforced				
	between 66 and 80mm thick		m2		
200.006	Take up or down and remove to tip off site				
	precast concrete or york stone paving slabs				
	any size or type including steel reinforced				
500 400	between 66 and 80mm thick	105.00	m2		
500.106	Lowering the level of any class of cover and				
	frames in the footway, area of cover exceeding				
	0.1m2 but not exceeding 0.5m2, exceeding 50mm but not exceeding 150mm.	5.00	nr		
500.107	Lowering the level of any class of cover and	0.00			
	frames in the footway, area of covers				
	exceeding 0.5m2 but not exceeding 1.0m2,				
	50mm or less	4.00	nr		
600.001	Excavation of any material in footways, verges		_		
600.007	and other pedestrian areas	21.00	m3		
600.007	Extra over excavation for excavation in hard				
	material in footways, verges and other pedestrian areas	3.00	m3		
600.012	Disposal of any material.(except class U1B and	0.00	1110		
	U2 material)	24.00	m3		
600.020	Completion of formation on material other than				
	Class 1C, 6B or rock in cuttings	105.00	m2		
1100.031	Remove from set aside area and relay flat				
	granite kerb, laid straight or curved exceeding	0.00			
1100.052	12 metres radius	0.00	m		
1100.052	65mm thick Artificial Stone Paving, any BS size				
	A,B,C or D on existing base or base measured separately and sand bedding 30mm thick				
	separately and saild bedding somm thick	105.00	m2		
1100.080	100mm ST1 concrete base in footways	105.00	m2		
1100.079	Extra and any item of paving sand bedding				
	30mm thick for sand cement mortar	105.00	m2		
1100.077	Extra over any item of surface course in				
	footways laid on existing layer for Tack coat of				
	bituminous spray class K1-40 of 0.4 to 0.6 litres		m2		
1100.112	per m² Additional ST1 concrete for any kerbs,		1112		
	channels or edgings	1.00	m3		
700.019	Stone Mastic Asphalt binder course (SMA 14				
	bin 40/60 des WRT1) 55mm thick in				
	carriagway (Ref Bi2S)	0.00	m2		
700.029	Thin Surface course Systems (TSCS 14)		_		
700.020	40mm thick in carriageway (Ref ST14)	0.00	m2		
700.039	Tack coat (K1-40 Bitumen emulsion, rate of	0.00	m2		
	spread 0.4-0.6 l/m²)	0.00	1112		
	1		•	Sub Total	
	Contractor Adjustment		%	£0.00	
	Fees		%	£0.00	
	Contingencies		%	£0.00	

Produced By:	Yuksel Arikan	Date:31.03.16	
Checked by:		Date	
Approved by:		Date	
Revision:		Date	

GRAND TOTAL £9,249.68