					Printed on:	21/04/2016	09:05:06	
Application No:	Consultees Name:	Consultees Addr:	Received:	Comment:	Response:			
2016/1680/P	Mark R. Nevard, C.Eng. M.I.C.E.	71 Flask Walk Hampstead London NW3 1ET	20/04/2016 17:47:04	COMMNT	proposal for trench sheeting to retain the earth while the wall is demolished is sound, should not be strutted off the pavement side, difficult anyway whilst demolishing the sheeting and the pavement, but should be held back by tiebacks to simple anchor plate behind, as are the existing tie rods. The main concern of The Flask Walk Neighbourhood Association is the need to main access along this narrow width between the wall and the drop down to the carriageway with details of the remaining width for pedestrians during the work is necessary. You	concern of The Flask Walk Neighbourhood Association is the need to maintain pedestrian ng this narrow width between the wall and the drop down to the carriageway. A cross section is of the remaining width for pedestrians during the work is necessary. You will note that safe width of pavement opposite, nor can pedestrians be asked to climb down to the road		