

T 0 1 26/06/15 Stage E Tender Issue

REV DATE DESCRIPTION


CONSULTANTS	
CLIENT:	Stanley Sidings
CONTRACTOR:	-
STRUCTURAL ENGINEER:	Walsh Group
MECHANICAL ENGINEER:	Hoare Lea
COST CONSULTANT:	Gardiner & Theobald
PROJECT MANAGER:	Gardiner & Theobald
ACOUSTIC CONSULTANT:	Hoare Lea
TRANSPORT CONSULTANT:	Arup
PLANNING CONSULTANT:	Gerald Eve
LANDSCAPE ARCHITECT:	Fabrik
CDM CO-ORDINATOR:	MSA Safety

1. Do not scale from this drawing. . All dimensions to be checked on site by the contractor and such dimensions to

be his responsibility. Report all drawing errors, omissions and discrepancies to the architect.

3. This document may be issued in an uncontrolled CAD format to enable others to use it as background information to make alterations and/or additions. In that instance the file will be accompanied by a PDF version. It is for those making

such alterations and additions to ensure that they make use of current background AHMM Ltd accepts no liability for any such alterations or additions to the background information or arising out of changes to background information which occur prior to alterations of additions being made.




ALLFORD HALL MONAGHAN MORRIS

ARCHITECTS Ltd 5-23 OLD STREET, LONDON, EC1V 9HL TEL 020 7251 5261 FAX 020 7251 5123 WEB WWW.AHMM.CO.UK

CAMDEN LOCK VILLAGE

drawing title / location WINDOW HEAD AND CILL DETAILS

NL KH 1:5@A1 TENDER CX_(21)_ 6001 |T01|



Glass balustrade as L10/331

Window system as L10/331

Window cill as L10/331

Cavity tray as F30/371


Weep holes as F30/130

02 DETAILED PLAN_C2 TYPICAL WINDOW CILL

Cavity fire barrier as P12/313

continuous seal

VCL - tape and jointed for complete



Insitu concrete slab to structural engineers details

WALL BUILDUP

continuous seal

2No. acoustic plasterboardVapour barrier as P10/311

- Cement Board as H20/151 - Breather membrane as P10/320

- Lightweight steel frame as G10/151 - In -fill mineral wool as P10/191A

- Partial fill cavity insulation as F30/156

VCL - tape and jointed for complete

All window junctions to allow full EPDM seals

MVHR unit and ventilation grille (with insect and

Window system as L10/331