## MICHAEL CHESTER & PARTNERS Consulting Civil and Structural Engineers 8 Hale Lane London NW7 3NX tel 020 8959 9119 fax 020 8959 9662 mail@michaelchester.co.uk

Our ref 15184

Langland Mansions Management Company c/o LRM 9A Macklin Street London WC2B 5NE

01.12.2015

**Dear Sirs** 

## LANGLAND MANSIONS Finchley Road. Boundary Retaining Walls

Further to viewing site I confirm that the boundary retaining walls along Langland Gardens and Finchley Road are in places in imminent danger of collapse due to the trees growing behind them.

Please find attached my drawing15184/01 which shows the damage to the Finchley Road retaining walls.

The drawing shows the verticality of the walls at the point measured. Please note that worst out of plumb section of wall is under the trees T3, T4 and T5 where the wall is 100 mm out of plumb immediately behind the bus shelter. The wall appears to be one brick thick at the top and might thicken lower down, never the less 100mm out of plumb is excessive and cause for immediate concern. I have no doubt that the failure of this wall is predominantly due to physical pressure from these trees. The significant lean of the trees is much the same as seen due to landslip on sloping sites. As the trees get bigger they will push the wall out further and the trunks will lean more. It is my opinion that the present outward movement of the retaining walls must not be allowed to continue.

The trees should be removed as quickly as possible.

I understand that this is a conservation area and so you will need to liaise urgently with the Council for the necessary consents. I append 3 photos which I hope will assist. You can scroll in for better detail.

Yours faithfully

Michael Chester

Michael Chester For and on behalf of Michael Chester and Partners LLP





Langland Gardens Walls

Continued page 2

Our Ref: 15184 Page 2 of 2



Finchley Road Wall