

PRICE & MYERS

30 Newman Street London W1T 1LT
Tel: 020 7631 5128 Fax: 020 7462 1390
Email: mt Tyler@pricemyers.com
www.pricemyers.com

Structural Calculations

For

17 Croftdown Road
NW5 1EL
London

Job No. 24555

Contents

Project description	0.1
Standards used	0.2
Structural Calculations	0.3

Project Description

24555/0.1

The existing structure is a three storey semi-detached house which includes 'room in the roof' accommodation. There is a partial basement some 2m deep over the rear foot print of the main house and an undercroft about 1.1m deep under the front of the main house. The construction consists primarily of masonry load bearing walls on corbelled foundations. The spin wall has been replaced with a two story steel box frame. The remaining walls, floors and roof are timber framed.

It is proposed to deepen the existing basement to the rear of the house by about 0.5m and deepen the undercroft by about 2.0m with two light wells out the front and back of the structure. There is to be a new reinforced concrete ground bearing slab on the lower ground level. The existing masonry load bearing foundations are to be underpinned by concrete extended down to the lower ground floor level.


Standards Used

24555 /0.2


BS 5268 Pt2 2002	Structural Use of Timber
BS 5628 Pt1 2005	Code of Practice for Structural Use of Unreinforced Masonry
BS 5950 Pt1 2000	Structural Use of Steelwork
BS 6399 Pt1 1996	Code of Practice for Dead and Imposed Loads
BS 6399 Pt2 1997	Code of Practice for Wind Loads
BS 6399 Pt3 1988	Code of Practice for Imposed Roof Loads
BS 8110 Pt1 1997	Structural Use of Concrete – Code of practice for design and construction
BS 8110 Pt2 1985	Structural Use of Concrete – Code of practice for special circumstances

UNDERPINS - FRONT ROOM

205 mm SSL LOWER GROUND TO GROUND SSL



RETAINING H. = $9.57 - 7.17$
 = 2.4m



Sur charge = 5 kPa


GNT = Ground level

Mas. Load = $[0.215 \times \sim 10m \times 18] \times 80\%$ 20% windows etc
 = 30 kN/m

Project Croftdown Road				Job no. 24555	
Calcs for Typical Underpin				Start page no./Revision 1	
Calcs by PJG	Calcs date 03/05/2016	Checked by	Checked date	Approved by	Approved date

RETAINING WALL ANALYSIS (BS 8002:1994)

TEDDS calculation version 1.2.01.06



Wall details

Retaining wall type
 Height of retaining wall stem
 Thickness of wall stem
 Length of toe
 Length of heel
 Overall length of base
 Thickness of base
 Depth of downstand
 Position of downstand
 Thickness of downstand
 Height of retaining wall
 Depth of cover in front of wall
 Depth of unplanned excavation
 Height of ground water behind wall
 Height of saturated fill above base
 Density of wall construction
 Density of base construction
 Angle of rear face of wall
 Angle of soil surface behind wall
 Effective height at virtual back of wall

Cantilever propped at base

$h_{\text{stem}} = 2500$ mm
 $t_{\text{wall}} = 200$ mm
 $l_{\text{toe}} = 1400$ mm
 $l_{\text{heel}} = 250$ mm
 $l_{\text{base}} = l_{\text{toe}} + l_{\text{heel}} + t_{\text{wall}} = 1850$ mm
 $t_{\text{base}} = 300$ mm
 $d_{\text{ds}} = 0$ mm
 $l_{\text{ds}} = 700$ mm
 $t_{\text{ds}} = 300$ mm
 $h_{\text{wall}} = h_{\text{stem}} + t_{\text{base}} + d_{\text{ds}} = 2800$ mm
 $d_{\text{cover}} = 0$ mm
 $d_{\text{exc}} = 0$ mm
 $h_{\text{water}} = 2800$ mm
 $h_{\text{sat}} = \max(h_{\text{water}} - t_{\text{base}} - d_{\text{ds}}, 0 \text{ mm}) = 2500$ mm
 $\gamma_{\text{wall}} = 23.6$ kN/m³
 $\gamma_{\text{base}} = 23.6$ kN/m³
 $\alpha = 90.0$ deg
 $\beta = 0.0$ deg
 $h_{\text{eff}} = h_{\text{wall}} + l_{\text{heel}} \times \tan(\beta) = 2800$ mm

Retained material details

Mobilisation factor $M = 1.5$

	Project Croftdown Road				Job no. 24555	
	Calcs for Typical Underpin				Start page no./Revision 2	
	Calcs by P J G	Calcs date 03/05/2016	Checked by	Checked date	Approved by	Approved date

Moist density of retained material $\gamma_m = 20.0 \text{ kN/m}^3$
Saturated density of retained material $\gamma_s = 20.0 \text{ kN/m}^3$
Design shear strength $\phi' = 22.0 \text{ deg}$
Angle of wall friction $\delta = 22.0 \text{ deg}$

Base material details

Hard clay
Moist density $\gamma_{mb} = 18.0 \text{ kN/m}^3$
Design shear strength $\phi'_b = 22.0 \text{ deg}$
Design base friction $\delta_b = 22.0 \text{ deg}$
Allowable bearing pressure $P_{\text{bearing}} = 110 \text{ kN/m}^2$

Using Rankine theory

Active pressure coefficient for retained material $K_a = (\cos(\beta) - \sqrt{[(\cos(\beta))^2 - (\cos(\phi'))^2]}) / (\cos(\beta) + \sqrt{[(\cos(\beta))^2 - (\cos(\phi'))^2]})$
 $K_a = 0.455$


Passive pressure coefficient for base material $K_p = (1 + \sqrt{[1 - (\cos(\phi'_b))^2]}) / (1 - \sqrt{[1 - (\cos(\phi'_b))^2]}) = 2.198$

At-rest pressure

At-rest pressure for retained material $K_0 = 1 - \sin(\phi') = 0.625$

Loading details

Surcharge load on plan Surcharge = 5.0 kN/m²
Applied vertical dead load on wall $W_{\text{dead}} = 30.0 \text{ kN/m}$
Applied vertical live load on wall $W_{\text{live}} = 0.0 \text{ kN/m}$
Position of applied vertical load on wall $l_{\text{load}} = 1700 \text{ mm}$
Applied horizontal dead load on wall $F_{\text{dead}} = 0.0 \text{ kN/m}$
Applied horizontal live load on wall $F_{\text{live}} = 0.0 \text{ kN/m}$
Height of applied horizontal load on wall $h_{\text{load}} = 0 \text{ mm}$



Project			Croftdown Road		Job no.		24555				
Calcs for			Typical Underpin			Start page no./Revision			3		
Calcs by		Calcs date		Checked by		Checked date		Approved by		Approved date	
P J G		03/05/2016									

Loads shown in kN/m, pressures shown in kN/m²

Vertical forces on wall

Wall stem

$$W_{\text{wall}} = h_{\text{stem}} \times t_{\text{wall}} \times \gamma_{\text{wall}} = \mathbf{11.8 \text{ kN/m}}$$

Wall base

$$W_{\text{base}} = l_{\text{base}} \times t_{\text{base}} \times \gamma_{\text{base}} = \mathbf{13.1 \text{ kN/m}}$$

Surcharge

$$W_{\text{sur}} = \text{Surcharge} \times l_{\text{heel}} = \mathbf{1.3 \text{ kN/m}}$$

Saturated backfill

$$W_s = l_{\text{heel}} \times h_{\text{sat}} \times \gamma_s = \mathbf{12.5 \text{ kN/m}}$$

Applied vertical load

$$W_v = W_{\text{dead}} + W_{\text{live}} = \mathbf{30 \text{ kN/m}}$$

Total vertical load

$$W_{\text{total}} = W_{\text{wall}} + W_{\text{base}} + W_{\text{sur}} + W_s + W_v = \mathbf{68.6 \text{ kN/m}}$$

Horizontal forces on wall

Surcharge

$$F_{\text{sur}} = K_a \times \text{Surcharge} \times h_{\text{eff}} = \mathbf{6.4 \text{ kN/m}}$$

Saturated backfill

$$F_s = 0.5 \times K_a \times (\gamma_s - \gamma_{\text{water}}) \times h_{\text{water}}^2 = \mathbf{18.2 \text{ kN/m}}$$

Water

$$F_{\text{water}} = 0.5 \times h_{\text{water}}^2 \times \gamma_{\text{water}} = \mathbf{38.5 \text{ kN/m}}$$

Total horizontal load

$$F_{\text{total}} = F_{\text{sur}} + F_s + F_{\text{water}} = \mathbf{63 \text{ kN/m}}$$

Calculate propping force

Passive resistance of soil in front of wall

$$F_p = 0.5 \times K_p \times (d_{\text{cover}} + t_{\text{base}} + d_{\text{ds}} - d_{\text{exc}})^2 \times \gamma_{\text{mb}} = \mathbf{1.8 \text{ kN/m}}$$

Propping force

$$F_{\text{prop}} = \max(F_{\text{total}} - F_p - (W_{\text{total}} - W_{\text{sur}}) \times \tan(\delta_b), 0 \text{ kN/m})$$

$$F_{\text{prop}} = \mathbf{34.0 \text{ kN/m}}$$

Overturning moments

Surcharge

$$M_{\text{sur}} = F_{\text{sur}} \times (h_{\text{eff}} - 2 \times d_{\text{ds}}) / 2 = \mathbf{8.9 \text{ kNm/m}}$$

Saturated backfill

$$M_s = F_s \times (h_{\text{water}} - 3 \times d_{\text{ds}}) / 3 = \mathbf{17 \text{ kNm/m}}$$

Water

$$M_{\text{water}} = F_{\text{water}} \times (h_{\text{water}} - 3 \times d_{\text{ds}}) / 3 = \mathbf{35.9 \text{ kNm/m}}$$

Total overturning moment

$$M_{\text{ot}} = M_{\text{sur}} + M_s + M_{\text{water}} = \mathbf{61.8 \text{ kNm/m}}$$

Restoring moments

Wall stem

$$M_{\text{wall}} = W_{\text{wall}} \times (l_{\text{toe}} + t_{\text{wall}} / 2) = \mathbf{17.7 \text{ kNm/m}}$$

Wall base

$$M_{\text{base}} = W_{\text{base}} \times l_{\text{base}} / 2 = \mathbf{12.1 \text{ kNm/m}}$$

Saturated backfill

$$M_{s_r} = W_s \times (l_{\text{base}} - l_{\text{heel}} / 2) = \mathbf{21.6 \text{ kNm/m}}$$

Design vertical dead load

$$M_{\text{dead}} = W_{\text{dead}} \times l_{\text{load}} = \mathbf{51 \text{ kNm/m}}$$

Total restoring moment

$$M_{\text{rest}} = M_{\text{wall}} + M_{\text{base}} + M_{s_r} + M_{\text{dead}} = \mathbf{102.4 \text{ kNm/m}}$$

Check bearing pressure

Surcharge

$$M_{\text{sur}_r} = W_{\text{sur}} \times (l_{\text{base}} - l_{\text{heel}} / 2) = \mathbf{2.2 \text{ kNm/m}}$$

Total moment for bearing

$$M_{\text{total}} = M_{\text{rest}} - M_{\text{ot}} + M_{\text{sur}_r} = \mathbf{42.8 \text{ kNm/m}}$$

Total vertical reaction

$$R = W_{\text{total}} = \mathbf{68.6 \text{ kN/m}}$$

Distance to reaction

$$x_{\text{bar}} = M_{\text{total}} / R = \mathbf{623 \text{ mm}}$$

Eccentricity of reaction

$$e = \text{abs}((l_{\text{base}} / 2) - x_{\text{bar}}) = \mathbf{302 \text{ mm}}$$

Reaction acts within middle third of base

Bearing pressure at toe

$$p_{\text{toe}} = (R / l_{\text{base}}) + (6 \times R \times e / l_{\text{base}}^2) = \mathbf{73.5 \text{ kN/m}^2}$$

Bearing pressure at heel

$$p_{\text{heel}} = (R / l_{\text{base}}) - (6 \times R \times e / l_{\text{base}}^2) = \mathbf{0.8 \text{ kN/m}^2}$$

PASS - Maximum bearing pressure is less than allowable bearing pressure

Project Croftdown Road			Job no. 24555		
Calcs for Typical Underpin			Start page no./Revision 4		
Calcs by PJG	Calcs date 03/05/2016	Checked by	Checked date	Approved by	Approved date

RETAINING WALL DESIGN (BS 8002:1994)

TEDDS calculation version 1.2.01.06

Ultimate limit state load factors

Dead load factor $\gamma_{f,d} = 1.4$
Live load factor $\gamma_{f,l} = 1.6$
Earth and water pressure factor $\gamma_{f,e} = 1.4$

Factored vertical forces on wall

Wall stem $W_{wall,f} = \gamma_{f,d} \times h_{stem} \times t_{wall} \times \gamma_{wall} = 16.5 \text{ kN/m}$
Wall base $W_{base,f} = \gamma_{f,d} \times l_{base} \times t_{base} \times \gamma_{base} = 18.3 \text{ kN/m}$
Surcharge $W_{sur,f} = \gamma_{f,l} \times \text{Surcharge} \times l_{heel} = 2 \text{ kN/m}$
Saturated backfill $W_{s,f} = \gamma_{f,d} \times l_{heel} \times h_{sat} \times \gamma_s = 17.5 \text{ kN/m}$
Applied vertical load $W_{v,f} = \gamma_{f,d} \times W_{dead} + \gamma_{f,l} \times W_{live} = 42 \text{ kN/m}$
Total vertical load $W_{total,f} = W_{wall,f} + W_{base,f} + W_{sur,f} + W_{s,f} + W_{v,f} = 96.4 \text{ kN/m}$

Factored horizontal active forces on wall

Surcharge $F_{sur,f} = \gamma_{f,l} \times K_a \times \text{Surcharge} \times h_{eff} = 10.2 \text{ kN/m}$
Saturated backfill $F_{s,f} = \gamma_{f,e} \times 0.5 \times K_a \times (\gamma_s - \gamma_{water}) \times h_{water}^2 = 25.4 \text{ kN/m}$
Water $F_{water,f} = \gamma_{f,e} \times 0.5 \times h_{water}^2 \times \gamma_{water} = 53.8 \text{ kN/m}$
Total horizontal load $F_{total,f} = F_{sur,f} + F_{s,f} + F_{water,f} = 89.5 \text{ kN/m}$

Calculate propping force

Passive resistance of soil in front of wall $F_{p,f} = \gamma_{f,e} \times 0.5 \times K_p \times (d_{cover} + t_{base} + d_{ds} - d_{exc})^2 \times \gamma_{mb} = 2.5 \text{ kN/m}$
Propping force $F_{prop,f} = \max(F_{total,f} - F_{p,f} - (W_{total,f} - w_{sur,f}) \times \tan(\delta_b), 0 \text{ kN/m})$
 $F_{prop,f} = 48.9 \text{ kN/m}$

Factored overturning moments

Surcharge $M_{sur,f} = F_{sur,f} \times (h_{eff} - 2 \times d_{ds}) / 2 = 14.3 \text{ kNm/m}$
Saturated backfill $M_{s,f} = F_{s,f} \times (h_{water} - 3 \times d_{ds}) / 3 = 23.7 \text{ kNm/m}$
Water $M_{water,f} = F_{water,f} \times (h_{water} - 3 \times d_{ds}) / 3 = 50.2 \text{ kNm/m}$
Total overturning moment $M_{ot,f} = M_{sur,f} + M_{s,f} + M_{water,f} = 88.3 \text{ kNm/m}$

Restoring moments

Wall stem $M_{wall,f} = w_{wall,f} \times (l_{toe} + t_{wall} / 2) = 24.8 \text{ kNm/m}$
Wall base $M_{base,f} = w_{base,f} \times l_{base} / 2 = 17 \text{ kNm/m}$
Surcharge $M_{sur,r,f} = w_{sur,f} \times (l_{base} - l_{heel} / 2) = 3.5 \text{ kNm/m}$
Saturated backfill $M_{s,r,f} = w_{s,f} \times (l_{base} - l_{heel} / 2) = 30.2 \text{ kNm/m}$
Design vertical load $M_{v,f} = W_{v,f} \times l_{load} = 71.4 \text{ kNm/m}$
Total restoring moment $M_{rest,f} = M_{wall,f} + M_{base,f} + M_{sur,r,f} + M_{s,r,f} + M_{v,f} = 146.8 \text{ kNm/m}$

Factored bearing pressure

Total moment for bearing $M_{total,f} = M_{rest,f} - M_{ot,f} = 58.5 \text{ kNm/m}$
Total vertical reaction $R_f = W_{total,f} = 96.4 \text{ kN/m}$
Distance to reaction $x_{bar,f} = M_{total,f} / R_f = 607 \text{ mm}$
Eccentricity of reaction $e_f = \text{abs}((l_{base} / 2) - x_{bar,f}) = 318 \text{ mm}$

Reaction acts outside middle third of base

Bearing pressure at toe $p_{toe,f} = R_f / (1.5 \times x_{bar,f}) = 105.8 \text{ kN/m}^2$
Bearing pressure at heel $p_{heel,f} = 0 \text{ kN/m}^2 = 0 \text{ kN/m}^2$
Rate of change of base reaction $\text{rate} = p_{toe,f} / (3 \times x_{bar,f}) = 58.06 \text{ kN/m}^2/\text{m}$
Bearing pressure at stem / toe $p_{stem_toe,f} = \max(p_{toe,f} - (\text{rate} \times l_{toe}), 0 \text{ kN/m}^2) = 24.5 \text{ kN/m}^2$

Project Croftdown Road				Job no. 24555	
Calcs for Typical Underpin				Start page no./Revision 5	
Calcs by PJG	Calcs date 03/05/2016	Checked by	Checked date	Approved by	Approved date

Bearing pressure at mid stem $p_{stem_mid_f} = \max(p_{toe_f} - (\text{rate} \times (l_{toe} + t_{wall} / 2)), 0 \text{ kN/m}^2) = \mathbf{18.7 \text{ kN/m}^2}$
 Bearing pressure at stem / heel $p_{stem_heel_f} = \max(p_{toe_f} - (\text{rate} \times (l_{toe} + t_{wall})), 0 \text{ kN/m}^2) = \mathbf{12.9 \text{ kN/m}^2}$

Design of reinforced concrete retaining wall toe (BS 8002:1994)

Material properties

Characteristic strength of concrete $f_{cu} = \mathbf{40 \text{ N/mm}^2}$
 Characteristic strength of reinforcement $f_y = \mathbf{500 \text{ N/mm}^2}$

Base details


Minimum area of reinforcement $k = \mathbf{0.00 \%}$
 Cover to reinforcement in toe $C_{toe} = \mathbf{40 \text{ mm}}$

Calculate shear for toe design

Shear from bearing pressure $V_{toe_bear} = (p_{toe_f} + p_{stem_toe_f}) \times l_{toe} / 2 = \mathbf{91.2 \text{ kN/m}}$
 Shear from weight of base $V_{toe_wt_base} = \gamma_{f_d} \times \gamma_{base} \times l_{toe} \times t_{base} = \mathbf{13.9 \text{ kN/m}}$
 Total shear for toe design $V_{toe} = V_{toe_bear} - V_{toe_wt_base} = \mathbf{77.3 \text{ kN/m}}$

Calculate moment for toe design

Moment from bearing pressure $M_{toe_bear} = (2 \times p_{toe_f} + p_{stem_mid_f}) \times (l_{toe} + t_{wall} / 2)^2 / 6 = \mathbf{86.3 \text{ kNm/m}}$
 Moment from weight of base $M_{toe_wt_base} = (\gamma_{f_d} \times \gamma_{base} \times t_{base} \times (l_{toe} + t_{wall} / 2)^2 / 2) = \mathbf{11.2 \text{ kNm/m}}$
 Total moment for toe design $M_{toe} = M_{toe_bear} - M_{toe_wt_base} = \mathbf{75.2 \text{ kNm/m}}$



Check toe in bending

Width of toe $b = \mathbf{1000 \text{ mm/m}}$
 Depth of reinforcement $d_{toe} = t_{base} - C_{toe} - (\phi_{toe} / 2) = \mathbf{252.0 \text{ mm}}$
 Constant $K_{toe} = M_{toe} / (b \times d_{toe}^2 \times f_{cu}) = \mathbf{0.030}$

Compression reinforcement is not required

Lever arm $Z_{toe} = \min(0.5 + \sqrt{(0.25 - (\min(K_{toe}, 0.225) / 0.9))}, 0.95) \times d_{toe}$
 $Z_{toe} = \mathbf{239 \text{ mm}}$

Area of tension reinforcement required $A_{s_toe_des} = M_{toe} / (0.87 \times f_y \times Z_{toe}) = \mathbf{722 \text{ mm}^2/\text{m}}$
 Minimum area of tension reinforcement $A_{s_toe_min} = k \times b \times t_{base} = \mathbf{0 \text{ mm}^2/\text{m}}$
 Area of tension reinforcement required $A_{s_toe_req} = \text{Max}(A_{s_toe_des}, A_{s_toe_min}) = \mathbf{722 \text{ mm}^2/\text{m}}$
 Reinforcement provided **16 mm dia.bars @ 200 mm centres**
 Area of reinforcement provided $A_{s_toe_prov} = \mathbf{1005 \text{ mm}^2/\text{m}}$

PASS - Reinforcement provided at the retaining wall toe is adequate

Check shear resistance at toe

Design shear stress $v_{toe} = V_{toe} / (b \times d_{toe}) = \mathbf{0.307 \text{ N/mm}^2}$
 Allowable shear stress $v_{adm} = \min(0.8 \times \sqrt{f_{cu}} / 1 \text{ N/mm}^2, 5) \times 1 \text{ N/mm}^2 = \mathbf{5.000 \text{ N/mm}^2}$

PASS - Design shear stress is less than maximum shear stress

Project Croftdown Road				Job no. 24555	
Calcs for Typical Underpin				Start page no./Revision 6	
Calcs by PJG	Calcs date 03/05/2016	Checked by	Checked date	Approved by	Approved date

From BS8110:Part 1:1997 – Table 3.8

Design concrete shear stress

$$V_{c_toe} = 0.611 \text{ N/mm}^2$$

$V_{toe} < V_{c_toe}$ - No shear reinforcement required

Design of reinforced concrete retaining wall heel (BS 8002:1994)

Material properties

Characteristic strength of concrete

$$f_{cu} = 40 \text{ N/mm}^2$$

Characteristic strength of reinforcement

$$f_y = 500 \text{ N/mm}^2$$

Base details

Minimum area of reinforcement

$$k = 0.00 \%$$

Cover to reinforcement in heel

$$C_{heel} = 30 \text{ mm}$$

Calculate shear for heel design

Shear from bearing pressure

$$V_{heel_bear} = p_{stem_heel_f} \times ((3 \times X_{bar_f}) - l_{toe} - t_{wall}) / 2 = 1.4 \text{ kN/m}$$

Shear from weight of base

$$V_{heel_wt_base} = \gamma_{fd} \times \gamma_{base} \times l_{heel} \times t_{base} = 2.5 \text{ kN/m}$$

Shear from weight of saturated backfill

$$V_{heel_wt_s} = W_{s_f} = 17.5 \text{ kN/m}$$

Shear from surcharge

$$V_{heel_sur} = W_{sur_f} = 2 \text{ kN/m}$$

Total shear for heel design

$$V_{heel} = -V_{heel_bear} + V_{heel_wt_base} + V_{heel_wt_s} + V_{heel_sur} = 20.5 \text{ kN/m}$$

Calculate moment for heel design

Moment from bearing pressure

$$M_{heel_bear} = p_{stem_mid_f} \times ((3 \times X_{bar_f}) - l_{toe} - t_{wall} / 2)^2 / 6 = 0.3 \text{ kNm/m}$$

Moment from weight of base

$$M_{heel_wt_base} = (\gamma_{fd} \times \gamma_{base} \times t_{base} \times (l_{heel} + t_{wall} / 2)^2 / 2) = 0.6 \text{ kNm/m}$$

Moment from weight of saturated backfill



$$M_{heel_wt_s} = W_{s_f} \times (l_{heel} + t_{wall}) / 2 = 3.9 \text{ kNm/m}$$

Moment from surcharge

$$M_{heel_sur} = W_{sur_f} \times (l_{heel} + t_{wall}) / 2 = 0.5 \text{ kNm/m}$$

Total moment for heel design

$$M_{heel} = -M_{heel_bear} + M_{heel_wt_base} + M_{heel_wt_s} + M_{heel_sur} = 4.7 \text{ kNm/m}$$



Check heel in bending

Width of heel

$$b = 1000 \text{ mm/m}$$

Depth of reinforcement

$$d_{heel} = t_{base} - C_{heel} - (\phi_{heel} / 2) = 265.0 \text{ mm}$$

Constant

$$K_{heel} = M_{heel} / (b \times d_{heel}^2 \times f_{cu}) = 0.002$$

Compression reinforcement is not required

Lever arm

$$Z_{heel} = \min(0.5 + \sqrt{(0.25 - (\min(K_{heel}, 0.225) / 0.9))}, 0.95) \times d_{heel}$$

$$Z_{heel} = 252 \text{ mm}$$

Area of tension reinforcement required

$$A_{s_heel_des} = M_{heel} / (0.87 \times f_y \times Z_{heel}) = 43 \text{ mm}^2/\text{m}$$

Minimum area of tension reinforcement

$$A_{s_heel_min} = k \times b \times t_{base} = 0 \text{ mm}^2/\text{m}$$

Area of tension reinforcement required

$$A_{s_heel_req} = \text{Max}(A_{s_heel_des}, A_{s_heel_min}) = 43 \text{ mm}^2/\text{m}$$

Reinforcement provided

10 mm dia.bars @ 1000 mm centres

Area of reinforcement provided

$$A_{s_heel_prov} = 79 \text{ mm}^2/\text{m}$$

PASS - Reinforcement provided at the retaining wall heel is adequate

Project Croftdown Road				Job no. 24555	
Calcs for Typical Underpin				Start page no./Revision 7	
Calcs by PJG	Calcs date 03/05/2016	Checked by	Checked date	Approved by	Approved date

Check shear resistance at heel

Design shear stress

$$v_{heel} = V_{heel} / (b \times d_{heel}) = \mathbf{0.078 \text{ N/mm}^2}$$

Allowable shear stress

$$v_{adm} = \min(0.8 \times \sqrt{f_{cu}} / 1 \text{ N/mm}^2, 5) \times 1 \text{ N/mm}^2 = \mathbf{5.000 \text{ N/mm}^2}$$

PASS - Design shear stress is less than maximum shear stress

From BS8110:Part 1:1997 – Table 3.8

Design concrete shear stress

$$V_{c_heel} = \mathbf{0.254 \text{ N/mm}^2}$$

$V_{heel} < V_{c_heel}$ - No shear reinforcement required

Design of reinforced concrete retaining wall stem (BS 8002:1994)

Material properties

Characteristic strength of concrete

$$f_{cu} = \mathbf{40 \text{ N/mm}^2}$$

Characteristic strength of reinforcement

$$f_y = \mathbf{500 \text{ N/mm}^2}$$

Wall details

Minimum area of reinforcement

$$k = \mathbf{0.00 \text{ \%}}$$

Cover to reinforcement in stem

$$c_{stem} = \mathbf{40 \text{ mm}}$$

Cover to reinforcement in wall

$$c_{wall} = \mathbf{40 \text{ mm}}$$

Factored horizontal active forces on stem

Surcharge

$$F_{s_sur_f} = \gamma_{f_l} \times K_a \times \text{Surcharge} \times (h_{eff} - t_{base} - d_{ds}) = \mathbf{9.1 \text{ kN/m}}$$

Saturated backfill

$$F_{s_s_f} = 0.5 \times \gamma_{f_e} \times K_a \times (\gamma_s - \gamma_{water}) \times h_{sat}^2 = \mathbf{20.3 \text{ kN/m}}$$

Water

$$F_{s_water_f} = 0.5 \times \gamma_{f_e} \times \gamma_{water} \times h_{sat}^2 = \mathbf{42.9 \text{ kN/m}}$$

Calculate shear for stem design

Shear at base of stem

$$V_{stem} = F_{s_sur_f} + F_{s_s_f} + F_{s_water_f} - F_{prop_f} = \mathbf{23.4 \text{ kN/m}}$$

Calculate moment for stem design

Surcharge

$$M_{s_sur} = F_{s_sur_f} \times (h_{stem} + t_{base}) / 2 = \mathbf{12.7 \text{ kNm/m}}$$

Saturated backfill


$$M_{s_s} = F_{s_s_f} \times h_{sat} / 3 = \mathbf{16.9 \text{ kNm/m}}$$

Water

$$M_{s_water} = F_{s_water_f} \times h_{sat} / 3 = \mathbf{35.8 \text{ kNm/m}}$$

Total moment for stem design

$$M_{stem} = M_{s_sur} + M_{s_s} + M_{s_water} = \mathbf{65.4 \text{ kNm/m}}$$



Check wall stem in bending

Width of wall stem

$$b = \mathbf{1000 \text{ mm/m}}$$

Depth of reinforcement

$$d_{stem} = t_{wall} - c_{stem} - (\phi_{stem} / 2) = \mathbf{152.0 \text{ mm}}$$

Constant

$$K_{stem} = M_{stem} / (b \times d_{stem}^2 \times f_{cu}) = \mathbf{0.071}$$

Compression reinforcement is not required

Lever arm

$$z_{stem} = \min(0.5 + \sqrt{(0.25 - (\min(K_{stem}, 0.225) / 0.9))}, 0.95) \times d_{stem}$$

$$z_{stem} = \mathbf{139 \text{ mm}}$$

Area of tension reinforcement required

$$A_{s_stem_des} = M_{stem} / (0.87 \times f_y \times z_{stem}) = \mathbf{1082 \text{ mm}^2/\text{m}}$$

Minimum area of tension reinforcement

$$A_{s_stem_min} = k \times b \times t_{wall} = \mathbf{0 \text{ mm}^2/\text{m}}$$

Area of tension reinforcement required

$$A_{s_stem_req} = \text{Max}(A_{s_stem_des}, A_{s_stem_min}) = \mathbf{1082 \text{ mm}^2/\text{m}}$$

Project		Croftdown Road		Job no.		24555	
Calcs for		Typical Underpin		Start page no./Revision		8	
Calcs by	Calcs date	Checked by	Checked date	Approved by	Approved date		
PJG	03/05/2016						

Reinforcement provided

16 mm dia.bars @ 200 mm centres

Area of reinforcement provided

$A_{s_stem_prov} = 1005 \text{ mm}^2/\text{m}$

FAIL - Reinforcement provided at the retaining wall stem is inadequate

Check shear resistance at wall stem

Design shear stress

$v_{stem} = V_{stem} / (b \times d_{stem}) = 0.154 \text{ N/mm}^2$

Allowable shear stress

$v_{adm} = \min(0.8 \times \sqrt{f_{cu}} / 1 \text{ N/mm}^2, 5) \times 1 \text{ N/mm}^2 = 5.000 \text{ N/mm}^2$

PASS - Design shear stress is less than maximum shear stress

From BS8110:Part 1:1997 – Table 3.8


Design concrete shear stress

$v_{c_stem} = 0.820 \text{ N/mm}^2$

$v_{stem} < v_{c_stem}$ - No shear reinforcement required

Project Croftdown Road				Job no. 24555	
Calcs for Typical Underpin				Start page no./Revision 9	
Calcs by PJG	Calcs date 03/05/2016	Checked by	Checked date	Approved by	Approved date

Indicative retaining wall reinforcement diagram




- Toe bars - 16 mm dia.@ 200 mm centres - (1005 mm²/m)
- Heel bars - 10 mm dia.@ 1000 mm centres - (79 mm²/m)
- Stem bars - 16 mm dia.@ 200 mm centres - (1005 mm²/m)

Project Croftdown Road				Job no. 24555	
Calcs for Small Retaining Wall				Start page no./Revision 1	
Calcs by PJG	Calcs date 29/04/2016	Checked by	Checked date	Approved by	Approved date

RETAINING WALL ANALYSIS (BS 8002:1994)

TEDDS calculation version 1.2.01.06



Wall details

Retaining wall type
 Height of retaining wall stem
 Thickness of wall stem
 Length of toe
 Length of heel
 Overall length of base
 Thickness of base
 Depth of downstand
 Position of downstand
 Thickness of downstand
 Height of retaining wall
 Depth of cover in front of wall
 Depth of unplanned excavation
 Height of ground water behind wall
 Height of saturated fill above base
 Density of wall construction
 Density of base construction
 Angle of rear face of wall
 Angle of soil surface behind wall
 Effective height at virtual back of wall

Cantilever propped at base

$h_{\text{stem}} = 1400$ mm
 $t_{\text{wall}} = 250$ mm
 $l_{\text{toe}} = 600$ mm
 $l_{\text{heel}} = 100$ mm
 $l_{\text{base}} = l_{\text{toe}} + l_{\text{heel}} + t_{\text{wall}} = 950$ mm
 $t_{\text{base}} = 300$ mm
 $d_{\text{ds}} = 0$ mm
 $l_{\text{ds}} = 400$ mm
 $t_{\text{ds}} = 300$ mm
 $h_{\text{wall}} = h_{\text{stem}} + t_{\text{base}} + d_{\text{ds}} = 1700$ mm
 $d_{\text{cover}} = 0$ mm
 $d_{\text{exc}} = 0$ mm
 $h_{\text{water}} = 1700$ mm
 $h_{\text{sat}} = \max(h_{\text{water}} - t_{\text{base}} - d_{\text{ds}}, 0 \text{ mm}) = 1400$ mm
 $\gamma_{\text{wall}} = 23.6$ kN/m³
 $\gamma_{\text{base}} = 23.6$ kN/m³
 $\alpha = 90.0$ deg
 $\beta = 0.0$ deg
 $h_{\text{eff}} = h_{\text{wall}} + l_{\text{heel}} \times \tan(\beta) = 1700$ mm

Retained material details

Mobilisation factor
 $M = 1.5$
 Moist density of retained material
 $\gamma_m = 20.0$ kN/m³

Project Croftdown Road				Job no. 24555	
Calcs for Small Retaining Wall				Start page no./Revision 2	
Calcs by PJG	Calcs date 29/04/2016	Checked by	Checked date	Approved by	Approved date

Saturated density of retained material $\gamma_s = 20.0 \text{ kN/m}^3$
 Design shear strength $\phi' = 22.0 \text{ deg}$
 Angle of wall friction $\delta = 22.0 \text{ deg}$

Base material details

Moist density $\gamma_{mb} = 20.0 \text{ kN/m}^3$
 Design shear strength $\phi'_b = 22.0 \text{ deg}$
 Design base friction $\delta_b = 22.0 \text{ deg}$
 Allowable bearing pressure $P_{\text{bearing}} = 110 \text{ kN/m}^2$

Using Coulomb theory

Active pressure coefficient for retained material

$$K_a = \sin(\alpha + \phi')^2 / (\sin(\alpha)^2 \times \sin(\alpha - \delta) \times [1 + \sqrt{(\sin(\phi' + \delta) \times \sin(\phi' - \beta) / (\sin(\alpha - \delta) \times \sin(\alpha + \beta)))]^2) = 0.396$$

Passive pressure coefficient for base material


$$K_p = \sin(90 - \phi'_b)^2 / (\sin(90 - \delta_b) \times [1 - \sqrt{(\sin(\phi'_b + \delta_b) \times \sin(\phi'_b) / (\sin(90 + \delta_b)))]^2) = 4.193$$

At-rest pressure

At-rest pressure for retained material $K_0 = 1 - \sin(\phi') = 0.625$

Loading details

Surcharge load on plan Surcharge = **5.0 kN/m²**
 Applied vertical dead load on wall $W_{\text{dead}} = 30.0 \text{ kN/m}$
 Applied vertical live load on wall $W_{\text{live}} = 0.0 \text{ kN/m}$
 Position of applied vertical load on wall $l_{\text{load}} = 725 \text{ mm}$
 Applied horizontal dead load on wall $F_{\text{dead}} = 0.0 \text{ kN/m}$
 Applied horizontal live load on wall $F_{\text{live}} = 0.0 \text{ kN/m}$
 Height of applied horizontal load on wall $h_{\text{load}} = 0 \text{ mm}$



Loads shown in kN/m, pressures shown in kN/m²

Project				Job no.	
Croftdown Road				24555	
Calcs for				Start page no./Revision	
Small Retaining Wall				3	
Calcs by	Calcs date	Checked by	Checked date	Approved by	Approved date
PJG	29/04/2016				

Vertical forces on wall

Wall stem	$W_{wall} = h_{stem} \times t_{wall} \times \gamma_{wall} = 8.3 \text{ kN/m}$
Wall base	$W_{base} = l_{base} \times t_{base} \times \gamma_{base} = 6.7 \text{ kN/m}$
Surcharge	$W_{sur} = \text{Surcharge} \times l_{heel} = 0.5 \text{ kN/m}$
Moist backfill to top of wall	$W_{m_w} = l_{heel} \times (h_{stem} - h_{sat}) \times \gamma_m = 0 \text{ kN/m}$
Saturated backfill	$W_s = l_{heel} \times h_{sat} \times \gamma_s = 2.8 \text{ kN/m}$
Applied vertical load	$W_v = W_{dead} + W_{live} = 30 \text{ kN/m}$
Total vertical load	$W_{total} = W_{wall} + W_{base} + W_{sur} + W_{m_w} + W_s + W_v = 48.3 \text{ kN/m}$

Horizontal forces on wall

Surcharge	$F_{sur} = K_a \times \cos(90 - \alpha + \delta) \times \text{Surcharge} \times h_{eff} = 3.1 \text{ kN/m}$
Moist backfill below water table	$F_{m_b} = K_a \times \cos(90 - \alpha + \delta) \times \gamma_m \times (h_{eff} - h_{water}) \times h_{water} = 0 \text{ kN/m}$
Saturated backfill	$F_s = 0.5 \times K_a \times \cos(90 - \alpha + \delta) \times (\gamma_s - \gamma_{water}) \times h_{water}^2 = 5.4 \text{ kN/m}$
Water	$F_{water} = 0.5 \times h_{water}^2 \times \gamma_{water} = 14.2 \text{ kN/m}$
Total horizontal load	$F_{total} = F_{sur} + F_{m_b} + F_s + F_{water} = 22.7 \text{ kN/m}$

Calculate propping force

Passive resistance of soil in front of wall	$F_p = 0.5 \times K_p \times \cos(\delta_b) \times (d_{cover} + t_{base} + d_{ds} - d_{exc})^2 \times \gamma_{mb} = 3.5 \text{ kN/m}$
Propping force	$F_{prop} = \max(F_{total} - F_p - (W_{total} - W_{sur}) \times \tan(\delta_b), 0 \text{ kN/m})$ $F_{prop} = 0.0 \text{ kN/m}$

Overturning moments

Surcharge	$M_{sur} = F_{sur} \times (h_{eff} - 2 \times d_{ds}) / 2 = 2.7 \text{ kNm/m}$
Moist backfill below water table	$M_{m_b} = F_{m_b} \times (h_{water} - 2 \times d_{ds}) / 2 = 0 \text{ kNm/m}$
Saturated backfill	$M_s = F_s \times (h_{water} - 3 \times d_{ds}) / 3 = 3.1 \text{ kNm/m}$
Water	$M_{water} = F_{water} \times (h_{water} - 3 \times d_{ds}) / 3 = 8 \text{ kNm/m}$
Total overturning moment	$M_{ot} = M_{sur} + M_{m_b} + M_s + M_{water} = 13.8 \text{ kNm/m}$

Restoring moments

Wall stem	$M_{wall} = W_{wall} \times (l_{toe} + t_{wall} / 2) = 6 \text{ kNm/m}$
Wall base	$M_{base} = W_{base} \times l_{base} / 2 = 3.2 \text{ kNm/m}$
Moist backfill	$M_{m_r} = (W_{m_w} \times (l_{base} - l_{heel} / 2) + W_{m_s} \times (l_{base} - l_{heel} / 3)) = 0 \text{ kNm/m}$
Saturated backfill	$M_{s_r} = W_s \times (l_{base} - l_{heel} / 2) = 2.5 \text{ kNm/m}$
Design vertical dead load	$M_{dead} = W_{dead} \times l_{load} = 21.8 \text{ kNm/m}$
Total restoring moment	$M_{rest} = M_{wall} + M_{base} + M_{m_r} + M_{s_r} + M_{dead} = 33.5 \text{ kNm/m}$

Check bearing pressure

Surcharge	$M_{sur_r} = W_{sur} \times (l_{base} - l_{heel} / 2) = 0.5 \text{ kNm/m}$
Total moment for bearing	$M_{total} = M_{rest} - M_{ot} + M_{sur_r} = 20.2 \text{ kNm/m}$
Total vertical reaction	$R = W_{total} = 48.3 \text{ kN/m}$
Distance to reaction	$X_{bar} = M_{total} / R = 417 \text{ mm}$
Eccentricity of reaction	$e = \text{abs}((l_{base} / 2) - X_{bar}) = 58 \text{ mm}$

Reaction acts within middle third of base

Bearing pressure at toe	$p_{toe} = (R / l_{base}) + (6 \times R \times e / l_{base}^2) = 69.3 \text{ kN/m}^2$
Bearing pressure at heel	$p_{heel} = (R / l_{base}) - (6 \times R \times e / l_{base}^2) = 32.3 \text{ kN/m}^2$

PASS - Maximum bearing pressure is less than allowable bearing pressure

Project			Croftdown Road		Job no.		24555				
Calcs for			Small Retaining Wall			Start page no./Revision			4		
Calcs by		Calcs date		Checked by		Checked date		Approved by		Approved date	
PJJ		29/04/2016									

RETAINING WALL DESIGN (BS 8002:1994)

TEDDS calculation version 1.2.01.06

Ultimate limit state load factors

Dead load factor $\gamma_{f,d} = 1.4$

Live load factor $\gamma_{f,l} = 1.6$

Earth and water pressure factor $\gamma_{f,e} = 1.4$

Factored vertical forces on wall

Wall stem $W_{wall,f} = \gamma_{f,d} \times h_{stem} \times t_{wall} \times \gamma_{wall} = 11.6 \text{ kN/m}$

Wall base $W_{base,f} = \gamma_{f,d} \times l_{base} \times t_{base} \times \gamma_{base} = 9.4 \text{ kN/m}$

Surcharge $W_{sur,f} = \gamma_{f,l} \times \text{Surcharge} \times l_{heel} = 0.8 \text{ kN/m}$

Moist backfill to top of wall $W_{m,w,f} = \gamma_{f,d} \times l_{heel} \times (h_{stem} - h_{sat}) \times \gamma_m = 0 \text{ kN/m}$

Saturated backfill $W_{s,f} = \gamma_{f,d} \times l_{heel} \times h_{sat} \times \gamma_s = 3.9 \text{ kN/m}$

Applied vertical load $W_{v,f} = \gamma_{f,d} \times W_{dead} + \gamma_{f,l} \times W_{live} = 42 \text{ kN/m}$

Total vertical load $W_{total,f} = W_{wall,f} + W_{base,f} + W_{sur,f} + W_{m,w,f} + W_{s,f} + W_{v,f} = 67.7 \text{ kN/m}$

Factored horizontal active forces on wall

Surcharge $F_{sur,f} = \gamma_{f,l} \times K_a \times \cos(90 - \alpha + \delta) \times \text{Surcharge} \times h_{eff} = 5 \text{ kN/m}$

Moist backfill below water table $F_{m,b,f} = \gamma_{f,e} \times K_a \times \cos(90 - \alpha + \delta) \times \gamma_m \times (h_{eff} - h_{water}) \times h_{water} = 0 \text{ kN/m}$

Saturated backfill $F_{s,f} = \gamma_{f,e} \times 0.5 \times K_a \times \cos(90 - \alpha + \delta) \times (\gamma_s - \gamma_{water}) \times h_{water}^2 = 7.6 \text{ kN/m}$

Water $F_{water,f} = \gamma_{f,e} \times 0.5 \times h_{water}^2 \times \gamma_{water} = 19.8 \text{ kN/m}$

Total horizontal load $F_{total,f} = F_{sur,f} + F_{m,b,f} + F_{s,f} + F_{water,f} = 32.4 \text{ kN/m}$

Calculate propping force

Passive resistance of soil in front of wall $F_{p,f} = \gamma_{f,e} \times 0.5 \times K_p \times \cos(\delta_b) \times (d_{cover} + t_{base} + d_{ds} - d_{exc})^2 \times \gamma_{mb} = 4.9 \text{ kN/m}$

Propping force $F_{prop,f} = \max(F_{total,f} - F_{p,f} - (W_{total,f} - W_{sur,f}) \times \tan(\delta_b), 0 \text{ kN/m})$

$F_{prop,f} = 0.5 \text{ kN/m}$

Factored overturning moments

Surcharge $M_{sur,f} = F_{sur,f} \times (h_{eff} - 2 \times d_{ds}) / 2 = 4.2 \text{ kNm/m}$

Moist backfill below water table $M_{m,b,f} = F_{m,b,f} \times (h_{water} - 2 \times d_{ds}) / 2 = 0 \text{ kNm/m}$

Saturated backfill $M_{s,f} = F_{s,f} \times (h_{water} - 3 \times d_{ds}) / 3 = 4.3 \text{ kNm/m}$

Water $M_{water,f} = F_{water,f} \times (h_{water} - 3 \times d_{ds}) / 3 = 11.2 \text{ kNm/m}$

Total overturning moment $M_{ot,f} = M_{sur,f} + M_{m,b,f} + M_{s,f} + M_{water,f} = 19.8 \text{ kNm/m}$

Restoring moments

Wall stem $M_{wall,f} = W_{wall,f} \times (l_{toe} + t_{wall} / 2) = 8.4 \text{ kNm/m}$

Wall base $M_{base,f} = W_{base,f} \times l_{base} / 2 = 4.5 \text{ kNm/m}$

Surcharge $M_{sur,r,f} = W_{sur,f} \times (l_{base} - l_{heel} / 2) = 0.7 \text{ kNm/m}$

Moist backfill $M_{m,r,f} = (W_{m,w,f} \times (l_{base} - l_{heel} / 2) + W_{m,s,f} \times (l_{base} - l_{heel} / 3)) = 0 \text{ kNm/m}$

Saturated backfill $M_{s,r,f} = W_{s,f} \times (l_{base} - l_{heel} / 2) = 3.5 \text{ kNm/m}$

Design vertical load $M_{v,f} = W_{v,f} \times l_{load} = 30.5 \text{ kNm/m}$

Total restoring moment $M_{rest,f} = M_{wall,f} + M_{base,f} + M_{sur,r,f} + M_{m,r,f} + M_{s,r,f} + M_{v,f} = 47.6 \text{ kNm/m}$

Factored bearing pressure

Total moment for bearing $M_{total,f} = M_{rest,f} - M_{ot,f} = 27.8 \text{ kNm/m}$

Total vertical reaction $R_f = W_{total,f} = 67.7 \text{ kN/m}$

Distance to reaction $X_{bar,f} = M_{total,f} / R_f = 410 \text{ mm}$

Eccentricity of reaction $e_f = \text{abs}((l_{base} / 2) - X_{bar,f}) = 65 \text{ mm}$

Project Croftdown Road				Job no. 24555	
Calcs for Small Retaining Wall				Start page no./Revision 5	
Calcs by PJG	Calcs date 29/04/2016	Checked by	Checked date	Approved by	Approved date

Reaction acts within middle third of base

Bearing pressure at toe	$p_{toe_f} = (R_f / l_{base}) + (6 \times R_f \times e_f / l_{base}^2) = 100.4 \text{ kN/m}^2$
Bearing pressure at heel	$p_{heel_f} = (R_f / l_{base}) - (6 \times R_f \times e_f / l_{base}^2) = 42.1 \text{ kN/m}^2$
Rate of change of base reaction	$rate = (p_{toe_f} - p_{heel_f}) / l_{base} = 61.40 \text{ kN/m}^2/\text{m}$
Bearing pressure at stem / toe	$p_{stem_toe_f} = \max(p_{toe_f} - (rate \times l_{toe}), 0 \text{ kN/m}^2) = 63.6 \text{ kN/m}^2$
Bearing pressure at mid stem	$p_{stem_mid_f} = \max(p_{toe_f} - (rate \times (l_{toe} + t_{wall} / 2)), 0 \text{ kN/m}^2) = 55.9 \text{ kN/m}^2$
Bearing pressure at stem / heel	$p_{stem_heel_f} = \max(p_{toe_f} - (rate \times (l_{toe} + t_{wall})), 0 \text{ kN/m}^2) = 48.2 \text{ kN/m}^2$

Design of reinforced concrete retaining wall toe (BS 8002:1994)

Material properties

Characteristic strength of concrete	$f_{cu} = 40 \text{ N/mm}^2$
Characteristic strength of reinforcement	$f_y = 500 \text{ N/mm}^2$

Base details


Minimum area of reinforcement	$k = 0.00 \%$
Cover to reinforcement in toe	$C_{toe} = 30 \text{ mm}$

Calculate shear for toe design

Shear from bearing pressure	$V_{toe_bear} = (p_{toe_f} + p_{stem_toe_f}) \times l_{toe} / 2 = 49.2 \text{ kN/m}$
Shear from weight of base	$V_{toe_wt_base} = \gamma_{fd} \times \gamma_{base} \times l_{toe} \times t_{base} = 5.9 \text{ kN/m}$
Total shear for toe design	$V_{toe} = V_{toe_bear} - V_{toe_wt_base} = 43.3 \text{ kN/m}$

Calculate moment for toe design

Moment from bearing pressure	$M_{toe_bear} = (2 \times p_{toe_f} + p_{stem_mid_f}) \times (l_{toe} + t_{wall} / 2)^2 / 6 = 22.5 \text{ kNm/m}$
Moment from weight of base	$M_{toe_wt_base} = (\gamma_{fd} \times \gamma_{base} \times t_{base} \times (l_{toe} + t_{wall} / 2)^2 / 2) = 2.6 \text{ kNm/m}$
Total moment for toe design	$M_{toe} = M_{toe_bear} - M_{toe_wt_base} = 19.9 \text{ kNm/m}$



Check toe in bending

Width of toe	$b = 1000 \text{ mm/m}$
Depth of reinforcement	$d_{toe} = t_{base} - C_{toe} - (\phi_{toe} / 2) = 264.0 \text{ mm}$
Constant	$K_{toe} = M_{toe} / (b \times d_{toe}^2 \times f_{cu}) = 0.007$

Compression reinforcement is not required

Lever arm	$Z_{toe} = \min(0.5 + \sqrt{(0.25 - (\min(K_{toe}, 0.225) / 0.9))}, 0.95) \times d_{toe}$
	$Z_{toe} = 251 \text{ mm}$

Area of tension reinforcement required	$A_{s_toe_des} = M_{toe} / (0.87 \times f_y \times Z_{toe}) = 182 \text{ mm}^2/\text{m}$
Minimum area of tension reinforcement	$A_{s_toe_min} = k \times b \times t_{base} = 0 \text{ mm}^2/\text{m}$
Area of tension reinforcement required	$A_{s_toe_req} = \text{Max}(A_{s_toe_des}, A_{s_toe_min}) = 182 \text{ mm}^2/\text{m}$
Reinforcement provided	12 mm dia.bars @ 200 mm centres
Area of reinforcement provided	$A_{s_toe_prov} = 565 \text{ mm}^2/\text{m}$

PASS - Reinforcement provided at the retaining wall toe is adequate

Project		Croftdown Road		Job no.		24555	
Calcs for		Small Retaining Wall		Start page no./Revision		6	
Calcs by	Calcs date	Checked by	Checked date	Approved by	Approved date		
PJG	29/04/2016						

Check shear resistance at toe

Design shear stress

$$v_{toe} = V_{toe} / (b \times d_{toe}) = \mathbf{0.164 \text{ N/mm}^2}$$

Allowable shear stress

$$v_{adm} = \min(0.8 \times \sqrt{f_{cu}} / 1 \text{ N/mm}^2, 5) \times 1 \text{ N/mm}^2 = \mathbf{5.000 \text{ N/mm}^2}$$

PASS - Design shear stress is less than maximum shear stress

From BS8110:Part 1:1997 – Table 3.8

Design concrete shear stress

$$v_{c_toe} = \mathbf{0.491 \text{ N/mm}^2}$$

$v_{toe} < v_{c_toe}$ - No shear reinforcement required

Design of reinforced concrete retaining wall heel (BS 8002:1994)

Material properties

Characteristic strength of concrete

$$f_{cu} = \mathbf{40 \text{ N/mm}^2}$$

Characteristic strength of reinforcement

$$f_y = \mathbf{500 \text{ N/mm}^2}$$

Base details

Minimum area of reinforcement

$$k = \mathbf{0.00 \text{ \%}}$$

Cover to reinforcement in heel

$$c_{heel} = \mathbf{30 \text{ mm}}$$

Calculate shear for heel design

Shear from bearing pressure

$$V_{heel_bear} = (p_{heel_f} + p_{stem_heel_f}) \times l_{heel} / 2 = \mathbf{4.5 \text{ kN/m}}$$

Shear from weight of base

$$V_{heel_wt_base} = \gamma_{fd} \times \gamma_{base} \times l_{heel} \times t_{base} = \mathbf{1 \text{ kN/m}}$$

Shear from weight of moist backfill

$$V_{heel_wt_m} = w_{m_w_f} = \mathbf{0 \text{ kN/m}}$$

Shear from weight of saturated backfill

$$V_{heel_wt_s} = w_{s_f} = \mathbf{3.9 \text{ kN/m}}$$

Shear from surcharge

$$V_{heel_sur} = w_{sur_f} = \mathbf{0.8 \text{ kN/m}}$$

Total shear for heel design

$$V_{heel} = -V_{heel_bear} + V_{heel_wt_base} + V_{heel_wt_m} + V_{heel_wt_s} + V_{heel_sur} = \mathbf{1.2}$$

kN/m

Calculate moment for heel design

Moment from bearing pressure

$$M_{heel_bear} = (2 \times p_{heel_f} + p_{stem_mid_f}) \times (l_{heel} + t_{wall} / 2)^2 / 6 = \mathbf{1.2 \text{ kNm/m}}$$

Moment from weight of base

$$M_{heel_wt_base} = (\gamma_{fd} \times \gamma_{base} \times t_{base} \times (l_{heel} + t_{wall} / 2)^2) / 2 = \mathbf{0.3 \text{ kNm/m}}$$

Moment from weight of moist backfill

$$M_{heel_wt_m} = w_{m_w_f} \times (l_{heel} + t_{wall}) / 2 = \mathbf{0 \text{ kNm/m}}$$

Moment from weight of saturated backfill

$$M_{heel_wt_s} = w_{s_f} \times (l_{heel} + t_{wall}) / 2 = \mathbf{0.7 \text{ kNm/m}}$$

Moment from surcharge

$$M_{heel_sur} = w_{sur_f} \times (l_{heel} + t_{wall}) / 2 = \mathbf{0.1 \text{ kNm/m}}$$

Total moment for heel design

$$M_{heel} = -M_{heel_bear} + M_{heel_wt_base} + M_{heel_wt_m} + M_{heel_wt_s} + M_{heel_sur} = \mathbf{-0.1}$$

kNm/m

As the moment is negative the design of the retaining wall heel is beyond the scope of this calculation

Design of reinforced concrete retaining wall stem (BS 8002:1994)

Material properties

Characteristic strength of concrete

$$f_{cu} = \mathbf{40 \text{ N/mm}^2}$$

Characteristic strength of reinforcement

$$f_y = \mathbf{500 \text{ N/mm}^2}$$

Wall details

Minimum area of reinforcement

$$k = \mathbf{0.00 \text{ \%}}$$

Cover to reinforcement in stem

$$c_{stem} = \mathbf{30 \text{ mm}}$$

Cover to reinforcement in wall

$$c_{wall} = \mathbf{30 \text{ mm}}$$

Factored horizontal active forces on stem

Surcharge

$$F_{s_sur_f} = \gamma_{fd} \times K_a \times \cos(90 - \alpha + \delta) \times \text{Surcharge} \times (h_{eff} - t_{base} - d_{ds}) = \mathbf{4.1}$$

kN/m

Moist backfill below water table

$$F_{s_m_b_f} = \gamma_{fd} \times K_a \times \cos(90 - \alpha + \delta) \times \gamma_m \times (h_{eff} - t_{base} - d_{ds} - h_{sat}) \times h_{sat} =$$

0 kN/m

Project Croftdown Road				Job no. 24555	
Calcs for Small Retaining Wall				Start page no./Revision 7	
Calcs by PJG	Calcs date 29/04/2016	Checked by	Checked date	Approved by	Approved date

Saturated backfill

$$F_{s_s_f} = 0.5 \times \gamma_{f_e} \times K_a \times \cos(90 - \alpha + \delta) \times (\gamma_s - \gamma_{water}) \times h_{sat}^2 = \mathbf{5.1 \text{ kN/m}}$$

Water

$$F_{s_water_f} = 0.5 \times \gamma_{f_e} \times \gamma_{water} \times h_{sat}^2 = \mathbf{13.5 \text{ kN/m}}$$

Calculate shear for stem design

Shear at base of stem

$$V_{stem} = F_{s_sur_f} + F_{s_m_b_f} + F_{s_s_f} + F_{s_water_f} - F_{prop_f} = \mathbf{22.2 \text{ kN/m}}$$

Calculate moment for stem design

Surcharge

$$M_{s_sur} = F_{s_sur_f} \times (h_{stem} + t_{base}) / 2 = \mathbf{3.5 \text{ kNm/m}}$$

Moist backfill below water table

$$M_{s_m_b} = F_{s_m_b_f} \times h_{sat} / 2 = \mathbf{0 \text{ kNm/m}}$$

Saturated backfill


$$M_{s_s} = F_{s_s_f} \times h_{sat} / 3 = \mathbf{2.4 \text{ kNm/m}}$$

Water

$$M_{s_water} = F_{s_water_f} \times h_{sat} / 3 = \mathbf{6.3 \text{ kNm/m}}$$

Total moment for stem design

$$M_{stem} = M_{s_sur} + M_{s_m_b} + M_{s_s} + M_{s_water} = \mathbf{12.2 \text{ kNm/m}}$$



Check wall stem in bending

Width of wall stem

$$b = \mathbf{1000 \text{ mm/m}}$$

Depth of reinforcement

$$d_{stem} = t_{wall} - c_{stem} - (\phi_{stem} / 2) = \mathbf{214.0 \text{ mm}}$$

Constant

$$K_{stem} = M_{stem} / (b \times d_{stem}^2 \times f_{cu}) = \mathbf{0.007}$$

Compression reinforcement is not required

Lever arm

$$z_{stem} = \min(0.5 + \sqrt{(0.25 - (\min(K_{stem}, 0.225) / 0.9))}, 0.95) \times d_{stem}$$

$$z_{stem} = \mathbf{203 \text{ mm}}$$

Area of tension reinforcement required

$$A_{s_stem_des} = M_{stem} / (0.87 \times f_y \times z_{stem}) = \mathbf{138 \text{ mm}^2/\text{m}}$$

Minimum area of tension reinforcement

$$A_{s_stem_min} = k \times b \times t_{wall} = \mathbf{0 \text{ mm}^2/\text{m}}$$

Area of tension reinforcement required

$$A_{s_stem_req} = \text{Max}(A_{s_stem_des}, A_{s_stem_min}) = \mathbf{138 \text{ mm}^2/\text{m}}$$

Reinforcement provided

$$\mathbf{12 \text{ mm dia. bars @ 200 mm centres}}$$

Area of reinforcement provided

$$A_{s_stem_prov} = \mathbf{565 \text{ mm}^2/\text{m}}$$

PASS - Reinforcement provided at the retaining wall stem is adequate

Check shear resistance at wall stem

Design shear stress

$$v_{stem} = V_{stem} / (b \times d_{stem}) = \mathbf{0.104 \text{ N/mm}^2}$$

Allowable shear stress

$$v_{adm} = \min(0.8 \times \sqrt{f_{cu}} / 1 \text{ N/mm}^2, 5) \times 1 \text{ N/mm}^2 = \mathbf{5.000 \text{ N/mm}^2}$$

PASS - Design shear stress is less than maximum shear stress

From BS8110:Part 1:1997 – Table 3.8


Design concrete shear stress

$$v_{c_stem} = \mathbf{0.555 \text{ N/mm}^2}$$

$v_{stem} < v_{c_stem}$ - No shear reinforcement required

Project		Croftdown Road		Job no.		24555	
Calcs for		Small Retaining Wall		Start page no./Revision		8	
Calcs by	Calcs date	Checked by	Checked date	Approved by	Approved date		
PJG	29/04/2016						

Indicative retaining wall reinforcement diagram



Toe bars - 12 mm dia.@ 200 mm centres - (565 mm²/m)

The design of the retaining wall heel is beyond the scope of this calculation!

Stem bars - 12 mm dia.@ 200 mm centres - (565 mm²/m)


BRACING OF BOX FRAME IN BASEMENT

$W = 0.4 \text{ kPa}$

$NHF = 0.5\%$

WIND

$W_{tot} = 0.4 \times (3.0 + 3.4) \times 7.8$
 $= 20 \text{ kN}$



NOTIONAL LOAD

$NHF_1 = 1.2 \text{ kN}$
 $NHF_2 = 1.7 \text{ kN}$ } from original calcs

$NHF_3 \sim 1.2 \text{ kN}$ — by inspection

Bracing load at ground level

$F_{tot} = 20 \text{ kN} + 3.5 \text{ kN}$
 $= 23.5 \text{ kN}$



$F_{water} = 2.5 \times 9.81$
 $= 26 \text{ kN/m}$



← joined with wind load.

$F_{soil} = 2.5 \times 19 \times 0.455$
 $= 21.6 \text{ kN/m}$

1000mm of retaining wall plus load of box frame above – 400x400mm RC COL

l_{crack} = 0.6






CONCRETE WALLS & GROUND BEAM

$$M_{uls} = 89 \text{ kNm} \\ (1.4Gk + 1.4Wk) \\ (\text{from retaining wall})$$

$$N^* = 113 \text{ kN} \\ (1.4Gk + 1.4Wk)$$



$$k = 89 \times 10^6 / 40 \times 400 \times (400 - 30)^2 \\ = 0.041$$

$$z = (400 - 30) \times (0.5 + (0.25 - 0.041 / 0.9)) \\ = 368 \text{ mm}$$

$$A_s = 89 \times 10^6 / (0.87 \times 500 \times 368) \\ = 555 \text{ mm}^2$$

→ 4 No. B16 = 804 mm² ✓ OK

$$s_{sls} = 4 \text{ mm} \times 400 = \text{Height} / 700$$

$$z = 136 \text{ mm}$$

$$= 177 \text{ mm}$$

$$A_s = 64 \text{ mm}^2$$

$$= 725 \text{ mm}^2$$

$$= 8 \text{ No. B16}$$



→ 400 x 400 mm col
8 No. B16 vert.
4 legs of B16 @ 100mm

RAPT - Version: 6.3.15.0
Reinforced And Post-Tensioned Concrete Analysis & Design Package
Copyright(C) 1988 - 2013 PCDC Pty. Ltd. All Rights Reserved

Licensee
Price Myers
30 Newman Street
London W1T 1LT
United Kingdom
56826220906URN4

General Interaction Diagram

Square 400mm
Reinforcement Bar, 8 T16
Reinforcement Ratio - 1.00%
United Kingdom - BS 8110
United Kingdom - United Kingdom Materials
Concrete Strength - 40MPa
Rotation 0.00 degrees clockwise. - Top Face in Compression



GROUND BEAM:

Original Spin Wall Load

$$DL = 9.7 \text{ kN/m} + 5.0 \text{ kN/m} + 5.0 \text{ kN/m}$$

$$= 19.7 \text{ kN/m}$$


$$LL = 9.8 \text{ kN/m} + 7.0 \text{ kN/m} + 5.0 \text{ kN/m}$$

$$= 21.8 \text{ kN/m}$$

$$W_{ULS} = 1.4 DL + 1.6 LL$$

$$= 55.0 \text{ kN/m}$$

$$L = 5200 \text{ mm}$$



→ 1000 x 300 dp
 8 No B20 top
 8 No B16 bottom
 6 legs of B10 @ 100cs.

RAPT - Version: 6.3.15.0
Reinforced And Post-Tensioned Concrete Analysis & Design Package
Copyright(C) 1988 - 2013 PCDC Pty. Ltd. All Rights Reserved

Licensee
 Price .Myers
 30 Newman Street
 London W1T 1LT
 United Kingdom
 56826220906URN4

Input

General

Design Code	List	United Kingdom - BS 8110
Material	List	United Kingdom - United Kingdom Materials
Reinforcement Type	List	Reinforced
Member Type	List	Beam
Panel Type	List	Internal
Strip Type	List	One way - Nominal Width
Column Stiffness	List	Equivalent Column
Concrete - Spanning Members	List	40MPa
Concrete - Columns	List	40MPa
Top Reinforcement Cover	mm	40
Bottom Reinforcement Cover	mm	40
Top Reinforcement Axis Depth Limit	mm	30
Bottom Reinforcement Axis Depth Limit	mm	30
Concrete Unit Weight	kn/m3	25
Self Weight Definition	List	Program Calculated
Pattern Live Load	Y/N	
Earthquake Design	List	None
Moment Redistribution	%	0
Design Surface Levels	List	Extreme Surfaces

Span

Span	Span Length	Slab Depth	Panel Width Left	Panel Width Right
	mm	mm	mm	mm
LE	0			
1	5200	300	1000	1000
RE	0			

Columns

Column	Column Grid Reference	Support Type	Transverse Column spacing	Transverse v'c
	A	List	mm	MPa
1	1	Knife-Edge	1000	
2	2	Knife-Edge	1000	

Beams

Beam Number	Beam Depth	Beam Width at Slab	Beam Width	Effective Flange Width
	mm	mm	mm	mm
1	300	1000	1000	1000

Load Cases

Load Case	Load Type	Load Definition	Live Load Deflection Case	Description
	List	List	Y/N	A
1	Self Weight	Applied Loads		

Load Case	Load Type	Load Definition	Live Load Deflection Case	Description
	List	List	Y/N	A
2	Initial Dead Load	Applied Loads		
3	Live Load	Applied Loads	Y	

1. Self Weight - Line

Load	Left End Reference Column	Left end of load from reference column	Load at left end	Right End reference column	Right end of load from reference column	Load at right end	Description
	#	mm	kN/m	#	mm	kN/m	A
1	1	0	7.5	2	0	7.5	

2. Initial Dead Load - Panel

Load	Left End reference column	Left end of load from reference column	Load at left end	Right End reference column	Right end of load from reference column	Load at right end	Description
	#	mm	kN/m2	#	mm	kN/m2	A
1	1	0	20	2	0	20	

3. Live Load - Panel

Load	Left End reference column	Left end of load from reference column	Load at left end	Right End reference column	Right end of load from reference column	Load at right end	Live Load reduction	Description
	#	mm	kN/m2	#	mm	kN/m2	##	A
1	1	0	22	2	0	22	1	

Load Combinations : Ultimate

Load Combination	Description	1. Self Weight	2. Initial Dead Load	3. Live Load
	A	##	##	##
1	Live Load	1.4	1.4	1.6
2	Live Load	1	1	1.6
3	Dead Load	1.5	1.5	0

Load Combinations : Short Term Service

Load Combination	Description	1. Self Weight	2. Initial Dead Load	3. Live Load
	A	##	##	##
1	Live Load	1	1	1

Load Combinations : Permanent Service

Load Combination	Description	1. Self Weight	2. Initial Dead Load	3. Live Load
	A	##	##	##
1	Live Load	1	1	0.25

Load Combinations : Deflection

Load Combination	Description	1. Self Weight	2. Initial Dead Load	3. Live Load
	A	##	##	##
1	Short Term - Deflection	1	1	1
2	Permanent - Deflection	1	1	0.25
3	Initial - Deflection	1	1	0

Load Combinations : Transfer Prestress

Load Combination	Description	1. Self Weight	2. Initial Dead Load	3. Live Load
	A	##	##	##
1	Transfer	1	0	0


Load Combinations : Pre Existing

Load Combination	Description	1. Self Weight	2. Initial Dead Load	3. Live Load
	A	##	##	##
1	Pre Existing	1	0	0


Load Combinations : Construction

Load Combination	Description	1. Self Weight	2. Initial Dead Load	3. Live Load
	A	##	##	##
1	Construction	1	0	0


Load Case 1 : 1. Self Weight



Load Case 2 : 2. Initial Dead Load



Load Case 3 : 3. Live Load



Reinforcement

Reinforcement Use	Reinforcement Type	Preferred Bar Size	Number of Legs
	List	List	#
Flexural Bar	T 460MPa		
Flexural Mesh	A 460MPa		
Shear Option 1	T 460MPa	12	4
Shear Option 2	T 460MPa	12	6
Shear Option 3	T 460MPa	12	2
Punching Shear	T 460MPa	10	2

Reinforcement

	Maximum Bar Spacing	Minimum Bar Spacing	Minimum Continuous Reinforcement	Minimum Span Reinforcement into End Support	Minimum Span Reinforcement into Internal Support	Infill Bars	Stagger Bars
	mm	mm	##	##	##	Y/N	Y/N
Support Reinforcement	300	60	0			N	N
Span Reinforcement	300	60		0	0	N	N

Design Zones : Top

Layer Number	Steel type	Left End Reference Column	Distance to left end of bar	Bar stagger length at left end	Top Cover at left end	Right End Reference Column	Distance to right end of bar	Bar stagger length at right end	Top Cover at Right end	Maximum Bar Size	Minimum Bar Size	Preferred bar size
	List	#	mm	mm	mm	#	mm	mm	mm	List	List	List
1	Bar	1	0	0	40	2	0	0	40	16	12	12


Layer Number	Minimum Number of Bars	Maximum Spacing of Bars	Minimum Steel area as %	Minimum Reinforcement placed at	% in Flange
	#	mm	%	List	%
1	4	0	0	All Points	0

Design Zones : Bottom

Layer Number	Steel type	Left End Reference Column	Distance to left end of bar	Bar stagger length at left end	Bottom Cover at left end	Right End Reference Column	Distance to right end of bar	Bar stagger length at right end	Bottom Cover at Right End	Maximum Bar Size	Minimum Bar Size	Preferred bar size
	List	#	mm	mm	mm	#	mm	mm	mm	List	List	List
1	Bar	1	0	0	25	2	0	0	25	25	16	20

Layer Number	Minimum Number of Bars	Maximum Spacing of Bars	Minimum Steel area as %	Minimum Reinforcement placed at	% in Flange
	#	mm	%	List	%
1	4	0	0	All Points	0

Reinforcement Design Zones



Design Data

Capacity Reduction factor (phi) for Flexure	##	1
Capacity Reduction factor (phi) for Shear	##	1
Material Factor for Concrete in Flexure	##	1.5
Material Factor for Concrete in Shear	##	1.25
Material Factor for Reinforcement	##	1.05
Maximum Ratio of Neutral Axis Depth for Ductility	##	0.5
Ductility Limit - Strain	##	0
Ductility Check at Left End Column	Y/N	Y
Ductility Check at Right End Column	Y/N	Y
Minimum Reinforcement Strength Limit - ### x M*	##	0
Flexural Critical Section - Consider Transverse Beams	Y/N	Y
Flexural Critical Section - Distance from centre of Support	##	-1
Beam Left Sideface Cover (Internal)	mm	25
Beam Right Sideface cover	mm	40
Prestress Minimum Reinforcement Basis	List	Program Default
Shear Enhancement at Supports	Y/N	Y
Ast Value in Shear Calculations	List	Calculated
Maximum Shear Stress for BS8110	MPa	0
Limit Reinforcement Strain	Y/N	N
Beam Shear Critical Section Location	List	Code Critical Section

Maximum Service Stress Change - Prestressed Sections	MPa	200
Maximum Service Stress Change - Reinforced Sections	MPa	0
Relative Humidity	%	50
Average Temperature	C.	20
Prestress Losses Calculations based on	List	Program Default
Crack Width Calculations	List	Code default
AS3600 Shrinkage and Temperature Reinforcement	List	Moderate
Degree of Restraint in Primary Direction	%	0
Degree of Restraint in Secondary Direction	%	0
Concrete Strength Gain Rate	List	N

Concrete Tensile Strength for Deflection Calculations- $### \times (F_c)n$	##	-1
Maximum Value of I_{eff}/I_{gross} for Deflection Calculations	##	0.6
Total Deflection Warning Limit - Maximum Span/Deflection	##	250
Total Deflection Warning Limit - Maximum Deflection	mm	20
Incremental Deflection Warning Limit - Maximum Span/Deflection	##	350
Incremental Deflection Warning Limit - Maximum Deflection	mm	20
Time of Loading in days	##	10
Age Adjustment Factor	##	0.76
Concrete Strength at Time of Loading	MPa	33.8
Loaded Period in years	##	30
Tension stiffening Approach	List	Modified Concrete Tensile Modulus Method

Live Load Pattern Factor	##
Pattern Live Load for Ultimate Strength	Y/N
Pattern Live Load for Crack Control	Y/N
Pattern Live Load For Deflections	Y/N
Pattern Live Load for Deflection Permanent Load Combination	Y/N

Material Properties

Concrete

Description	40MPa
Characteristic Compressive Strength	40
Mean Compressive Strength	46.53
Lower Characteristic Tensile Strength	3.16
Upper Characteristic Tensile Strength	5.69
Concrete Density	2447
Design Concrete Modulus	28000
Mean Concrete Modulus	29305
Basic Shrinkage Strain	0
Shrinkage Multiplier	1
Basic Creep Factor	0
Concrete Strain at Peak Stress	0.002
Squash Load Factor	0.85
Concrete Strain Limit	0.004


Reinforcement Bar

Designation	Type	Yield Stress	Elastic Modulus	Ductility	Peak Strain	Peak Stress	Design Strain Limit	Material Factor Flexure	Material Factor Shear	Material Capacity Reduction Factor - Flexure	Material Capacity Reduction Factor - Shear	Include as Flexural Reinforcement for Shear
T	Deformed	460	2e5	N	0.05	496.8	90	-1	-1	-1	-1	Y


Description

Nominal Bar Size	Bar Diameter	Bar Area	Bar Inertia	Bar Weight	Stock Length
A	mm	mm ²	mm ⁴	kg/m	mm
8	8	50.3	201.14	0.4	12000
10	10	78.5	491.07	0.62	12000
12	12	113	1018.29	0.89	12000
16	16	201	3218.29	1.58	12000
20	20	314	7857.14	2.47	12000
25	25	491	19182.5	3.85	12000
32	32	804	51492.6	6.31	12000
40	40	1260	1.257e5	9.86	12000

Elevation view



Plan view



Warnings

Input

No errors or warnings were found.

Output

Warning:At 416mm, the moment curvature calculations did not converge on the design moment within our set limits after 100 iterations. We have adopted the nearest solution. This normally only occurs at points of very low moment and is not normally a problem so we have continued with the design.


Warning:Incremental Deflection span/deflection ratio in at least one span is less than defined limit.

Warning:Total Deflection span/deflection ratio in at least one span is less than defined limit.


Warning:Incremental deflection in at least one span is greater than defined limit.

Warning:Total deflection in at least one span is greater than defined limit.

Bending Moments Load Combinations Ultimate Flexure



Moment Moment 1 Moment 2



**Flexural Design
Reinforcement**

Span 1

Locat mm	Top Design (1)		Bott Design (1)	
	Area mm2	Depth mm	Area mm2	Depth mm
100	452	46	1256	265
240	452	46	1256	265
416	452	46	1256	265
592	452	46	1256	265
768	452	46	1256	265
944	452	46	1365.78	265
1120	452	46	1569.18	265
1300	452	46	1757.45	265
1733	452	46	2121.02	265
2166	452	46	2346.33	265
2600	452	46	2422.91	265
3033	452	46	2346.68	265
3466	452	46	2121.7	265
3900	452	46	1757.45	265
4076	452	46	1573.59	265
4252	452	46	1370.6	265
4428	452	46	1256	265
4604	452	46	1256	265
4780	452	46	1256	265
4960	452	46	1256	265
5100	452	46	1256	265

**Ultimate
Span 1**

Locat mm	Min Width mm	Design Moment		Initial Condition		Final Design Condition				Reinforcement	
		M* kNm	Mmin kNm	Phi Mu kNm	ku mm/mm	Phi Mu kNm	ku mm/mm	dtens mm	Max Strain Ratio #.#	Top mm2	Bottom mm2
100	1000	18.79	56.92	0	0	137.79	0.1625	249	0.3886	452	1256
240	1000	43.87	56.92	0	0	137.79	0.1625	249	0.3886	452	1256
416	1000	73.34	56.92	0	0	137.79	0.1625	249	0.3886	452	1256
592	1000	100.52	56.92	0	0	137.79	0.1625	249	0.3886	452	1256
768	1000	125.43	56.92	0	0	137.79	0.1625	249	0.3886	452	1256
944	1000	148.05	56.92	0	0	148.74	0.166	255.7	0.367	452	1365.78
1120	1000	168.39	56.92	0	0	168.75	0.1756	265	0.3286	452	1569.18
1300	1000	186.83	56.92	0	0	187.15	0.1909	265	0.2967	452	1757.45
1733	1000	221.41	56.92	0	0	222.06	0.2221	265	0.2451	452	2121.02
2166	1000	242.17	56.92	0	0	243.24	0.2425	265	0.2187	452	2346.33
2600	1000	249.11	56.92	0	0	250.35	0.2496	265	0.2105	452	2422.91
3033	1000	242.2	56.92	0	0	243.27	0.2425	265	0.2186	452	2346.68
3466	1000	221.47	56.92	0	0	222.12	0.2222	265	0.245	452	2121.7
3900	1000	186.83	56.92	0	0	187.15	0.1909	265	0.2967	452	1757.45
4076	1000	168.83	56.92	0	0	169.18	0.176	265	0.3278	452	1573.59
4252	1000	148.54	56.92	0	0	149.21	0.1662	256	0.3661	452	1370.6
4428	1000	125.97	56.92	0	0	137.79	0.1625	249	0.3886	452	1256
4604	1000	101.12	56.92	0	0	137.79	0.1625	249	0.3886	452	1256
4780	1000	73.98	56.92	0	0	137.79	0.1625	249	0.3886	452	1256
4960	1000	43.87	56.92	0	0	137.79	0.1625	249	0.3886	452	1256
5100	1000	18.79	56.92	0	0	137.79	0.1625	249	0.3886	452	1256

**Service
Span 1**

Locat mm	Design Moment		Gross Concrete Stress				Cracked Sect Results							Concrete Compression Face Strain mm/mm
	Mser kNm	Msmod kNm	P/A MPa	Top MPa	Bottom MPa	Igross Transform mm4	Comp Stress MPa	Kdser mm	Tension Stress Change MPa	Extra Tension Reinforcement mm2	Maximum Spacing mm	Maximum Bar Size mm	Cracked Inertia mm4	
100	12.62	12.62	0	0.81	-0.78	2.38e9	0.72	149.2	40.83	0	300	0	4.61e8	0
240	29.46	29.46	0	1.88	-1.83	2.38e9	1.67	149.2	95.5	0	300	0	4.59e8	0.0001
416	49.26	49.26	0	3.14	-3.06	2.38e9	3.62	110.6	158.38	0	300	0	4.61e8	0.0003
592	67.52	67.52	0	4.31	-4.2	2.38e9	5.58	93.6	219.55	0	300	0	4.55e8	0.0004
768	84.24	84.24	0	5.38	-5.24	2.38e9	7.35	85.7	274.32	0	300	0	4.54e8	0.0005

Locat mm	Design Moment		Gross Concrete Stress				Cracked Sect Results							Concrete Compression Face Strain mm/mm
	Mser kNm	Msmo kNm	P/A MPa	Top MPa	Bottom MPa	Igross Transform mm4	Comp Stress MPa	Kdser mm	Tension Stress Change MPa	Extra Tension Reinforcement mm2	Maximum Spacing mm	Maximum Bar Size mm	Cracked Inertia mm4	
944	99.44	99.44	0	6.33	-6.15	2.39e9	8.58	85.5	296.75	0	249.2	0	4.89e8	0.0006
1120	113.1	113.1	0	7.18	-6.93	2.41e9	9.32	89.3	295.92	0	236.3	0	5.47e8	0.0007
1300	125.48	125.48	0	7.93	-7.62	2.42e9	9.96	92.7	294.54	0	229.9	0	6e8	0.0007
1733	148.71	148.71	0	9.34	-8.88	2.45e9	11.08	98.9	291.23	0	225.2	0	6.97e8	0.0008
2166	162.65	162.65	0	10.18	-9.61	2.47e9	11.72	102.5	289.53	0	225.2	0	7.54e8	0.0009
2600	167.31	167.31	0	10.46	-9.85	2.47e9	11.92	103.7	288.93	0	225.6	0	7.73e8	0.0009
3033	162.67	162.67	0	10.18	-9.61	2.47e9	11.72	102.5	289.53	0	225.2	0	7.54e8	0.0009
3466	148.75	148.75	0	9.35	-8.88	2.45e9	11.08	98.9	291.22	0	225.2	0	6.98e8	0.0008
3900	125.48	125.48	0	7.93	-7.62	2.42e9	9.96	92.7	294.54	0	229.9	0	6e8	0.0007
4076	113.39	113.39	0	7.19	-6.95	2.41e9	9.34	89.3	295.91	0	236.2	0	5.48e8	0.0007
4252	99.76	99.76	0	6.35	-6.17	2.39e9	8.6	85.6	296.73	0	248.8	0	4.91e8	0.0006
4428	84.61	84.61	0	5.4	-5.26	2.38e9	7.39	85.6	275.51	0	300	0	4.54e8	0.0005
4604	67.91	67.91	0	4.33	-4.22	2.38e9	5.62	93.4	220.85	0	300	0	4.55e8	0.0004
4780	49.69	49.69	0	3.17	-3.09	2.38e9	3.67	110	159.96	0	300	0	4.61e8	0.0003
4960	29.46	29.46	0	1.88	-1.83	2.38e9	1.67	149.2	95.5	0	300	0	4.59e8	0.0001
5100	12.62	12.62	0	0.81	-0.78	2.38e9	0.72	149.2	40.83	0	300	0	4.61e8	0

Concrete Tension Face Strain mm/mm
0
-0.0001
-0.0004
-0.0009
-0.0013
-0.0016
-0.0016
-0.0017
-0.0017
-0.0017
-0.0017
-0.0017
-0.0017
-0.0017
-0.0016
-0.0016
-0.0013
-0.0009
-0.0004
-0.0001
0

**Permanent
Span 1**

Locat mm	Design Moment		Gross Concrete Stress				Cracked Sect Results							Concrete Compression Face Strain mm/mm
	Mser kNm	Msmo kNm	P/A MPa	Top MPa	Bottom MPa	Igross Transform mm4	Comp Stress MPa	Kdser mm	Tension Stress Change MPa	Extra Tension Reinforcement mm2	Maximum Spacing mm	Maximum Bar Size mm	Cracked Inertia mm4	
100	8.41	8.41	0	0.54	-0.52	2.38e9	0.54	151.9	2.85	0	300	0	4.61e8	0
240	19.64	19.64	0	1.25	-1.22	2.38e9	2.49	56.6	63.66	0	300	0	4.59e8	0
416	32.84	32.84	0	2.1	-2.04	2.38e9	4.12	57	105.82	0	300	0	4.61e8	0.0001
592	45.01	45.01	0	2.87	-2.8	2.38e9	5.66	57.3	146.17	0	300	0	4.55e8	0.0002
768	56.16	56.16	0	3.58	-3.49	2.38e9	7.02	57.5	182.54	0	300	0	4.54e8	0.0003
944	66.29	66.29	0	4.22	-4.1	2.39e9	7.92	59.8	197.59	0	249.2	0	4.89e8	0.0003
1120	75.4	75.4	0	4.78	-4.62	2.41e9	8.51	63.6	196.99	0	236.3	0	5.47e8	0.0003
1300	83.65	83.65	0	5.29	-5.08	2.42e9	9.01	66.8	196.26	0	229.9	0	6e8	0.0003
1733	99.14	99.14	0	6.23	-5.92	2.45e9	9.89	72.5	194.57	0	225.2	0	6.97e8	0.0004
2166	108.43	108.43	0	6.79	-6.41	2.47e9	10.4	75.8	193.42	0	225.2	0	7.54e8	0.0004
2600	111.54	111.54	0	6.97	-6.57	2.47e9	10.56	76.8	193.01	0	225.6	0	7.73e8	0.0004
3033	108.45	108.45	0	6.79	-6.41	2.47e9	10.4	75.8	193.42	0	225.2	0	7.54e8	0.0004
3466	99.17	99.17	0	6.23	-5.92	2.45e9	9.9	72.6	194.57	0	225.2	0	6.98e8	0.0004
3900	83.65	83.65	0	5.29	-5.08	2.42e9	9.01	66.8	196.26	0	229.9	0	6e8	0.0003
4076	75.59	75.59	0	4.8	-4.63	2.41e9	8.52	63.7	196.98	0	236.2	0	5.48e8	0.0003

Locat mm	Design Moment		Gross Concrete Stress				Cracked Sect Results							Concrete Compression Face Strain mm/mm
	Mser kNm	Msmod kNm	P/A MPa	Top MPa	Bottom MPa	Igross Transform mm4	Comp Stress MPa	Kdser mm	Tension Stress Change MPa	Extra Tension Reinforcement mm2	Maximum Spacing mm	Maximum Bar Size mm	Cracked Inertia mm4	
4252	66.51	66.51	0	4.23	-4.11	2.39e9	7.94	59.9	197.58	0	248.8	0	4.91e8	0.0003
4428	56.4	56.4	0	3.6	-3.51	2.38e9	7.05	57.5	183.33	0	300	0	4.54e8	0.0003
4604	45.28	45.28	0	2.89	-2.82	2.38e9	5.69	57.3	147.04	0	300	0	4.55e8	0.0002
4780	33.13	33.13	0	2.11	-2.06	2.38e9	4.16	57	106.74	0	300	0	4.61e8	0.0001
4960	19.64	19.64	0	1.25	-1.22	2.38e9	2.49	56.6	63.66	0	300	0	4.59e8	0
5100	8.41	8.41	0	0.54	-0.52	2.38e9	0.54	151.9	2.85	0	300	0	4.61e8	0

Concrete Tension Face Strain mm/mm
0
-0.0004
-0.0006
-0.0009
-0.0011
-0.0012
-0.0012
-0.0012
-0.0011
-0.0011
-0.0011
-0.0011
-0.0011
-0.0012
-0.0012
-0.0012
-0.0011
-0.0009
-0.0006
-0.0004
0

**Shear Design
Beam
Span 1**


Locat	V*	Mv*	Mdec	d	Ast	bv	phi Vuc	phi Vut	phi Vu	Phi Vumax	Asv/s	Spacing of Sets		
												4 legs T12	6 legs T12	2 legs T12
mm	kN	kNm	kNm	mm	mm2	mm	kN	kN	kN	kN	mm2/mm	mm	mm	mm
100	184.25	18.79	0	265	1256	1000	897.22	99999	897.22	1325	0.91	198.8	198.8	198.8
240	173.93	43.87	0	265	1256	1000	373.84	99999	373.84	1325	0.91	198.8	198.8	198.8
416	160.96	73.34	0	265	1256	1000	215.68	99999	215.68	1325	0.91	198.8	198.8	198.8
592	147.99	100.52	0	265	1256	1000	169.29	99999	169.29	1325	0.91	198.8	198.8	198.8
768	136.45	119.09	0	265	1256	1000	169.29	99999	169.29	1325	0.91	198.8	198.8	198.8
944	123.48	141.96	0	265	1365.78	1000	174.08	99999	174.08	1325	0.91	198.8	198.8	198.8
1120	110.51	162.56	0	265	1569.18	1000	182.33	99999	182.33	1325	0.91	198.8	198.8	198.8
1300	101.53	164.52	0	265	1757.45	1000	189.34	99999	189.34	1325	0.91	198.8	198.8	198.8
1733	69.62	201.58	0	265	2121.02	1000	201.59	99999	201.59	1325	0.91	198.8	198.8	198.8
2166	44.86	203.12	0	265	2346.33	1000	208.49	99999	208.49	1325	0.91	198.8	198.8	198.8
2600	22.88	189.62	0	265	2422.91	1000	210.73	99999	210.73	1325	0.91	198.8	198.8	198.8
3033	-44.78	203.16	0	265	2346.68	1000	208.5	99999	208.5	1325	0.91	198.8	198.8	198.8
3466	-69.54	201.64	0	265	2121.7	1000	201.61	99999	201.61	1325	0.91	198.8	198.8	198.8
3900	-101.53	164.52	0	265	1757.45	1000	189.34	99999	189.34	1325	0.91	198.8	198.8	198.8
4076	-110.21	163	0	265	1573.59	1000	182.5	99999	182.5	1325	0.91	198.8	198.8	198.8
4252	-123.18	142.46	0	265	1370.6	1000	174.29	99999	174.29	1325	0.91	198.8	198.8	198.8
4428	-136.15	119.64	0	265	1256	1000	169.29	99999	169.29	1325	0.91	198.8	198.8	198.8
4604	-147.69	101.12	0	265	1256	1000	169.29	99999	169.29	1325	0.91	198.8	198.8	198.8
4780	-160.67	73.98	0	265	1256	1000	213.62	99999	213.62	1325	0.91	198.8	198.8	198.8
4960	-173.93	43.87	0	265	1256	1000	373.84	99999	373.84	1325	0.91	198.8	198.8	198.8
5100	-184.25	18.79	0	265	1256	1000	897.22	99999	897.22	1325	0.91	198.8	198.8	198.8

Shear Reinforcement				
Spacing of Sets				
Area	4 legs	6 legs	2 legs	Shear Comments
mm ² /mm	T12 mm	T12 mm	T12 mm	
0.91	198.8	198.8	198.8	Minimum Steel
0.91	198.8	198.8	198.8	Minimum Steel
0.91	198.8	198.8	198.8	Minimum Steel
0.91	198.8	198.8	198.8	Minimum Steel
0.91	198.8	198.8	198.8	Minimum Steel
0.91	198.8	198.8	198.8	Minimum Steel
0.91	198.8	198.8	198.8	Minimum Steel
0.91	198.8	198.8	198.8	Minimum Steel
0.91	198.8	198.8	198.8	Minimum Steel

Design Comments:-

- Span - 1 - Reinforcement added at left span contraflexure point for Offset of Bending Moment Diagram for Shear - 313.96mm²
- Span - 1 - Reinforcement added at right span contraflexure point for Offset of Bending Moment Diagram for Shear - 313.96mm²

Reinforcement Layout



Project Croftdown Road				Job no. 24555	
Calcs for Steel COLUMN				Start page no./Revision 1	
Calcs by PJG	Calcs date 28/04/2016	Checked by	Checked date	Approved by	Approved date


STEEL MEMBER DESIGN (BS5950)

In accordance with BS5950-1:2000 incorporating Corrigendum No.1

TEDDS calculation version 3.0.04

Section details

Section type	SHS 100x100x5.0 (Corus Celsius)
Steel grade	S275
From table 9: Design strength p_y	
Thickness of element	$t = 5.0$ mm
Design strength	$p_y = 275$ N/mm ²
Modulus of elasticity	$E = 205000$ N/mm ²



Lateral restraint

Distance between major axis restraints	$L_x = 3000$ mm
Distance between minor axis restraints	$L_y = 3000$ mm

Effective length factors

Effective length factor in major axis	$K_x = 1.00$
Effective length factor in minor axis	$K_y = 1.00$
Effective length factor for lateral-torsional buckling	$K_{LT} = 1.00$

Classification of cross sections - Section 3.5

$$\epsilon = \sqrt{[275 \text{ N/mm}^2 / p_y]} = 1.00$$

Web - major axis - Table 12

Depth of section	$d = D - 3 \times t = 85$ mm
Stress ratios	$r1 = \min(F_c / (2 \times d \times t \times p_{yw}), 1) = 0.385$
	$r2 = F_c / (A \times p_{yw}) = 0.175$
	$d / t = 17.0 \times \epsilon \leq \max(64 \times \epsilon / (1 + r1), 40 \times \epsilon)$ Class 1 plastic

Flange - major axis - Table 12

Width of section	$b = B - 3 \times t = 85$ mm
	$b / t = 17.0 \times \epsilon \leq 40 \times \epsilon$ Class 3 semi-compact
	Section is class 3 semi-compact

Project			Croftdown Road		Job no.		24555				
Calcs for			Steel COLUMN			Start page no./Revision			2		
Calcs by		Calcs date		Checked by		Checked date		Approved by		Approved date	
PJJ		28/04/2016									

Shear capacity - Section 4.2.3

Design shear force

$$F_{y,v} = 20 \text{ kN}$$

$$(D - 3 \times t) / t < 70 \times \epsilon$$

Web does not need to be checked for shear buckling

Shear area

$$A_v = A \times D / (D + B) = 937 \text{ mm}^2$$

Design shear resistance

$$P_{y,v} = 0.6 \times p_y \times A_v = 154.5 \text{ kN}$$

PASS - Design shear resistance exceeds design shear force

Shear capacity - Section 4.2.3

Design shear force

$$F_{x,v} = 20 \text{ kN}$$

Shear area

$$A_v = A_x = 937 \text{ mm}^2$$

Design shear resistance

$$P_{x,v} = 0.6 \times p_y \times A_v = 154.5 \text{ kN}$$

PASS - Design shear resistance exceeds design shear force

Moment capacity - Section 4.2.5

Design bending moment

$$M = 10 \text{ kNm}$$

Effective plastic modulus - Section 3.5.6

Limiting value for class 2 compact flange

$$\beta_{2f} = \min(32 \times \epsilon, 62 \times \epsilon - 0.5 \times d / t) = 32$$

Limiting value for class 3 semi-compact flange

$$\beta_{3f} = 40 \times \epsilon = 40$$

Limiting value for class 2 compact web

$$\beta_{2w} = \max(80 \times \epsilon / (1 + r_1), 40 \times \epsilon) = 57.761$$

Limiting value for class 3 semi-compact web

$$\beta_{3w} = \max(120 \times \epsilon / (1 + 2 \times r_2), 40 \times \epsilon) = 88.926$$

Effective plastic modulus - cl.3.5.6.3

$$S_{eff} = \min(Z + (S - Z) \times \min([\beta_{3w} / (d / t) - 1] / (\beta_{3w} / \beta_{2w} - 1), [(\beta_{3f} / (b / t) - 1) / (\beta_{3f} / \beta_{2f} - 1)]), S) = 66358 \text{ mm}^3$$

Moment capacity low shear - cl.4.2.5.2

$$M_c = \min(p_y \times S_{eff}, 1.2 \times p_y \times Z) = 18.2 \text{ kNm}$$

Effective length for lateral-torsional buckling - Section 4.3.5

Effective length for lateral torsional buckling

$$L_E = 1.0 \times L_y = 3000 \text{ mm}$$

Slenderness ratio

$$\lambda = L_E / r_{yy} = 77.673$$

Equivalent slenderness - Annex B.2.6.1

Torsion constant

$$J = 4394108 \text{ mm}^4$$

$$\gamma_b = (1 - I_{yy} / I_{xx}) \times (1 - J / (2.6 \times I_{xx})) = 0.000$$

$$\phi_b = [S_{xx}^2 \times \gamma_b / (A \times J)]^{0.5} = 0.000$$

Ratio - cl.4.3.6.9

$$\beta_w = S_{eff} / S_{xx} = 1.000$$

Equivalent slenderness

$$\lambda_{LT} = 2.25 \times \sqrt{\phi_b \times \lambda \times \beta_w} = 0.000$$

Limiting slenderness - Annex B.2.2

$$\lambda_{L0} = 0.4 \times (\pi^2 \times E / p_y)^{0.5} = 34.310$$

$\lambda_{LT} < \lambda_{L0}$ - No allowance need be made for lateral-torsional buckling

Buckling resistance moment - Section 4.3.6.4

Bending strength

$$p_b = p_y = 275 \text{ N/mm}^2$$

Buckling resistance moment

$$M_b = p_b \times S_{eff} = 18.2 \text{ kNm}$$

PASS - Moment capacity exceeds design bending moment

Compression members - Section 4.7

Design compression force

$$F_c = 90 \text{ kN}$$

Effective length for major (x-x) axis buckling - Section 4.7.3

Effective length for buckling

$$L_{Ex} = L_x \times K_x = 3000 \text{ mm}$$

Slenderness ratio - cl.4.7.2

$$\lambda_x = L_{Ex} / r_{xx} = 77.673$$

Compressive strength - Section 4.7.5

Limiting slenderness

$$\lambda_0 = 0.2 \times (\pi^2 \times E / p_y)^{0.5} = 17.155$$

Project				Job no.	
Croftdown Road				24555	
Calcs for				Start page no./Revision	
Steel COLUMN				3	
Calcs by	Calcs date	Checked by	Checked date	Approved by	Approved date
PJG	28/04/2016				

Strut curve - Table 23

a

Robertson constant

$$\alpha_x = 2.0$$

Perry factor

$$\eta_x = \alpha_x \times (\lambda_x - \lambda_0) / 1000 = 0.121$$

Euler stress

$$p_{Ex} = \pi^2 \times E / \lambda_x^2 = 335.4 \text{ N/mm}^2$$

$$\phi_x = (p_y + (\eta_x + 1) \times p_{Ex}) / 2 = 325.5 \text{ N/mm}^2$$

Compressive strength - Annex C.1

$$p_{cx} = p_{Ex} \times p_y / (\phi_x + (\phi_x^2 - p_{Ex} \times p_y)^{0.5}) = 208.4 \text{ N/mm}^2$$

Compression resistance - Section 4.7.4

Compression resistance - cl.4.7.4

$$P_{cx} = A \times p_{cx} = 390.3 \text{ kN}$$

PASS - Compression resistance exceeds design compression force

Effective length for minor (y-y) axis buckling - Section 4.7.3

Effective length for buckling

$$L_{Ey} = L_y \times K_y = 3000 \text{ mm}$$

Slenderness ratio - cl.4.7.2

$$\lambda_y = L_{Ey} / r_{yy} = 77.673$$

Compressive strength - Section 4.7.5

Limiting slenderness

$$\lambda_0 = 0.2 \times (\pi^2 \times E / p_y)^{0.5} = 17.155$$

Strut curve - Table 23

a

Robertson constant

$$\alpha_y = 2.0$$

Perry factor

$$\eta_y = \alpha_y \times (\lambda_y - \lambda_0) / 1000 = 0.121$$

Euler stress

$$p_{Ey} = \pi^2 \times E / \lambda_y^2 = 335.4 \text{ N/mm}^2$$

$$\phi_y = (p_y + (\eta_y + 1) \times p_{Ey}) / 2 = 325.5 \text{ N/mm}^2$$

Compressive strength - Annex C.1

$$p_{cy} = p_{Ey} \times p_y / (\phi_y + (\phi_y^2 - p_{Ey} \times p_y)^{0.5}) = 208.4 \text{ N/mm}^2$$

Compression resistance - Section 4.7.4

Compression resistance - cl.4.7.4

$$P_{cy} = A \times p_{cy} = 390.3 \text{ kN}$$

PASS - Compression resistance exceeds design compression force

Compression members with moments - Section 4.8.3

Comb.compression & bending check - cl.4.8.3.2

$$F_c / (A \times p_y) + M / M_c = 0.723$$

PASS - Combined bending and compression check is satisfied

Member buckling resistance - Section 4.8.3.3

Max major axis moment governing M_b

$$M_{LT} = M_x = 10.00 \text{ kNm}$$

Equivalent uniform moment factor for major axis flexural buckling

$$m_x = 1.000$$

$$m_y = 1.000$$

Buckling resistance checks - cl.4.8.3.3.3

$$F_c / P_{cx} + m_x \times M / M_c \times (1 + 0.5 \times F_c / P_{cx}) = 0.842$$

$$F_c / P_{cy} + 0.5 \times m_{LT} \times M_{LT} / M_{cx} = 0.505$$

PASS - Member buckling resistance checks are satisfied

SLAB DESIGN

→ Uplift. between underpin toes

$$\begin{aligned} \text{Span} &= 5.6\text{m} - 1.4 \times 2 \\ &= 2.8\text{m} \end{aligned}$$

GWL = 2.0m highest water level @ ground level in front garden.

$$\begin{aligned} \text{Uplift} &= (10 \times 2.0) \times 1.6 - (0.25 \times 24) \\ &= 26 \text{ kNm / m width.} \end{aligned}$$

$$\begin{aligned} \text{Cap M} &= 393 \text{ mm}^2 \times 500 \times (250 - 30) \times 0.85 \\ &= 36.7 \text{ kNm} \quad \checkmark \text{OK.} \end{aligned}$$

→ Global Uplift.

$$\begin{aligned} \text{Uplift} &= (5.6 + 2 \times 0.215) \times 2.0 \times 10 \\ &= 120 \text{ kN} \end{aligned}$$

$$\begin{aligned} \text{Structure W} &= (0.25 + 0.005) \times 24 \times 6 \quad \text{Slab + screed} \\ &+ (0.215 \times 18 \times 11\text{m} \times 80\%) \times 2 \quad \text{walls} \\ &+ (0.5\text{m} \times 1.4 \times 24) \times 2 \quad \text{average building height slab thickening} \\ &= 145 \text{ kN} > 120 \text{ kN} \quad \checkmark \text{OK.} \end{aligned}$$

• Screed + floors + roof build ups conservatively ignored.

→ 250mm Slab
A393 mesh flying ends.