



SCHEDULE OF MATERIALS FOR SUBMISSION TO PLANNING		
Document No. S(00)01		
	ITEM	MATERIAL
1)	Paving	Sawn Sandstone (600 x 400mm), pavers 20mm thick, laid in stretcher bond pattern
2)	Gravel area	Cedagravel Stabilisation System (CED supplier) and Peashingle (10-20mm) laid on top. Edged with Everedge and laid 20mm proud of the finished gravel area
3)	Timber	Pre-treated timber oak
4)	Retaining brick walls and pillars	Red bricks to match existing wall and piers
5)	Steps 1	Step treads replaced with grey sandstone tread minimum 30mm
6)	Steps 2	Black PPC steel stair, with handrail and balustrades to match
7)	Steps 3	Timber sleepers set in a bed of concrete; infill of the steps will be stabilised gravel
8)	Bin store trellis	Western Red Cedar 1200mm high trellis to screen bin store, and fastened with stainless steel fixings
9)	New coping and pier caps	Reconstituted stone in grey/off white to match existing