

SEQUENCE OF UNDERPINNING

- 1. WORKING IN STRIPS NOT EXCEEDING 1. EXCAVATE TO REQUIRED DEPTH BENEATH FOOTING.
- 2. HACK AWAY TO PROVIDE LEVEL SOFFIT TO BRICK FOOTING AND THOROUGHLY CLEAN UNDERPINNING.
- 3. CAST NEW CONCRETE BASE INCLUDING T16 BARS AND ALLOW 24 HOURS TO CURE.
- 4. CONSTRUCT FORMWORK FOR THE STEM.
- 5. CAST MASS CONCRETE STEM TO WITHIN SOFFIT
- 6. RAM IN DRY PACK MORTAR BETWEEN EXISTING FOOTINGS.
- 7. NEVER EXCAVATE TWO ADJACENT STRIPS ALLOWING 3 DAYS FROM TIME OF DRY PACKIN
- 8. WHEN ADJACENT SECTIONS ARE OPENED EXPOSED CONCRETE SURFACES SHO THOROUGHLY CLEANED OF ALL LOOSE MATE SCRABBLED TO FORM A GOOD KEY.
- 9. UNDERPINNING TO BE AS NOTED ON DRAWING
- ALL NEW CONCRETE BELOW GROUN GRADE 40.
- 11. DRY PACK 3 : 1 SAND CEMENT.
- 12. CONTRACTOR TO CAREFULLY INSPECT ALL MASONRY PRIOR TO UNDERPINNING EACH SEQUENCE. REPORT ANY ANOMALIES TO E FOR ADVICE AND REASSESSMENT OF SCHEME
- 13. UNDERPINNING SECTIONS TO BE CAST IN N ORDER.

	REINFORCED CONCRETE NOTES
1.0M LONG	
H EXISTING	1. ALL DIMENSIONS TO BE VERIFIED ON SITE. 2. READ IN CONJUNCTION WITH ARCHITECT'S
) EXISTING	DRAWINGS.
N BEFORE	3. REINFORCED CONCRETE BEAM/SLAB/WALL TO BE CAST IN GRADE 35 N/mm2 CONCRETE AND
6 STARTER	REINFORCED IN ACCORDANCE WITH DESIGN INFORMATION AND REINFORCEMENT SCHEDULES, PROVIDED BY THE ENGINEER - MIN CEMENT CONTENT 330 kg/m2.
N 50mm OF I NEW AND	4. READY MIX CONCRETE MUST BE OBTAINED FROM A PLANT, WHICH HOLDS A CURRENT CERTIFICATE OF ACCREDITATION UNDER THE QUALITY SCHEME FOR READY MIX CONCRETE.
S WITHOUT	5. NO CONCRETE IS TO BE PLACED WHEN THE AMBIENT AIR TEMPERATURE IS LESS THAN 5 O C.
NG.	6. REINFORCEMENT SHALL BE: (TO BS 8110).
d up the Ould be Ferial and	7. ALL MAIN BARS TO BE GRADE 460 (HIGH YIELD) NOTED 'H'. PLAIN BARS (i.e. LINKS) ALSO TO BE GRADE 460 (HIGH YIELD) UNLESS STATED OTHERWISE [IN WHICH CASE; TO BS 4449, GRADE 250 (MILD STEEL)].
ND TO BE	8. REINFORCEMENT TO BE FIXED ADEQUATELY USING TYING WIRE OR STEEL CLIPS.
	9. CONCRETE COVER TO BE MIN 35 mm COVER, UNLESS STATED OTHERWISE ON DRAWING.
L EXISTING CH BAY IN ENGINEER IE.	10. UNLESS NOTED OTHERWISE ON DRAWINGS, ALL REINFORCEMENT IS TO BE LAPPED 40d (WHERE d IS THE DIAMETER OF THE LARGER BAR).
NUMERICAL	13NO WORK IS TO COMMENCE ON SITE PRIOR TO BUILDING CONTROL APPROVAL OF STRUCTURAL DETAILS.
	14. DRAWING TO BE READ WITH ENGINEERING SPECIFICATION (INCLUDING DIAGRAMATICAL DETAILS) & ARCHITECTURAL SPECIFICATION.
	PRELIMINARY
SSUE	REVISION INITIAL DATE
4 Edward Square, London N1 OSP Tel: 020 7837 5377; Fax: 020 7837 3211 Martin Redston Associates Consulting Civil & Structural Engineers	
56b King Henry's Road	
London NW3 3RP	
	PROPOSED SECTION B-B
Drawn: AOR	Checked: MR 15.700.04
Scale: AS SH	10WN Date: 31.05.16