

Project Title	S106 Works	
Location:	Adeline Place	
Client:		
Correspondence File:		

ESTIMATED/MEASURED BILL OF QUANTITIES

	DESCRIPTION		
	<p>Take up or down and remove to tip off site precast concrete or york stone paving slabs any size type including fiber reinforced up to 65mm thick</p> <p>Take up or down and remove to tip off site granite flat, edge or standard profile bus boarder kerb</p> <p>Take up or down and set aside for reuse traffic sign face, not exceeding 0.25m2</p> <p>Take up or down and set aside for reuse; standard traffic sign post any diameter</p> <p>Take up or down and set aside for reuse hooped Sheffield cycle stand or similar, any width with or without tapping rail</p> <p>Raising the level of any class of cover and frames in the footway, area of cover exceeding 0.1m2 but not exceeding 0.5m2, 50mm or less</p> <p>Raising the level of any class of cover and frames in the footway, area of covers exceeding 1.0m2 but not exceeding 1.5m2, exceeding 50mm but not exceeding 150mm</p> <p>Raising the level of any class of cover and frames in the footway, area of covers exceeding 1.5m2 but not exceeding 2.0m2, exceeding 50mm but not exceeding 150mm</p> <p>Excavation of any material in footways, verges and other pedestrian areas</p> <p>Extra over excavation for excavation in hard material in footways, verges and other pedestrian areas</p> <p>Disposal of any material.(except class U1B and U2 material)</p> <p>Completion of formation on material other than Class 1C, 6B or rock in cuttings</p> <p>Thin Surface course Systems (TSCS 10)</p> <p>30mm thick in carriageway (Ref ST10)</p> <p>Milling pavement up to a maximum thickness of 30mm</p> <p>Granite flat kerb 300x200mm, 'fine picked' finish, laid to curves not exceeding 12 metres radius</p> <p>Granite edge kerb 150x300mm, 'fine picked' finish, laid straight or curved exceeding 12 metres radius</p> <p>Extra over Granite edge kerb for laying flush and in transition at crossings and crossovers</p> <p>65mm thick Artificial Stone Paving, any BS size A,B,C or D on existing base or base measured separately and sand bedding 30mm thick</p> <p>65mm thick Artificial Stone red, buff or grey</p> <p>Tactile Blister Paving, on existing base or base measured separately and sand bedding 30mm thick</p> <p>100mm cement bound granular mixture C (Rc= C8/10) base in footways</p> <p>Remove from set aside area and re-erect Sheffield cycle stand, hooped with or without tapping rail, 1045mm or 970mm wide and 750mm above ground, surface fixed</p> <p>Remove from store on site and re-erect sign face, any shape or diagram number, on existing post or post measured separately, area not exceeding 0.50m²</p> <p>Remove from store on site and erect straight or large base sign post not exceeding 114mm diameter</p> <p>Continuous line in yellow thermoplastic screed with applied solid glass beads, 100mm wide</p> <p>Intermittent line in white thermoplastic screed with applied solid glass beads, 50mm wide in parking bays (line and gap varies)</p> <p>Intermittent line in white thermoplastic screed with applied solid glass beads, 100mm wide, 4000mm line, 2000mm gap</p> <p>Intermittent line in white thermoplastic screed with applied solid glass beads, 200mm wide, 600mm line, 300mm gap</p> <p>Worker time for other adjustments to smoke vents</p> <p>Labourer (plain time rates)</p> <p>Working Ganger (plain time rates)</p> <p>Mason (plain time rates)</p> <p>Agent/Supervisor (plain time rates)</p>		
	Sub Total	£24,458.36	
Fees	25%	£6,114.59	£30,572.95
Contingencies	15%	£4,585.94	£35,158.89
GRAND TOTAL		£35,158.89	