Third floor



Type E skirting

Stair

To be retained, carefully repaired and repainted



Type D skirting

Bedroom B

To be retained, carefully repaired and repainted



Type D skirting

Stairwell

To be removed and replaced with type E skirting



Type D skirting

Bedroom C

To be removed



Type D skirting

Bedroom A

To be retained, carefully repaired and repainted

Skirting schedule

Dado rail



Dado Rail

Stairwell

To be retained, carefully repaired and repainted

Ground floor





FP 00 01

Dining room

To be retained and carefully repaired

FP 00 02

Library

First floor



FP 01 01

Drawing room West

To be retained and carefully repaired



FP 01 02

Drawing room East

Second floor



FP 02 01

Master bedroom

Third floor





Bedroom A

To be retained and carefully repaired



FP 03 02

Bedroom B

Ground floor











ED 00 01

Four panel solid timber door

Entrance

Structural opening size - W/H - as existing

Door - to be retained, rubbed back, repaired as necessary and repainted. Weather seal cut into door leaf to be retained. New ironmongery to be installed

Architrave - N/A

PD 00 01

Four panel solid timber door

Entrance

Structural opening size - W/H - as existing

Door - new timber and glass door to be installed

Architrave - to be retained, rubbed back, repaired as necessary and repainted

PD 00 02

Four panel solid timber door

Dining room

Structural opening - W/H - to be completely opened up

Door - to be removed

Architrave- to be removed

PD 00 03

Four panel solid timber door

Library

Structural opening - W/H - to be closed up

Door - to be removed

Architrave- to be removed

PD 00 04

Four panel solid timber door

Link

Structural opening - W/H - to be widened

Door -to be removed

Architraves- to be removed

First floor





PD 01 01

Four panel solid timber door

Drawing room West

Structural opening - W/H - as existing

Door - to be retained, rubbed back, repaired as necessary and repainted. New ironmongery to be installed

Architrave - to be retained, sanded back, repaired as necessary and repainted

PD 01 02

Four panel solid timber door

Drawing room East

Structural opening - W/H - as existing

Door - to be retained, rubbed back, repaired as necessary and repainted. New ironmongery to be installed

Architrave - to be retained, sanded back, repaired as necessary and repainted

Second floor





Four panel solid timber door

Master bedroom

Structural opening - W/H - as existing

Door - to be retained, rubbed back, repaired as necessary and repainted. New ironmongery to be installed

Architrave - to be retained, sanded back, repaired as necessary and repainted



PD 02 02

Four panel solid timber door

Walk-in closet

Structural opening - W/H - as existing

Door - to be retained, rubbed back, repaired as necessary and repainted. New ironmongery to be installed

Architrave - to be retained, sanded back, repaired as necessary and repainted



PD 02 03

Four panel solid timber door

Master bathroom

Structural opening - W/H - to be repositioned

Door - to be retained, rubbed back, repaired as necessary and repainted. New ironmongery to be installed

Architrave - to be retained, sanded back, repaired as necessary and repainted

Third floor





Four panel solid timber door

Bedroom A

Structural opening - W/H - as existing

Door - to be retained. Door to be rubbed back, repaired as necessary and repainted. New ironmongery to be installed

Architrave - to be removed and replaced to match rest of architraves



PD 03 02

Four panel solid timber door

Bathroom A

Structural opening - W/H - to be removed

Door - to be removed

Architrave - to be removed



PD 03 03


Four panel solid timber door

Bedroom B

Structural opening - W/H - as existing

Door - to be retained. Door to be rubbed back, repaired as necessary and repainted. New ironmongery to be installed

Architrave - to be retained, sanded back, repaired as necessary and repainted



PD 03 04

Four panel solid timber door

Bathroom B

Structural opening - W/H - to be closed up

Door - to be removed, rubbed back, repaired as necessary, repainted and repositioned.

New ironmongery to be installed.

Architrave - to be removed and repositioned



PD 03 05

Four panel solid timber door

Bedroom C

Structural opening - W/H - to be closed up

Door - to be removed, rubbed back, repaired as necessary, repainted and repositioned.

New ironmongery to be installed.

Architrive - to be removed and repositioned