



NOTE:

The Contractor is to check and verify all building and site dimensions, levels and sewer invert levels at connection points before work starts.

This drawing must be read with and checked against any structural or other specialist drawings provided.

The Contractor is to comply in all respects with the current Building Regulations whether or not specifically stated on these drawings.

This drawing is not intended to show details of foundation or ground conditions. Each area of ground relied upon to support the structure depicted must be investigated by the Contractor and suitable methods of foundation be provided.

This drawing is to be read in conjunction with all other standard Mitchells and Butlers specifications and documentation.

© This drawing remains the copyright of Mitchells and Butlers.

**sdj DESIGN**

18 Nell Lane Chorlton Manchester M21 7UD  
Tel/Fax 0161 861 8688 e-mail sdjdesign@tesco.net

THIS DRAWING HAS BEEN PREPARED FOR PRESENTATION PURPOSES CONSULTANTS WISHING TO USE THE DRAWING FOR GUIDANCE MUST CHECK ALL DIMENSIONS ON SITE PRIOR TO FINALISING THEIR ELEMENT OF WORK UNDERTAKEN

Rev.	By	Date

**Mitchells & Butlers**

27 Fleet Street  
Birmingham  
B3 1LP  
Tel. 0870 608 3000  
www.mbutl.com

**CASTLE**

**11614**

**EDINBORO' CASTLE CAMDEN**

**GARDEN PLAN AS PROPOSED**

Project Manager/ Checked	Drawn By	Scale	Date
Arch/Des	Drawing Number		
	ECG 02		

**LIGHTING NOTES**

**EXISTING LIGHTING**  
All tree existing tree uplighters & fairy lighting to remain as existing and re-lamped and repaired as necessary. (not shown on drg). Existing Quartz heaters to Jumbrella are not shown but to remain.

- Existing Lantern to be retained & re-lamped and made working as necessary
- Existing Lantern to be removed and wiring point adapted as indicated
- Existing Gas Heaters re-located to new positions as indicated (by Main contractor)

- New FITTINGS
- New 60w size large festoon lighting to existing posts (existing to be taken down from posts)
- Medium capsule lamp size festoon lighting
- External IP rated PAR 38 spots with red Lamp
- 'WETSY' buried LED uplighter - white light
- New Blanket fairy lighting nets to cover Pergola. These to be fitted to underside of new trellis with cable ties by Main Contractor. Lumax - Please note these are not shown on drawing but should be sufficient in quantity to cover the whole of the pergola area. Please
- TANSUN Quartz Heaters (supply by Electrical Contractor)

**FURNITURE NOTES & KEY**

Furniture shown in BLACK is existing and Furniture shown in PURPLE is new.

Site dimensions to be taken for fitted furniture (made to fit). BJ to check with TR Builders internal dimensions of market stall has not changed from drg.

All existing furniture to remain on site and decorated/repainted/left as existing by Main Contractor. Picnic benches to be painted in approx 50% mix of each colour - Dulux 10RR 13/081 (dark plum) Dulux 10GG 13/057 (green) Paints in exterior satin finish.

RBM/LHM to advise on what is to happen to the remaining furniture which is not being re-used in the proposed furniture layout.

Main Contractor to lay out Furniture as shown. Furniture not taken away for re-upholstery to be stored safely on site for re-use.

BJ to refer to furniture schedule also.

**GENERAL NOTES**

- This drawing to be read in conjunction with drawing ECG 01 which shows location of existing furniture.
- Please refer to drawing ECI 03 for details of works to Interior.
- All existing tree uplighters and fairy lights to be repaired and re-lamped as necessary.
- Also refer to mood board for details.
- 

MC New furniture by Main Contractor  
BX existing furniture to be reupholstered by BJ  
B New furniture supplied by BJ  
X existing furniture - no works (see notes on drg)

high indicates poseur height  
med indicates dining height  
low indicates 600h approx height