

SITE INVESTIGATION FACTUAL REPORT

Report No: 287859
Client: Crawford Claims Management
Site: 16 Heath Hurst Road, London

Client Ref: SU1503854-
Date of Visit: 04/12/2015




Home Emergency Response - Subsidence Investigation - Drainage Services – Crack & Level Monitoring – Property Video Surveys

Unit E2 First Floor Suite, Boundary Court
Willow Farm Business Park, Castle Donington
Leicestershire, DE74 2NN



CET is the trading name of CET Structures Ltd
Registered in England No. 02527130



Remarks:

Original house (x2) was approx 1m shorter than it is now PH advised.
 Parking - permit.
 Water supply - outside tap.
 Site access - through house.

Scale: N.T.S.

Key:

- Combined Gully RWWG
- Manhole MH
- Rain Water Pipe RWP
- Rain Water Gully RWG
- Soil Vent Pipe SVP
- Waste Gully WG
- Waste Pipe WP

Surface Water Drain



Foul Water Drain


Tree / Bush
(approx. ht in m)

Trial Pit

Borehole

O/D - Open Discharge





Borehole No: 1		Sheet: 1 of 1		Job No: 287859		Site: 16 Heath Hurst Road			
Boring Method: Hand Auger		Date: 04.12.15		Ground Level mOD:		Work Carried out for: Crawford Claims Management Ltd			
Diameter: 75mm	Coordinates:		Ground Level mOD:		Work Carried out for: Crawford Claims Management Ltd				
Depth (m)	Description of Strata	Thickness (m)	Legend	Sample	Test Type	Result	Depth (m)	Field Records/Comments	Depth to water (m)
0.72	As Trial Pit 1	0.72							
1.00	Firm, mid brown, mottled orange, grey veined, silty CLAY with partings of orange silt & fine sand & carbon flecks.	0.28	—x	D	V	132 136	1.00	Roots of live appearance to 2mm diameter to 1m, 2mm diameter roots to 2m & 1mm diameter roots to 2.6m	
1.50	Stiff, mid brown, grey veined, silty CLAY with partings of orange silt & fine sand & crystals.	0.50	—x	D	V	140+ 140+	1.50		
3.00	Very stiff, as above.	1.50	x—	D	V	140+ 140+	2.00	No roots observed below 2.6m	
			—x	D	V	140+ 140+	2.50		
	Borehole ends at 3m		—x	D	V	140+ 140+	3.00		
Remarks: Borehole dry and open on completion					Key: T.D.T.D. Too Dense to Drive D Small disturbed sample J Jar sample B Bulk disturbed sample V Pilcon Vane (kPa) W Water sample M Mackintosh Probe				
Logged: AC	Checked: SA	Typed by: DVC		Scale: NTS	Weather: DRY				

Laboratory Summary Results

Our Ref: 287859 Date Sampled: 04/12/2015
 Location: 16, Heath Hurst Road, London, NW3 Date Received: 07/12/2015
 Work carried out for: Crawford Claims Management Date Tested: 08/12/2015
 Date of Report: 15/12/2015

TP/BH No	Sample Ref ¹		Moisture Content (%) [11]	Soil Friction > 0.425mm (%) [21]	Liquid Limit (%) [31]	Plastic Limit (%) [41]	Plasticity Index (%) [51]	Liquidity Index [51]	Modified Plasticity Index (%) [61]	Soil ² Class [71]	Filter Paper Contact Time (h) [81]	Soil Sample Suction (kPa) [81]	Oedometer Strain [91]	Estimated Heave Potential (Dd) (mm) [101]	In situ ³ Shear Vane Strength (kPa) [111]	Organic ⁴ Content (%) [121]	pH ⁵ Value [131]	Sulphate Content ⁶ (g/L)			Class [161]
	Depth (m)	Type																903	904	151	
1	U/S 0.52	D	38	<5	94	32	62	0.10	62	CE	168	284			47						
	1.0	D	28	<5	80	27	53	0.01	53	CV	168	859			134						
	1.5	D	27	<5							168	870			> 140						
	2.0	D	28	<5	79	26	53	0.04	53	CV	168	790			> 140						
	2.5	D	31	<5							168	539			> 140						
	3.0	D	33	<5	83	31	52	0.03	52	CV	168	600			> 140						

Test Methods / Notes

[1] In-house Test Procedure S1 Die One Dimensional Swell/Shrink Test
 [2] BS 1377: Part 2: 1990, Test No 3.2
 [3] BS 1377: Part 2: 1990, Test No 4.4
 [4] BS 1377: Part 2: 1990, Test No 5.3
 [5] BS 1377: Part 2: 1990, Test No 5.4
 [6] BRE Digest 240: 1993
 [7] BS 5930: 1981, Figure 31.1 - Plasticity Chart for the classification of fine soils
 [8] In-house method S96, adapted from BRE IP 493
 [9] In-house Test Procedure S1 Die One Dimensional Swell/Shrink Test
 [10] Estimated Heave Potential (Dd)
 [11] Values of shear strength were determined in situ by CUE testing
 [12] BS 1377: Part 3: 1990, Test No 4
 [13] BS 1377: Part 2: 1990, Test No 9
 [14] BS 1377: Part 3: 1990, Test No 5.6
 [15] SO = 1.2 x SO_u
 [16] BRE Special Digest One (Concrete in Aggressive Ground) August 2005
 Note that if the SO4 content falls into the DS-4 or DS-5 class, it would be prudent to consider the sample as falling into the DS-4M or DS-5M class respectively unless water soluble magnesium testing is undertaken to prove otherwise.
 * These tests are not UKAS accredited
 Full reports can be provided upon request

Key

D Disturbed sample (small)
 D Disturbed sample (bulk)
 U Undisturbed sample
 W Groundwater sample
 LNP Essentially Non-plastic by inspection
 US Underside of Foundation




Version: SBH V1.4 - 11/05/15
 86118

Moisture Content Profiles


Our Ref: 287859
 Location: 16, Heath Hurst Road, London, NW3
 Work carried out for: Crawford Claims Management

Date Sampled: 04/12/2015
 Date Received: 07/12/2015
 Date Tested: 08/12/2015
 Date of Report: 15/12/2015



Notes:
 1. If plotted, $0.4LL$ and $PL-2$ (after Dinseff, 1983) should only be applied to Loam, Clay, and similarly overconsolidated clay / silty shallow deposits.
 2. Unless specifically noted the profiles have not been related to a site datum.

Shear Strength Profiles





Notes:
 1. Unless otherwise stated, values of Shear Strength were determined in situ by CU using a Picon Hand Vane the calibration of which is limited to a maximum setting of 140 kPa.
 2. Unless specifically noted the profiles have not been related to a site datum.

Moisture Content Profiles

Our Ref: 287859
 Location: I6, Heath Hurst Road, London, NW3
 Work carried out for: Crawford Claims Management

Soil Suction Profiles

Date Sampled: 04/12/2015
 Date Received: 07/12/2015
 Date Tested: 08/12/2015
 Date of Report: 15/12/2015



Notes

1. If plotted, $0.4 LL$ and $PL-2$ (after Dinssell, 1983) should only be applied to London Clay (and similarly overconsolidated clay) at shallow depths.
2. Unless specifically noted the profiles have not been defined to a safe datum.

Note

When shown, the theoretical equilibrium suction profiles are based on conventional assumptions associated with London Clay (and similarly overconsolidated clay) at shallow depths. Note that the sample disturbance component is dependent on the method of sampling and any subsequent re-compaction. The above plots allow this to be identified, which is the value suggested by the BSC on the basis of their limited number of tests on re-compacted samples. This may or may not be appropriate in this instance and judgement should be exercised!

Certificate of Analysis

The following work was commissioned by CET on behalf of their client. Root samples were obtained in sealed packets from the above site with no reference given as to the types of tree or shrub from which they may have originated.
The results were as follows -

<u>Trial pit/ Borehole number</u>	<u>Root diameter (mm)</u>	<u>Tree, shrub or climber from which root originates</u>	<u>Result of starch test</u>
TP1 (USF)	1.5 mm	Rosa spp. 3 roots	Positive
TP1 (USF)	1.5 mm	Fraxinus spp. 2 roots	Positive
BH1 (0.72-2m)	2 mm	Rosa spp.	Positive
BH1 (0.72-2.6m)	1 mm	Fraxinus spp. 4 roots	Positive

Rosa spp. are roses.
Fraxinus spp. include common ash.



MDM

Address for correspondence: EPSL, Intec, Parc Menai, Bangor, Gwynedd, North Wales, LL57 4FG


Head of Laboratory Services : M D Mitchell B.Sc. (Hons), M.Phil.

Plant Anatomist : Dr G S Turner B.Sc. (Hons), M.Sc., Ph.D

Plant Anatomist : Dr D P Aebischer B.Sc. (Hons), M.Sc., Ph.D

Consultant: Dr M P Denne B.Sc. (Hons), M.Sc., Ph.D

Registered in England. No 3256771, Registered Office: Yarmouth House, 1300 Parkway, Solent Business Park, Hampshire, PO15 7AE



To:
Fiac: Gordon McEwan
Site:

Crawford Claims Management
16 Heath Hurst Road

Client Ref: SU1503854
Job No: 287859
Claim No:
Date: 10-Dec-15

ESTIMATE

Item	Amount
No recommendations required to the private drainage surveyed.	

Notes

Repairs to shared runs and off boundary pipe-work may be the responsibility of the water authority.

Condition Grade

- A - Structurally sound with no leakage evident.
- B - Cracks and fractures observed.
- C - Structurally unsound

Quotation is binding only if accepted within 28 days from date of issue and is subject to our Standard Terms and Conditions
The price qualification notes, stated on the drainage solutions schedule of rates, apply to this quotation.
CET Structures Ltd undertakes to return to site free of charge to carry out remedial work to the drainage repairs set out above for a period of 2 months from the date of this invoice. The company standard charge rates will apply to the visit should the work requested be unrelated to the said repairs.

Underground Drainage Report	Sheet: 1 of 3	Site: 16 Heath Hurst Road
	Job No: 287859	Work carried out for: Crawford Claims Management
	Date: 4-Dec-15	
<u>MANHOLE DETAILS</u>		
Manhole	Depth to Invert	Condition
MH1	1100mm	As built
<u>CCTV Survey:-</u>		
1. Drainage Run:		
From manhole 1 run 1 to upstream - 150mm clay combined - upstream (not shared)		
Metres:	Code:	Observations:
		Surface Material/ Condition:
0.0		Start
0.1	WL	Water level 20%
0.7	DC	Dimension of sewer changes to 100mm
2.0	JN	Junction at 3 o'clock 100mm WG1 (JN1)
4.3	JN	Junction at 3 o'clock 100mm RWG1 (JN2)
5.2	LR	Line right
6.2		Under house (laminated floor)
8.8	DE	Debris 20%
9.0	JN	Junction at 3 o'clock capped off
9.2	DE	Debris 100%
9.2	FH	Finish - unable to push further
Note: Run appears disused after JN at 4.3m		
Water Test Grade:		
0 - Unable to fill	2 - Medium Loss over 2 minutes	
1 - Heavy Loss	3 - Slow Loss over 5 minutes	
	4 - No Loss	

Underground Drainage Report	Sheet: 2 of 3	Site: 16 Heath Hurst Road
	Job No: 287859	Work carried out for: Crawford Claims Management
	Date: 4-Dec-15	
2. Drainage Run:		
From manhole 1 run 2 to soil stack - 100mm plastic foul water - upstream (not shared)		
Metres:	Code:	Observations:
		Surface Material/ Condition:
0.0		Start
0.5		Concrete
0.8	DE	Under house
1.0	WL	Debris 30%
2.5	WL	Water level 20%
3.0	WL	Water level 20%
4.1	LU	Water level 10%
4.4	FH	Line up
		Finish - reached soil stack
3 Drainage Run:		
From manhole 1 run 3 to soil vent pipe 1 - 100mm clay foul water - upstream (not shared)		
Metres:	Code:	Observations:
		Surface Material/ Condition:
0.0		Start
0.7	LU	Concrete
0.8	FH	Line up
		Finish - reached SVP1
4 Drainage Run:		
<i>Break in</i> junction in run 1 - run 4 to waste gully 1 - 100mm clay foul water - upstream (not shared)		
Metres:	Code:	Observations:
		Surface Material/ Condition:
0.0		Start
0.8	LU	Concrete
1.0	FH	Line up
		Finish - reached WG1
Gully condition:	As built	
Water Test Grade:		
0 - Unable to fill	2 - Medium Loss over 2 minutes	
1 - Heavy Loss	3 - Slow Loss over 5 minutes	
	4 - No Loss	

Underground Drainage Report	Sheet: 3 of 3	Site: 16 Heath Hurst Road	
	Job No: 287859	Work carried out for: Crawford Claims Management	
	Date: 4-Dec-15		
5 Drainage Run:			
<i>Break in junction in run 1 - run 5 to rain water gully 1 - 100mm clay surface water - upstream (not shared)</i>			
Metres:	Code:	Observations:	
		Surface Material/ Condition:	
0.0		Start	
0.3	LU	Line up	
0.3	FH	Finish - reached RWG1	
Gully condition:	As built		
- End of Survey -			
<table border="1"> <tr> <td> <p><i>Our assessment of the drainage system is based on our visual inspection and on information collated at the time of the survey. Where assumptions have been made these are based on our experience and do not constitute any form of guarantee, nor do we guarantee that further deterioration will not occur following this survey. CCTV video records will be stored for a period of 3 months from date of inspection and then destroyed.</i></p> </td> </tr> </table>			<p><i>Our assessment of the drainage system is based on our visual inspection and on information collated at the time of the survey. Where assumptions have been made these are based on our experience and do not constitute any form of guarantee, nor do we guarantee that further deterioration will not occur following this survey. CCTV video records will be stored for a period of 3 months from date of inspection and then destroyed.</i></p>
<p><i>Our assessment of the drainage system is based on our visual inspection and on information collated at the time of the survey. Where assumptions have been made these are based on our experience and do not constitute any form of guarantee, nor do we guarantee that further deterioration will not occur following this survey. CCTV video records will be stored for a period of 3 months from date of inspection and then destroyed.</i></p>			
Water Test Grade:			
0 - Unable to fill	2 - Medium Loss over 2 minutes		
1 - Heavy Loss	3 - Slow Loss over 5 minutes		
	4 - No Loss		

Water Authority Sewer Condition Codes

B Broken pipe at... (or from... to...) o'clock	JN Junction at...o'clock, diameter...mm
BR Branch Major	JX Junction defective at.. o'clock, diameter.. mm
CC Crack circumferential from... to... o'clock	LC Lining of sewer changes/starts/finishes at this point
CL Crack longitudinal @... o'clock	LD Line of sewer deviates down
CM Cracks multiple from... to... o'clock	LL Line of sewer deviates left
CN Connection at... o'clock, diameter... mm	LN Line defect at (or from.. to..) o'clock
CNI Connection at... o'clock, diameter... mm, intrusion... r	LR Line of sewer deviates right
CU Camera under water	LU Line of sewer deviates up
CX Connection defective at... o'clock	MB Missing bricks at.. (or from.. to..) o'clock
CXI Connection defective at... o'clock, diameter... mm, intrusion... mm	MC Material of sewer changes at this point
D Deformed sewer... %	MH Manhole/node
DB Displaced bricks at (or from.. to..) o'clock	MM Mortar missing medium at.. (or from.. to..) o'clock
DC Dimension of sewer changes at this point	MS Mortar missing surface at.. (or from.. to..) o'clock
DE Debris (non silt/grease)... % cross-sectional loss	MT Mortar missing total at.. (or from.. to..) o'clock
DEG Debris grease... % cross-sectional area loss	OB Obstruction... % height/diameter loss
DES Debris silt... % cross-sectional area loss	OJL Open joint large
DI Dropped invert, gap... mm	OJM Open joint medium
EHJ Encrustation heavy from.. to.. o'clock % cross-sectional area loss (at joint)	PC Length of pipe forming sewer changes at this point, new length...mm
ELJ Encrustation light from.. to.. o'clock%	RFJ Roots fine (at joint)
EMJ Encrustation medium from.. to.. o'clock %, cross-sectional area loss (at joint)	RMJ Roots mass... % cross-sectional area loss (at joint)
ESH Scale heavy... % cross-sectional area loss from... to.. o'clock	RTJ Roots tap (at joint)
ESL Scale light from... to... o'clock	SA Survey abandoned
ESM Scale medium... % cross-sectional area loss from... to... o'clock	SC Shape of sewer changes at this point
FC Fracture circumferential from... to... o'clock	SSL Surface damage, spalling large at (or from.. to..) o'clock
FL Fracture longitudinal at... o'clock	SSM Surface damage, spalling medium at (or from.. to..) o'clock
FM Fractures multiple from... to... o'clock	SSS Surface damage, spalling slight at (or from.. to..) o'clock
GO General observation at this point	SWL Surface damage, wear large at... (or from.. to..) o'clock
GP General photograph number... taken at this point	SWM Surface damage, wear medium at... (or from.. to..) o'clock
H Hole in sewer at... o'clock	SWS Surface damage, wear slight at.. (or from.. to..) o'clock
IDJ Infiltration dripper at (or from... to...) o'clock (at joint)	V Vermin (rats and mice)
IGJ Infiltration gusher at (or from... to...) o'clock (at joint)	WL Water level... % height/diameter
IRJ Infiltration runner at (or from... to...) o'clock (at joint)	X Sewer collapsed... % cross-sectional area loss
ISJ Infiltration seeper at (or from... to...) o'clock (at joint)	FH End of survey
JDM Joint displaced medium	
JDL Joint displaced large	

Contract: 287859


Date: 04-Dec-15

Site Address: 16 Heath Hurst Road

Operative Initial: AC

Page: 1 of 1

M/H: 1 Depth: 1100mm



Chamber Dimension (mm): 600 X 450


Depths of run if different to invert level:-

Run _____

Manhole Condition

As built

M/H: Depth:




Chamber Dimension (mm):

Depths of run if different to invert level:-

Run _____

Manhole Condition

M/H: Depth:



Chamber Dimension (mm):

Depths of run if different to invert level:-

Run _____

Manhole Condition

KEY...



Internal Back Drop



External Back Drop



Interceptor

Water Pressure Test Results

From:

To:

Pass / Fail