

Arboricultural Consultancy
Holmwood Farm Grange Horsham Road North Holmwood Dorking Surrey RH5 4JR
Tel: 01306 743374 Email: info@challiceconsulting.co.uk Web: www.challiceconsulting.co.uk

Our Ref: CC/1514 AR2827

16th December 2015

Mr. Simon Goldstein Squire & Partners 77 Wicklow Street London WC1X 9JY

Dear Mr. Goldstein,

#### Re: Tree Protection Relating to 192 Haverstock Hill, London NW3 2AJ

Please find enclosed an arboricultural report relating to the proposed development at the above site. I would be grateful if you could review the contents of this report to ensure it meets your requirements before it is forwarded to the Local Planning Authority. A copy of this report should be maintained on site at all times and be available to all site personnel.

Attendance at the pre-commencement meeting and for inspections/supervision (sections 16.0 and 27.0 of report) is chargeable at the standard hourly rate, details of which are available upon request.

I hope that this information is clear and helpful and if I can be of any further assistance, please do not hesitate to contact me.

Yours sincerely,

Mr. David Challice

Chartered Arboriculturist

Challice

Enc.

# Tree Survey Arboricultural Impact Assessment Arboricultural Method Statement

# Relating to:

# 192 Haverstock Hill, London NW3 2AJ

#### **Produced for:**

Squire & Partners

#### Prepared by:

Challice Consulting Ltd.
Mr. David Challice
Dip. Arb. (RFS), F.Arbor.A, MICFor

#### Date:

16th December 2015

#### Our Ref:

CC/1514 AR2827

INTRODUCTION	SECTION
Frequently Used Key Terms and Abbreviations	1.0

Frequently Used Key Terms and Abbreviations	1.0
The Proposal	2.0
Instructions and Purpose	3.0
Scope	4.0
Documents Supplied/Used	5.0
Site Details	6.0

#### TREE SURVEY

Survey Method	7.0
Tree Details	8.0

#### ARBORICULTURAL IMPACT ASSESSMENT

Introduction to Arboricultural Impact Assessment	9.0
Tree Removal and Retention	10.0
Tree Pruning Works	11.0
Incursions into Root Protection Areas	12.0
Proximity Issues and Shading	13.0
Summary of Arboricultural Impact	14.0

### ARBORICULTURAL METHOD STATEMENT

Introduction to Arboricultural Method Statement	15.0
Pre-Commencement Meeting	16.0
General Site Precautions	17.0
Tree Works	18.0
Tree Protective Fencing	19.0
Ground Protection	20.0
Site Access/Hard Surfaces	21.0
Demolition	22.0
Underground Services	23.0
Foundations	24.0
Construction/Hard Landscaping	25.0
Soft Landscaping/Boundary Fencing	26.0
Sequencing and Supervision	27.0
Amendments	28.0

#### **APPENDICES**

Appendix 1	List of Contacts
Appendix 2	Tree Survey Schedule with Recommended Tree Works
Appendix 3	Tree Protection Plan in Colour at A1 and Scale 1:100 with Tree
	Protective Fencing Specification
Appendix 4	Example of Site Inspection Record
Appendix 5	Induction Form for Personnel

# **INTRODUCTION**

# 1.0 Frequently Used Key Terms and Abbreviations

Tree Preservation Order	TPO
Arboricultural Method Statement	AMS
British Standard 5837:2012 – Recommendations for Trees in	BS 5837
Relation to Design, Demolition and Construction	
British Standard 3998:2010 - Recommendations for Tree Work	BS 3998
Root Protection Area/Root Protection Areas	RPA/RPAs
Local Planning Authority	LPA

#### 2.0 The Proposal

2.1 The proposal is to demolish an existing single storey building and erect a five storey building, plus basement, to create retail space at ground and basement levels (Class A1), and five self-contained flats. Planning consent was granted by Camden Council for an amended scheme (reference 2014/6672/P) on 27<sup>th</sup> January 2015. The original consent was granted on 29<sup>th</sup> November 2013 (reference 2012/5391/P).

#### 3.0 Instructions and Purpose

- 3.1 This report has been commissioned by Squire & Partners to;
  - Survey the trees in accordance with British Standard (BS 5837)
     5837:2012 Trees in Relation to Design, Demolition and Construction- Recommendations.
  - Detail the arboricultural impact of the proposed project.
  - Prepare a tree work schedule to British Standard (BS 3998)
     3998:2010 Recommendations for Tree Work.
  - Develop a tree protection strategy for the duration of the development including any demolition works.
  - Present the necessary arboricultural information to discharge Condition 8 of Planning Consent reference 2014/6672/P issued by Camden Council on 27<sup>th</sup> January 2015.
  - Provision of the above information is designed to address the requirements of the LPA in terms of the arboricultural information necessary to register and determine the planning application.

#### 4.0 Scope

4.1 In surveying the trees to the requirements of BS 5837, trees on and immediately adjacent to the site with a stem diameter over 75mm have Challice Consulting Ltd.

Holmwood Farm Grange Horsham Road North Holmwood Dorking Surrey RH5 4JR Tel: 01306 743374 Email: info@challiceconsulting.co.uk Web: www.challiceconsulting.co.uk

been included. Large shrubs and hedges have been included where these are considered to be of significant amenity value. These are particularly important where they provide boundary screening. For clarity and ease of data interpretation, large shrubs have been classified as trees.

4.2 A full hazard assessment of the trees (including the assessment of decay or defects and their impact), has not been undertaken as this is considered beyond the scope of this report. Any obvious hazards and defects have been identified in the Tree Survey Schedule and appropriate works recommended for immediate action.

#### 5.0 Documents Supplied/Used

Document	Obtained From	Format/Ref.
Existing and proposed layout plans	Squire & Partners	Dwg.

#### 6.0 Site Details

- 6.1 The site is comprised of a single storey commercial building, situated on the northeastern side of Haverstock Hill.
- 6.2 The site is largely flat with no significant inclines in any direction.
- 6.3 The site is within the administrative jurisdiction of London Borough of Camden Council.
- 6.4 I have not been instructed to ascertain the protection status of any of the trees on or near the site.

#### TREE SURVEY

#### 7.0 Survey Method

7.1 The site and trees were inspected on 9<sup>th</sup> December 2015.

- 7.2 The trees were inspected from ground level and no climbing inspections were undertaken.
- 7.3 Heights of the trees were estimated by eye and crown spreads were estimated by pacing.

#### 8.0 Tree Details

8.1 The total number of records is as follows:

Individual Trees (T): 2

Tree Groups (G): 0

- 8.2 The tree details and proposed works are presented in the Tree Survey Schedule with Recommended Tree Works at **Appendix 2** and tree positions are shown on the Tree Protection Plan at **Appendix 3**.
- 8.3 The quality and value of the tree stock has been broken down by BS 5837 quality grade. The grading system can be summarised as follows:

**A Grade** – trees of high quality and value with a life expectancy of more than 40 years

**B Grade** – trees of moderate quality and value, with a life expectancy of more than 20 years

**C Grade** – trees of low quality and value, with a life expectancy of more than 10 years

U Grade - trees for removal, with a life expectancy of less than 10 years

#### **Quality and Value of Existing Tree Stock**

Total No. Trees (2)	A Grade	B Grade	C Grade	U Grade	
No. of Trees	1	1	0	0	

8.4 The RPAs of the trees are included in the Tree Survey Schedule with reference to Table 1 of BS 5837. The RPA is the area, measured in m<sup>2</sup>, which is calculated in accordance with the BS 5837 using the stem

diameter of the trees. This should provide retained trees with sufficient rooting environment to survive the proposed development.

#### ARBORICULTURAL IMPACT ASSESSMENT

#### 9.0 Introduction to Arboricultural Impact Assessment

9.1 This section comprises an assessment of the impact the proposed works detailed in Section 2 above have on trees. It considers the arboricultural impact and how this may be mitigated.

#### 10.0 Tree Removal and Retention

10.1 The proposed scheme provides for the retention and protection of both the surveyed trees.

#### 11.0 Tree Pruning Works

11.1 Minor tree pruning works are recommended to Sycamore T2 to ensure reasonable clearance from the proposed construction. The pruning described in the Tree Survey Schedule with Recommended Tree Works at **Appendix 2** will not adversely affect the trees or their contribution to local amenity.

#### 12.0 Incursions into Root Protection Areas

- 12.1 There are no incursions into the RPAs of retained trees within this scheme.
- 12.2 No new underground services are to be installed within the RPAs of retained trees.

### 13.0 Proximity Issues and Shading

13.1 The approximate shade segments for surveyed trees have been plotted using the ArborCAD software system, which identifies the area of the site which may be affected by shade during the course of the day. The shade

Challice Consulting Ltd.

Holmwood Farm Grange Horsham Road North Holmwood Dorking Surrey RH5 4JR Tel: 01306 743374 Email: info@challiceconsulting.co.uk Web: www.challiceconsulting.co.uk

segment does not represent the area which will be in shade all day long; however, it represents an area which **may** be affected **at some point** during the course of a day by shade depending on the time of day and season.

- 13.2 The juxtaposition between retained trees and the proposed development is in accordance with Section 5.3 of the BS 5837 and should not lead to future pressure to heavily prune or remove retained trees for the following reasons:
  - 1. Tree pruning has been recommended to provide adequate separation between the proposed development and the retained trees.
  - 2. Any future tree pruning works are unlikely to be over and above those generally accepted as good arboricultural practice in an urban environment.

#### 14.0 Summary of Arboricultural Impact

- 14.1 In summary, the arboricultural impact of the proposed scheme is minor as no trees are to be removed and minimal pruning is required to enable construction works to be completed.
- 14.2 The surveyed trees can be afforded an appropriate degree of protection in accordance with the BS 5837 as detailed in the AMS.

#### ARBORICULTURAL METHOD STATEMENT

#### 15.0 Introduction to Arboricultural Method Statement

- 15.1 To safeguard the retained trees (both above and below ground parts) during the development works and preserve the soil structure of areas which have been allocated for new planting, it will be necessary to implement tree protection measures as outlined below.
- 15.2 The basic principle is that the area inside the tree protective fencing and where ground protection has been used is to be protected for the duration of the works.

- 15.3 A copy of this AMS shall be maintained on site at all times and made available to all site personnel.
- 15.4 All site personnel shall be made aware of the key impact of this AMS and be given an arboricultural induction by the Site Manager. An Induction Form is attached at **Appendix 5**. A copy of the Induction Form will be signed by all site personnel to confirm that they have understood the issues involved.
- 15.5 As of 2005, Local Planning Authorities have powers to serve **Temporary Stop Notices** if agreed tree protection measures are not carried out. Adhering to this AMS will ensure that such costly and time consuming action is avoided.

#### 16.0 Pre-Commencement Meeting

16.1 A pre-commencement site meeting, involving representatives from the Development Company, the Arboricultural Consultant and the LPA Tree Officer will be held to ensure that all aspects of the tree protection process are understood and agreed. A record of the meeting will be communicated to all parties by the Arboricultural Consultant.

#### 17.0 General Site Precautions

- 17.1 The following points will be observed at all times:
  - No fires will be lit on site during the construction or demolition phases.
  - No access will be permitted inside the tree protective fencing.
  - No materials, equipment or debris will be stored within the tree protective fencing.
  - Notice boards, telephone cables or other services will not be attached to any parts of retained trees.
  - Materials which will contaminate the soil (e.g. diesel oil and vehicle washings) will not be permitted to migrate into the RPAs of retained trees.

 A dedicated mixing and cleaning area will be set up to prevent concrete, cement and cleaning residue leaching into the RPAs of the retained trees (see Tree Protection Plan for specification).

#### 18.0 Tree Works

- 18.1 All works will be carried out in accordance with BS 3998:2010 'Recommendations for Tree Work' (as amended) and to current arboricultural best practice. Tree works will be carried out by a suitably qualified and experienced Arboricultural Contractor holding the necessary insurance cover. This contractor should carry out the relevant site specific risk assessments and record such information prior to commencement of tasks and work in accordance with current health and safety standards, practices and legislation. A list of such contractors is available from the Arboricultural Association at www.trees.org.uk.
- 18.2 The subject trees may be protected by virtue of being within a Conservation Area or covered by a by a TPO. Submission of this AMS in connection with a planning application should be construed as a formal application to carry out those works specified in the Tree Survey Schedule with Recommended Tree Works at **Appendix 2**. It is recommended that this matter be clarified in writing with the LPA prior to any works commencing.
- 18.3 In addition, prior to the commencement of any tree works, an ecological assessment of specific trees may be required to ascertain whether protected species (e.g. bats, badgers and certain invertebrates) may be affected.
- 18.4 If additional pruning of trees is required to facilitate the proposed works or access for machinery/plant, the Arboricultural Consultant will be contacted to advise on appropriate works and liaise with the LPA as necessary.

#### 19.0 Tree Protective Fencing

- 19.1 Tree protective fencing is used to ensure that the RPAs of retained trees are safeguarded. These measures may also be employed to protect areas of ground for new landscaping.
- 19.2 The positioning and specification of the fencing is shown in **Appendix 3**. In this case, the default specification of BS 5837 consisting of **fixed Heras** fencing would be effective.
- 19.3 The protective fencing will remain in position for the duration of the development, including the removal of any existing structures. Clear signs will be attached to the fencing once erected suggested wording will be 'Construction Exclusion Zone No Access'.

#### 20.0 Ground Protection

20.1 In this instance, there is no requirement for ground protection as the RPAs of the retained trees can be afforded an adequate degree of protection using tree protective fencing and existing fencing at the front of the site.

#### 21.0 Site Access/Hard Surfaces

21.1 The existing driveway into the rear of the site is suitable for site access during construction and little or no damage is anticipated to the root systems of retained trees.

#### 22.0 Demolition

22.1 There is no requirement for demolition within the RPAs of retained trees.

#### 23.0 Underground Services

23.1 The proposed scheme can make use of existing services and all new services and soakaways will be located in the adequate space outside the RPAs of the retained trees.

23.2 The locations of all new services will be available for review at the precommencement site meeting before any works start on site.

#### 24.0 Foundations

24.1 The foundations for the proposed development are located outside the RPAs of retained trees, therefore, the design and installation of specialised foundations is not required.

#### 25.0 Construction/Hard Landscaping

- 25.1 There is no requirement for additional construction or hard landscaping that will affect the surveyed trees.
- 25.2 Construction is taken to include erection of scaffolding and the installation of associated hard landscaping features such as retaining walls, patios, and cycle stores.
- 25.3 In this instance, retained trees will not impede the erection of scaffolding and no ancillary structures are proposed within the RPAs of the retained trees.
- 25.4 Subject to all of the above tree protection measures being implemented, construction works may proceed without risk of damage to retained trees.

#### 26.0 Soft Landscaping/Boundary Fencing

- 26.1 Soft landscaping will be undertaken when heavy machinery has been removed from site and tree protective fencing taken down. The following points will be observed:
  - Care will be taken not to compact the soil within the RPAs of retained trees or where new tree planting is to be carried out.
  - No changes in ground levels will occur within the RPAs of the retained trees.
  - Unwanted vegetation will be removed manually or using contact herbicides that will not damage existing tree roots.

Challice Consulting Ltd.

Holmwood Farm Grange Horsham Road North Holmwood Dorking Surrey RH5 4JR Tel: 01306 743374 Email: info@challiceconsulting.co.uk Web: www.challiceconsulting.co.uk

- No irrigation or drainage pipes will be installed within the RPAs of retained trees.
- If soil has been compacted in areas where planting is proposed, measures to improve soil structure (e.g. decompaction) may be necessary to facilitate successful plant establishment.
- Where fence posts are being installed within the RPAs of retained trees, this will be undertaken under arboricultural supervision.
   Fence post holes shall be lined with polythene where concrete is used to prevent the harmful cement leaching into the soil and damaging the roots of the retained trees.

#### 27.0 Sequencing and Supervision

- 27.1 Effective tree protection relies on following a logical sequence of events and arboricultural inspection/supervision.
- 27.2 Works which have the potential to affect trees will be supervised by a suitably qualified and experienced Arboricultural Consultant. Regular inspection visits will also be undertaken to ensure that tree protection measures are being adhered to. The final details of supervision and the frequency of inspection visits will be agreed at the pre-commencement meeting. The Arboricultural Consultant will make a record of visits, which will be attached to the site copy of the AMS for inspection and communicated in writing to the LPA. An example of the Site Inspection Record is found in **Appendix 4**.

#### **Sequencing and Supervision**

Stage	Action	Personnel				
1.	Issue arboricultural report to site manager	Client/Developer				
2.	Give Arboricultural Consultant (AC) at least a week's notice of pre-commencement meeting	Client/Developer				
3.	Pre-commencement meeting	Site Manager, Tree Officer and AC				
4.	Arboricultural induction	All personnel				
5.	Carry out tree works	AC to monitor				
6.	Erect tree protective fencing	AC to inspect				
7.	Install underground services outside the RPAs of the retained trees	Site Manager				
8.	Erect scaffolding and carry out construction (including hard landscaping)	Site Manager				
9.	Remove machinery/plant	Site Manager				
10.	Remove tree protective fencing	Site Manager				
11.	Carry out soft landscaping and erect boundary fencing	Site Manager to brief landscaping company on site and supervise				


#### 28.0 Amendments

28.1 Issues sometimes arise on development sites which require amendments to the previously agreed tree protection details. Any amendments to this AMS will be discussed with the Arboricultural Consultant and approved in writing by the LPA prior to being implemented. Copies of paperwork relating to any amendments shall be attached to the site copy of the AMS to provide a definitive record of what has been agreed.



# **List of Contacts**

Contact	Name	Company/LPA	Contact Number(s)	Report Issued to?
Client	Mr. Simon Goldstein	Squire & Partners	020 7278 5555	Yes
Arboricultural Supervisor	Mr. David Challice	Challice Consulting Ltd.	01306 743374 07831 855764	N/a



Challice Consulting Ltd. Tel: 01306 743374

# **Tree Survey Schedule with Recommended Tree Works**

Page 1

Surveyor: Mr. David Challice

Our Ref: CC/1514 AR2827

Site: 192 Haverstock Hill, London NW3 2AJ


Date Surveyed: 9th December 2015


- 410 0		o. <b>_</b> 0.0													
Tree No.	English Name		Crown Spread	Ground Clearance	Age Class	Stem Diameter		Protection Radius	Growth Vitality	Structural Condition	Landscape Contribution				Observations
	Common Beech  1 Number  ended Works/ or Works:  No work	18 proposed	5 5 5 5	GC 4 FB5 N	Mature	640 1	12	7.7	Normal	Good	High	A	1,2	40+	Street tree with roots lifting pavement Tree protection not required at the front of the site due to metal railing fence
T2	Sycamore 1 Number	17	2 5 4 6	GC 4 FB5 S	Mature	440 1 est	12	5.3	Normal	Fair	Medium	В	1,2	20+	Ivy smothering stem prevented proper inspection or stem measurement Tree located off site
	ended Works/ or Works: Cut back to give from propo									Re	ecommended to pe development	ermit			

#### Notes:

- 1. Height describes the approximate height of the tree measured in meters from ground level.
- 2. The Crown Spread refers to the crown radius in meters from the stem centre and is shown above on each of the four compass points (i.e. N, S, E, W).
- 3. Ground Clearance (**GC**) is the height in meters of crown clearance above adjacent ground level, the height of the first significant branch (**FB**) and the direction in which it is growing.
- 4. Stem Diameter is the diameter of the stem measured in millimeters at 1.5m from ground level. The stem diameter may be estimated (est) where access is restricted or an average (ave) taken for groups or multi-stemmed trees with more than five stems. The number of stems is also indicated.
- 5. Protection Multiplier is the number used to calculate the tree's protection radius and area and is shown as 12.

- 6. Protection Radius is a radial distance measured from the trunk centre.
- 7. Growth Vitality Normal growth, Moderate (below normal), Poor (sparse/weak) or Dead (dead or dying tree).
- 8. Structural Condition Good (no or only minor defects), Fair (remedial defects), Poor (major defects present).
- 9. Landscape Contribution High (prominent landscape feature), Medium (visible in landscape), Low (secluded/among other trees).
- 10. B.S. Cat refers to British Standard 5837:2012 Table 1 and refers to tree/group quality and value; 'A' High, 'B' Moderate, 'C' Low, 'U' Remove.
- 11. Sub Cat refers to the retention criteria values where 1 is Arboricultural, 2 is Landscape and 3 is Cultural including Conservational, Historic and Commemorative.
- 12. Useful Life is the tree's estimated remaining contribution in years.







**Challice Consulting Ltd.** 

T: 01306 743374

**Arboricultural Site Supervision** 

Site: Sample D. Challice Inspected By:

The Builder Client: Site Agent: No staff present **Date of Inspection: Time of Inspection:** 



Tree protection in correct location

**Comments/Action** No action at this time

# **Agreed Construction Exclusion Zone**

No debris within construction exclusion zone



Tree protection T23

#### Comments/Action

No action at this time

# **Amendments to Documentation Required**

No amendments required

Comments/Action



Tree protection T14

# **Remedial Works**

Install protection as per Arboricultural Method Statement

# **General Comments**

No ground protection in place for T11,12,14,17 & 22 Sweet Gum T1 not removed



#### Induction Form for all Site Personnel:

Site Name:	

- I have had explained to me by the Site Manager the key implications of the Arboricultural Method Statement relating to the development at the above site.
- I am aware that the tree protective fencing must remain in its original position and must not be moved without the approval of the appointed Arboricultural Consultant.
- I understand that certain operations must be supervised by the appointed Arboricultural Consultant and that these operations must not start until the consultant is present and has given approval.
- I confirm that I will bring any concerns about potential damage to trees to the attention of the Site Manager.
- I am aware that I must not cause damage to any of the retained trees on or adjacent to the site. Damage may be caused by direct means (i.e. physical damage caused to roots or the trunk/branches of the tree) or by indirect means (e.g. by fire or toxic materials entering the rooting environment of the tree).

<u>Print Name</u> :.	 	 •••••	 
Sign Name:			
<u>Olgii Ivaiilo</u>	 	 	 
Date:	 	 	 

Drint Name