



7 GREVILLE PLACE

LONDON

NW6 5JP

STRUCTURAL FEASIBILITY REPORT

PREPARED FOR

MR N RAVEENDRAN

Ref: 16497/DO/mf

Date: August 2016

1 Athenaeum Road
Whetstone
London N20 9AA

t. 020 8445 7721
e. office@halsteads.co.uk
w. www.halsteads.co.uk

CONSULTING engineers
QUANTITY surveyors
PROJECT coordinators
CDM coordinators
Party Wall surveyors

CONTENTS

		<u>Page No.</u>
1.00	Brief	1
2.00	Screening	2
3.00	Site Investigations	3
4.00	Basement Information	4
5.00	Ground Movement Assessment & Predicted Damage Category	6
6.00	Monitoring	8
7.00	Waterproofing	12
8.00	Party Walls	13
9.00	Temporary Works	14
Appendix A	Drawings	15

1.00

BRIEF

1.01

The Structural Engineering design brief was to produce a feasibility study into the construction of a new basement extension to an existing three storey semi-detached house at 7 Greville Place, London NW6. The existing house has a full footprint basement and the proposed works will extend the basement to the front and side of the existing layout.

1.02

This Report is to be read in conjunction with Halstead Associates Drawing Nos. 16497/PL01, PL02 and PL03.

1.03

This report is also to be read in conjunction with Jomas Geotechnical Study Ground Investigation and Basement Impact Assessment, reference P939372J779, dated 11 February 2016.

2.00 SCREENING

2.01 Structural Stability Screening Assessment

1.	Does the proposed basement involve underpinning of the existing building?	Yes
2.	Does the proposed basement extend lower than the party fence structure to the right?	Yes
3.	Does the proposed basement extend lower than the building structure to the right?	Yes
4.	Does the proposed basement extend lower than the party fence structure to the left?	Yes
5.	Does the proposed basement extend lower than the building structure to the left?	Yes
6.	Does the proposed basement undermine the public highway?	Yes

3.00 **SITE INVESTIGATIONS**

3.01 A desk study and associated site based geotechnical investigation was carried out in January 2016 by Jomas Associates Ltd which incorporated two boreholes (4m and 9m deep) and a ground water monitoring point within one of the boreholes.

3.02 The boreholes revealed a narrow band of made ground of up to 0.5m in thickness at shallow level. Below this level firm to stiff brown slightly gravely clay was recorded in both boreholes to their full depth.

3.03 Ground water levels were found to be approximately 1.8m below ground level within borehole WS1 during a return visit to the property. However, it is expected that the water is that which has accumulated within the monitoring installation via run off from the clay surface, or alternatively has been trapped within pockets within the clay. The water is expected to be limited in volume and to be very slow to recharge.

4.00 **BASEMENT FORMATION**

4.01 Given the proximity to adjacent properties and to the back of the public footpath to the front of the property, it is expected that the walls of the new basement extension will be formed in an underpinning type sequence. This will involve carrying out local excavations of around 1m in width and down to the formation level of the new basement, followed by the fixing of reinforcement within the excavations and the casting of concrete to form an individual retaining wall section complete with base.

The sequencing of this work would be such that no more than 20% of a single wall elevation would be excavated at any given time. At the required excavation depth, suitable shoring would be required to provide a safe working area for site operatives. Typical sequencing for the excavation of a wall section is shown on Drawing No. 16497/PL03.

4.02 At the expected depth required for the excavation, it is likely that temporary shoring to the retaining wall sections will be required in the short term in order to prevent overturning and/or sliding, until the basement slab has been installed. The slab will then act to brace the perimeter walls against the existing building.

4.03 Whilst it has not been established at this stage, it is possible that underpinning of the existing walls to the house directly adjacent to the new basement will be required in order to achieve the new slab levels. Again, this will be carried out in a sequence whereby the extent of the excavation on a single wall line will be limited to 20% of the length of the wall at any one time.

Ideally, this underpinning will be carried out with access gained from the existing basement, therefore limiting the depth of the excavation. However, it is likely that preference will be not to disturb the existing slab and tanking to the basement and as a result the works may need to be carried out externally.

4.00 **BASEMENT FORMATION (Cont'd)**

This would require a much deeper excavation but can be achieved on the basis that suitable shoring is provided in line with good practice.

4.04 Once the basement slab and perimeter walls are fully in place, along with intermediate supporting columns and walls, then the ground floor slab can be cast. This will take support off the existing wall of the building with the use of recessed reinforced concrete pockets into the masonry.

4.05 At 3-3.5m depth down to formation level, it is not expected that the recovery of the load consolidating clays would be significant. Notwithstanding, an allowance is to be made within the design of the basement slab for theoretical heave pressures.

4.06 The Contractor will provide a method statement prior to commencement of work on site in which full details of hours, site set up and method for the formation of reinforced and under reinforced underpinning sections will be detailed. Drawing No. 16497/PL03 shows as indicative sequence for the construction of RC retaining wall "underpin" sections.

5.00 **GROUND MOVEMENT & PREDICTED DAMAGE CATEGORY**

5.01 Any ground works pose an elevated risk to adjacent properties. The proposed works undermines the adjacent property along the Party Wall line.

5.02 It is not expected that any cracking will occur during the works. However, our experience informs us that there is a risk of movement to the neighbours.

5.03 To reduce the risk to the development:

- Employ a reputable firm for extensive knowledge of basement works.
- Employ suitably qualified Consultants. Halstead Associates have extensive experience with basement constructions.
- Design the underpins to be suitably propped during construction until permanent props are in place.
- Provide method statements for the Contractors to follow.
- Investigate the ground, now completed.
- Record and monitor the external properties. This is completed by a condition survey under the Party Wall Act before and after the works are completed.

5.04 The maximum level of cracking anticipated is Hairline cracking which can be repaired with decorative cracking and can be repaired with decorative repairs. Under the Party Wall Act damage is allowed (although unwanted) to occur to a neighbouring property as long as repairs are suitably undertaken to rectify this. To mitigate this risk the Party Wall Act is to be followed and a Party Wall Surveyor will be appointed.

5.00 GROUND MOVEMENT & PREDICTED DAMAGE CATEGORY (Cont'd)

5.05 Burland Scale:

Extract from The Institution of Structural Engineers "Subsidence of Low-Rise Buildings"

Classification of visible damage to walls with particular reference to type of repair and rectification consideration.

Category of damage	Approximate crack width	Limiting tensile strain	Definitions of cracks & repair types / considerations
0	Up to 0.1	0.0 – 0.05	HAIRLINE – Internally cracks can be filled or covered by wall covering and redecorated. Externally, cracks rarely visible & remedial works rarely justified
1	0.2 to 2	0.05 – 0.075	FINE – Internally cracks can be filled or covered by wall covering, and redecorated. Externally, cracks may be visible, sometimes repairs required for weather tightness or aesthetics. NOTE: Plaster cracks may, in time, become visible again if not covered by a wall covering.

6.00 MONITORING

6.01 In order to safeguard the existing structures during underpinning and new basement construction movement monitoring is to be undertaken.

Monitoring Level Proposed	Type of Works
<p>Monitoring 1 Visual inspection and production of condition survey by Party Wall Surveyors at the beginning of the works and also at the end of the works.</p>	<p>Loft conversion, cross wall removals, insertion of padstones Survey of LUL and Network Rail tunnels. Mass concrete, reinforced and piled foundations to new build properties.</p>
<p>Monitoring 2 Visual inspection and production of condition survey by Party Wall Surveyors at the beginning of the works and also at the end of the works. Visual inspection of existing Part Wall during the works. Inspection of the footing to ensure that the footings are stable and adequate.</p>	<p>Removal of lateral stability and insertion of new stability frames. Removal of main masonry load bearing walls. Underpinning works less than 1.2mm deep.</p>
<p>Monitoring 3 Visual inspection and production of condition survey by Part Wall Surveyors at the beginning of the works and also at the end of the works. Visual inspection of existing Party Wall during the works. Inspection of the footing to ensure that the footings are stable and adequate. Vertical monitoring movement by standard optical equipment.</p>	<p>Lowering of existing basement and cellars more than 2.5m. Underpinning works less than 3.0m deep in clays. Basements up to 2.5m deep in clays.</p>

6.00

MONITORING (Cont'd)

<p>Monitoring 4</p> <p>Visual inspection of production of condition survey by Party Wall Surveyors at the beginning of the works and also at the end of the works.</p> <p>Visual inspection of existing Party Wall during the works.</p> <p>Inspection of the footing to ensure that the footings are stable and adequate.</p> <p>Vertical monitoring movement by standard optical equipment.</p> <p>Lateral movement between walls by laser measurements.</p>	<p>New basements greater than 2.5m and shallower than 4m deep in gravels.</p> <p>Basements up to 4.5m deep in clays.</p> <p>Underpinning works to Grade I Listed Building.</p>
<p>Monitoring 5</p> <p>Visual inspection of production of condition survey by Party Wall Surveyors at the beginning of the works and also at the end of the works.</p> <p>Visual inspection of existing Party Wall during the works.</p> <p>Inspection of the footing to ensure that the footings are stable and adequate.</p> <p>Vertical & lateral monitoring movement by theodolite at specific times during the project.</p>	<p>Underpinning works to Grade I Listing Building.</p> <p>Basements to Listed Building.</p> <p>Basements deeper than 4m in gravels.</p> <p>Basements deeper than 4.5m in clays.</p> <p>Underpinning basements to buildings that are expressing defects.</p>
<p>Monitoring 6</p> <p>Visual inspection of production of condition survey by Party Wall Surveyors at the beginning of the works and also at the end of the works.</p> <p>Visual inspection of existing Party Wall during the works.</p> <p>Inspection of the footing to ensure that the footings are stable and adequate.</p> <p>Vertical & lateral monitoring movement by electronic means with live data gathering.</p> <p>Weekly interpretation.</p>	<p>Double storey basements supported by piled retaining walls in gravels and soft sands (N<12).</p>

6.00 MONITORING (Cont'd)

<p>Monitoring 7 Visual inspection of production of condition survey by Party Wall Surveyors at the beginning of the works and also at the end of the works. Visual inspection of existing Party Wall during the works. Inspection of the footing to ensure that the footings are stable and adequate. Vertical & lateral monitoring movement by electronic means with live data transfer.</p>	<p>Larger multi-storey basements on particular projects.</p>
<p>Monitoring Conclusion</p>	
<p>Monitoring 4 Visual inspection of production of condition survey by Party Wall Surveyors at the beginning of the works and also at the end of the works. Visual inspection of existing Party Wall during the works. Inspection of the footing to ensure that the footings are stable and adequate. Vertical monitoring movement by standard optical equipment. Later movement between walls by laser measurements.</p>	<p>New basements greater than 2.5m and shallower than 4m deep in gravels. Basements up to 4.5m deep in clays. Underpinning works to Grade I Listed Building.</p>

6.02 Before the works begin a detailed monitoring report is required to confirm the implementation of the monitoring. The items that this should cover are:

- Risk Assessment to determine level of monitoring
- Scope of Works
- Applicable Standards
- Specification for Instrumentation
- Monitoring of existing cracks
- Monitoring of movement

6.00 **MONITORING (Cont'd)**

- Reporting
- Triggering Levels using a RED AMBER GREEN system

Recommended levels are:

Movement	Category	Action
0mm – 5mm	Green	No action required.
5mm – 12mm	Amber	Crack monitoring: Carry out a local structural review. Preparation for the implementation of remedial measures should be required.
>12mm	Red	Crack monitoring: Implementation of structural support as required. Cease works with the exception of necessary works for the safety and stability of the structure and personnel. Review monitoring data and implement revised method of works.

7.00 **WATERPROOFING**

7.01 As this form of construction will not allow external damp proofing systems to be employed, it is envisaged that the Architect will opt for a proprietary drained cavity system to line the external face of the retaining wall and slab. Any inflow of ground water which may result would then be directed to an internal sump and then pumped as necessary into the surface water system.

8.00 **PARTY WALLS**

8.01 Given the proximity of adjacent buildings, Party Wall Agreements may be required with neighbouring home owners, particularly in light of the recommendations for monitoring during the works.

9.00

TEMPORARY WORKS

9.01

A competent Contractor, experienced in this form of residential basement construction must be used, and a Temporary Works Coordinator should be employed to ensure that the stability of the ground and adjoining buildings is maintained through out the construction process.



.....

David Oates CEng BEng (Hons) MStructE

APPENDIX A

Halstead Associates Drawing Nos. 16497/PL01, PL02 and PL03A.


FOR INFORMATION ONLY

Notes:
1. This drawing is to be read in conjunction with all relevant Consultant's drawings and specifications.

No.	Date	Revisions	By	Design


Project:	7 GREVILLE PLACE, NW6 5JP
Site:	GA BASEMENT AND GROUND FLOOR PLANS
Drawn by:	JK
Checked by:	DO
Date:	26th February 2016
Scale:	1:50 @ A1
Drawing No.:	16497/PL01

HatisCAD Associates CONSULTANTS 1. 020 8412 7721 2. 020 8412 7722 3. 020 8412 7723 4. 020 8412 7724 5. 020 8412 7725 6. 020 8412 7726 7. 020 8412 7727 8. 020 8412 7728 9. 020 8412 7729 10. 020 8412 7730 11. 020 8412 7731 12. 020 8412 7732 13. 020 8412 7733 14. 020 8412 7734 15. 020 8412 7735 16. 020 8412 7736 17. 020 8412 7737 18. 020 8412 7738 19. 020 8412 7739 20. 020 8412 7740 21. 020 8412 7741 22. 020 8412 7742 23. 020 8412 7743 24. 020 8412 7744 25. 020 8412 7745 26. 020 8412 7746 27. 020 8412 7747 28. 020 8412 7748 29. 020 8412 7749 30. 020 8412 7750 31. 020 8412 7751 32. 020 8412 7752 33. 020 8412 7753 34. 020 8412 7754 35. 020 8412 7755 36. 020 8412 7756 37. 020 8412 7757 38. 020 8412 7758 39. 020 8412 7759 40. 020 8412 7760 41. 020 8412 7761 42. 020 8412 7762 43. 020 8412 7763 44. 020 8412 7764 45. 020 8412 7765 46. 020 8412 7766 47. 020 8412 7767 48. 020 8412 7768 49. 020 8412 7769 50. 020 8412 7770 51. 020 8412 7771 52. 020 8412 7772 53. 020 8412 7773 54. 020 8412 7774 55. 020 8412 7775 56. 020 8412 7776 57. 020 8412 7777 58. 020 8412 7778 59. 020 8412 7779 60. 020 8412 7780 61. 020 8412 7781 62. 020 8412 7782 63. 020 8412 7783 64. 020 8412 7784 65. 020 8412 7785 66. 020 8412 7786 67. 020 8412 7787 68. 020 8412 7788 69. 020 8412 7789 70. 020 8412 7790 71. 020 8412 7791 72. 020 8412 7792 73. 020 8412 7793 74. 020 8412 7794 75. 020 8412 7795 76. 020 8412 7796 77. 020 8412 7797 78. 020 8412 7798 79. 020 8412 7799 80. 020 8412 7800 81. 020 8412 7801 82. 020 8412 7802 83. 020 8412 7803 84. 020 8412 7804 85. 020 8412 7805 86. 020 8412 7806 87. 020 8412 7807 88. 020 8412 7808 89. 020 8412 7809 90. 020 8412 7810 91. 020 8412 7811 92. 020 8412 7812 93. 020 8412 7813 94. 020 8412 7814 95. 020 8412 7815 96. 020 8412 7816 97. 020 8412 7817 98. 020 8412 7818 99. 020 8412 7819 100. 020 8412 7820 	




GROUND FLOOR PLAN

NO 6
NO 7
NO 32
Greville Place



BASEMENT FLOOR PLAN





FOR INFORMATION ONLY

DPC, FINISHES AND WATERPROOFING TO ARCHITECT'S DETAILS

Note: The drawings shall be read in conjunction with all relevant Consultant's drawings and specifications.

No.	Date	By	Engineer

Project: 7 GREVILLE PLACE, NW6 5JF		Drawn by: JK
Title: STRUCTURAL SECTIONS		Checked by: DO
Client: M/N Flavincoan		Date: 26th February 2016
Architect: Herbert Schneider Designers		Scale: AS NOTED @ A1
herbstschneider architects 1, 2 & 3rd Floor 7, 8 & 9, 10 & 11, 12 Upper Cross Street London W1R 3AA Tel: +44 (0)20 7663 4000 Fax: +44 (0)20 7663 4001 Email: info@hsdn.co.uk		Drawing No: 16497/PL02



FOR INFORMATION ONLY

No.	Date	By	Engineer	Revision												
A	28/03/18				01											

Project: 7 GREVILLE PLACE, NW6 SLP	Drawn: JK
SUGGESTED CONSTRUCTION SEQUENCING FOR RETAINING WALL SECTIONS	Checked: DO
Client: M N Ramchandran	Date: 26th February 2016
Architect: Schneider Designers	Scale: AS NOTED @ A1
halslead	Quantity: 16497/PL03
1, 4th Floor, 7 Greville Place, London NW6 5LP, UK	1, 4th Floor, 7 Greville Place, London NW6 5LP, UK
Tel: 020 8415 7773	Fax: 020 8415 7773
Email: info@halslead.co.uk	Website: www.halslead.co.uk

Notes:

- The drawing is to be read in conjunction with all relevant Consultant's drawings and specifications.