

**LEVEL 03 - PROPOSED LAYOUT** 

LEVEL 04 - PROPOSED LAYOUT

- ALL EXISTING FIREPLACES, HEARTHSTONES ANAD GRATES TO BE RETAINED AND REPLACED WHERE REQUIRED NEW SURROUNDS SPECHED AND INSTALLED IN XCCORDANCE WITH CONSERVATION BEST PRACTICE.
- ALL SHUTTERS TO BE RESTORED TO WORKING ORDER AND REPLACED WHERE REQUIRED IN ACCORDANCE WITH CONSERVATION BEST PRACTICE
- SKIRTING AND CORNICING TO BE RESTORED.
  REPLACED AS PER ORIGINAL FEATURES IN
  ACCORDANCE WITH CONSERVATION BEST
  PRACTICE
- 5 NEW CONTEMPORARY FEATURE LIGHTING IN HALLWAY AND STAIRWELL
- 6 CONTEMPORARY AND UNOBTRUSIVE ACCESS SYSTEM AND MAIL BOXES FIXED TO WALLS WITHIN ENTRANCE PORCH
- 7 FLOOR JOISTS TO BE STRENGTHENED LOCALLY AND REPLACED WHERE REQUIRED TO RESTORE STRUCTURAL INTEGRITY AND TAKE NEW LOADS
- (B) ORIGINAL FLOORING RESTORED AND REPLACED WHERE POSSIBLE OR NEW TIMBER / STONE FLOORING ALL WALLS TO BE SKIMMED AND PAINTED IN HERITAGE APPROVED PAINT RANGE COLOUR TBC IN ACCORDANCE WITH CONSERVATION BEST PRACTICE
- (1) ORIGINAL STONE AND TIMBER STAIRCASES TO BE RESTORED IN ACCORDANCE WITH IN ACCORDANCE WITH CONSERVATION BEST PRACTICE
- (II) CARPET ON STAIRCASE TO BE REPLACED WITH NEW RUNNER
- (12) NEW BRICK CLOSET WING WITH SLATE ROOF TO MATCH EXISTING ADJOINING BUILDING
- (3) EXCAVATED ARCHES WITH LOWERED GROUND TO ACCOMMODATE NEW BATHROOM BIN AND BIKE STORE
- (4) NEW LIMESTONE FLAGSTONES
- (S) STEEL FRAMED 'CRITTAL' GLAZED PARTITION AND DOORWAY
- (7) EXISTING STONE STEPS AT ENTRANCE TO BE RESTORED IN ACCORDANCE WITH CONSERVATION BEST PRACTICE
- (B) ALL ORIGINAL SASH WINDOWS AND TIMBER SHUTTERS TO BE MADE GOOD, REPAIRED AND WHERE REQUIRED REPLACED TO MATCH EXISTING IN ACCORDANCE WITH CONSERVATION BEST PRACTICE
- (9) ROOF TO BE RECONSTRUCTED ALL ORIGINAL SLATES TO BE RE-USED, TIMBER STRUCTURE REPLACED AND POOR QUALITY ROOFING FELT REPLACED WITH LEAD SHEETING
- (20) NEW TIMBER ENTRANCE DOORS TO REPLACE POOR QUALITY EXISTING SET PAINTED BLACK INKEEPING WITH THE REST OF THE TERRACE
- (1) FANLIGHTS ABOVE ENTRANCE DOORS TO BE RESTORED IN ACCORDANCE WITH CONSERVATION BEST PRACTICE
- 22 NEW CAST IRON RAINWATER PIPES INKEEPING WITH EXISTING
- 23) NEW DORMER WINDOWS IN KEEPING WITH THE CHARACTER OF THE TERRACE 24) NEW OPENING IN REAR FACADE AT LOWER GROUND LEVEL TO ACCOMMODATE NEW BLACK STEEL FRAMED DOORS
- ALL RAILINGS AND BALUSTRADING TO LIGHTWELL AND EXTERNAL STAIRCASE TO BE REPARED AND RAINED AND EXTERNAL STAIRCASE TO BE REPARED AND RAINED BALUSTRING BIRCK TO BE CLEANED REPAIRED AND REPAIRED GLOSS BLOCK TO BE CLEANED REPAIRED AND RESTORED TO ACROSTORAL CONSTRUCTION BEST PRACTICE AS REQUIRED AND RESTORED TO ORIGINAL CONDITION IN PRACTICE MAD RESTORED TO ORIGINAL CONDITION IN PRACTICE.

  27 EXISTING CAST-RON BALCON'T TO BE REPAIRED AND RESTORED TO ORIGINAL CONDITION IN PRACTICE.

  28 NEWLONDON STOCK BRICKWORDS LAID IN

- (28) NEW LONDON STOCK BRICKWORK, LAID IN FLEMISH BOND AND SOOTWASHED TO MATCH EXISTING
- 29 NEW DOUBLE GLAZED BLACK FRAMED WINDOWS, COLOUR TO MATCH EXISTING WINDOWS
- $\ensuremath{\bigcirc{30}}$  New masonry wall with white render finish
- 3) EXCAVATION OF LOWER GROUND FLOOR TO COMBAT DAMP AND PROVIDE ADEQUATE FLOOR BUILDUP
- (32) NEW FIRE-RATED ACOUSTICALLY INSULATED ENCLOSURES CONTAINING KITCHEN AND BATHROOM ACCOMMODATION FLUSH FINISH WITH CONICEALED FIXINGS AND CONTEMPORARY DETAILING
- 33 NEW FIRE-RATED TIMBER DOOR SETS TO MATCH EXISTING
- NEW FIRE-RATED ACOUSTICALLY INSULATED STUD PARTITION WALL
- 35 NEW FIRE-RATED FRAMELESS TIMBER DOOR SETS FLUSH WITH WALL
- 36 NEW CONTEMPORARY TIMBER STAIRCASE

- NOTES
- 519A 67 GUILFORD STREET 28.10.15 OOK ARCHITECTS SHALL HAVE NO RESPONSIBILITY FOR ANY USE MADE OF THIS DOCUMENT OTHER THAN FOR THAT WHICH IT WAS REPRABED AND SSUED ALL DIMENSIONS SHOULD BE CHECKED ON SITE DO NOT SCALE FROM THIS DRAWING, ANY DRAWING ERRORS OR DIVERSENCES SHOULD BE STOUGHT TO THE ATTENTION OF OOK ARCHITECTS. Level 03 & 04 - Proposed Layout 1:100 **PLANNING** P0 I



OOK ARCHITECTS 119 Farringdon Road London EC1R 3DA