

anealed glass to be fitted within extened sill and new architrave. Refer to SK 06 for further

details.

Type 3 - 'Make good' timber casements, replace crittall casements with new timber to match existing. Refer to SK 07 for further details. Type 4 - 'Make good' timber casements, replace crittall casements with new timber to

match existing. Existing glazing lights to be replaced with Histoglass d11. Refer to SK 07 for further details.

Type 5 - To be overhauled and redecorated.

Type 6 - To be overhauled and redecorated. Type 7 - Window to be investigated further as currently covered by joinery.

Doors - see sketch drawings SK 08.

Front Door - To make good. New ironmongery, acoustic seals etc. Type 1 - Existing doors to be retained, overhauled and redecorated, with new iron

mongery and acoustic treatment applied. Type 2 - New doors to match existing, new iron mongery and acoustic treatment applied. Type 3 - New pocket door with acoutic treatment. Door to be within joinery of Tv Room.

Type 4 - New pocket door with acoutic treatment. Door to be within joinery of Utility Room. Type 5 - Existing external doors to be retained and overhauled with new decoration,

ironmongery and acoustic treatment applied. Secondary internal swing glazed doors are to be fitted within existing frame.

Type 6 - New Door to match Door Type 1 Internal Doors. Type 7 - New door within new glazed partition. Refer to SK 09 for further details. Access Hatch to Storage in Loft above Bedroom 2, 3 and TV room to be widened.

Ceilings - see sketch drawings SK 04 for further details. All existing ceilings to be removed and replaced with the exception of Master Bedroom. Type 1 - Existing Joists retained, GypLyner Universal ceiling suspended with Gypframe GL1 Lining Channels, 100mm Rockwool in the cavity, Ceiling linings to be specified. Type 2 - Existing Joists retained, StoSilent Top A-Tec System with Galvanised steel suspension system, StoSilent Top A-Tec Panel, StoSilent Top Basic + Top Finish Type 3 - Existing Ceiling to be retained. GypLyner Universal ceiling suspended with Gypframe GL1 Lining Channels to give a minimum cavity of 50mm to a maximum of 145mm, 50mm Rockwool in the cavity, Ceiling Linings to be specified.

<u>General Notes</u> - 1. All habitable rooms to be provided with airconditioning, replacing any existing with new. Continuous feed of ventilation to be provided to all habitable rooms at the front of the flat.

2. Garage loft to be floored for storage.

All cornice + skirling to be removed and replaced with exception to Master Bedroom.
All radiators to be removed with exception to Master Ensuite bathroom.
Master Bedroom wall panels to remain.

6. Ceiling's to be raised as marked.

THIT

LEGEND. EXISTING WALLS. NEW INTERNAL PARTITIONS. ZZZFF1. HERRINGBONE TIMBER FLOORING 'WELDON'. FF2. TILED FLOORING TO BE SPECIFIED. FF3. CARPET FLOORING TO BE SPECIFIED (W 00) SEE WINDOW SKETCH DRAWINGS. D 00 SEE DOOR SKETCH DRAWINGS.

ACOUSTICALLY LINED.

SECONDARY GLAZING.



The Belvedere 2 Back Lane Hampstead London NW3 1HL Scale: 1:100@A3 T 020 7794 1234 E office@charltonbrown.com This drawing is copyright Please follow the drawings exactly. If you find errors or omissions ask for clarification. Do not proceed without revised instructions. No dimensions to be scaled

1316 / AP 02

Flat 8, Inverforth House, London

Proposed Floor Finishes Plan