



BASEMENT IMPACT ASSESSMENT

FOR

PROPOSED BASEMENT WORKS (OFFICE SCHEME)

AT

75 BAYHAM STREET LONDON **NW1 0AA**

FOR

W12 STUDIOS

Project No. P3096-OFF

ISSUE 2.0 – REVISED SCHEME

Michael Alexander Consulting Engineers, Foundation House, 4 Percy Road, London E-mail mail@maengineers.com Tel 020 8445 9115

DOCUMENT CONTROL SHEET

	75 Bayham Street, London NW1 0AA	Project No.	P3096-OFF
Prepared By:	Giovanni Sclavi BEng MSc(Hons) GIPENZ	Jelin	(ja-
Reviewed By:	Isaac Hudson MEng MA(Cantab.) CEng MIStructE Director	Time	\sum
Issue No.	Status	Date	
0.1	Draft Issue	14/10/2015	
1.0	First Issue	23/10/2015	
1.1	Updated to Reflect Comments	26/10/2015	
1.2	Updated to Reflect Comments	26/10/2015	
1.3	Updated to reflect Review Comments	07/03/2016	
	Amendments: - Clause 3.01.2 amended Clause 4.01.9 amended Clause 4.01.13 amended Clause 4.01.15 amended Clause 4.02.1 amended Clause 4.03.1 amended Clause 4.04.3 amended Clause 4.04.6a amended Clause 4.04.12 amended Clause 5.01, E05 & E12 amended Appendix F added		

Updated to reflect Revised Scheme Amendments: -Clause 2.01 amended Clause 2.01a added Clause 3.01.2 amended Clause 3.02.1 amended Clause 3.03.1 amended Clause 4.03.1 amended Clause 4.04.1 amended Clause 4.04.4 amended Figure A2 amended Drawings D2, D3, D4 & D5 amended Clauses E8 & E12 amended and E9a add

Clauses F3, F4, F5 & F6 amended

2.0

P3096-OFF Basement Impact Assessment v2.0



	26/09/2016
aaed	

CONTENTS

Page

1.00	INTRODUCTION	3
2.00	BASEMENT PROPOSALS	3
3.00	SUBTERRANEAN (GROUND WATER) FLOW	4
4.00	GROUND STABILITY	7
5.00	SURFACE FLOW AND FLOODING	13

APPENDICES

I	Appendix A	Impermeable Area Plans	A1 – A2
	Appendix B	Thames Water Records	B1 – B3
	Appendix C	Photographs	C1 – C3
I	Appendix D	Outline Structural Drawings	D1 – D5
I	Appendix E	Construction Method Statement	E1 – E2
I	Appendix F	Preliminary Structural Calculations	F1 – F4
	Appendix G	Outline Construction Programme	G1 – G2



INTRODUCTION 1.00

- Michael Alexander Consulting Engineers has been appointed to prepare a Basement Impact 1.01 Assessment Report to support the Planning Application for the proposed new building (including a basement) at 75 Bayham Street, London NW1 0AA.
- This document has been prepared by Giovanni Sclavi BEng MSc(Hons) GIPENZ and reviewed 1.02 by Isaac Hudson MEng MA (Cantab) CEng MIStructE who is a chartered structural engineer. The document has been reviewed by Seamus Lefroy-Brooks of LBH Wembley, a chartered geologist.
- The existing property is currently occupied by offices to the upper floors and with a warehouse to 1.03 the rear. The three storey building was built circa 1880.
- The existing property is located within the Camden Town Conservation Area, but is not Listed. 1.04
- 1.05 The site is bounded by Bayham Street to the front (east), 77 Bayham Street and unit 1, 6a Pratt Street to the right (north) and 69, 71 and 73 Bayham Street to the left (south). To the rear of the property (west) the site is bounded by 1 and 2 Pratt Mews.
- 1.06 The proposed works are for the renovation, re-modelling and extension of the buildings on the site, to create offices varying in height from two to four storeys above ground. The proposed building will have a single storey basement below. This document addresses the specific issues relating to the basement construction, as described in Camden Planning Guidance CPG4 (2015 Revision).

2.00 **BASEMENT PROPOSALS**

The architectural proposal for the basement is shown on the following Innes Associates 2.01 Architecture & Urban Design drawings.

107 02 001	Basement Floor Plan
107 02 00	Ground Floor Plan
107 02 01	Lower First Floor Plan
107 02 02	First Floor Plan
107 02 03	Second Floor Plan
107 02 RF	Roof Plan
107 03 01	Section AA
107 03 02	Section BB
107 03 03	Section CC
107 03 04	Section DD
107 03 05	Section EE
107 03 06	Section FF
107 04 01	East Elevation
107 04 02	West Elevation
107 04 03	South Elevation

- 2.01a The structural proposal for the new building and basement have been developed by Momentum Structural Engineers and used as basis for our Basement Impact Assessment drawings as shown in Appendix D.
- 2.02 The details of the existing structure and site boundaries will be subject to detailed exploratory work prior to and during the works on-site.
- 2.03 The design and construction of the building structure shall be in accordance with current Building Regulations, British Standards, Codes of Practice, Health and Safety requirements and good building practice.



3.00 SUBTERRANEAN (GROUND WATER) FLOW

3.01 Stage 1: Screening

The impact of the proposed development on ground water flows is considered here as outlined in Camden Planning Guidance CPG 4 (2015 Revision). The references are to the screening chart Figure 1 in CPG4.

3.01.1 GW Q1a Is the site located directly above an aquifer?

No. With reference to the Camden Geological, Hydrogeological and Hydrological Study (Figure (a)) the site is not above an aquifer.

3.01.2 GW Q1b Will the proposed basement extend beneath the water table surface?

No. Near-surface groundwater table was not found at the time of site investigations as stated on LBH Wembley report LBH4318 Ver 1.8. No groundwater is expected within the impermeable London Clay.

3.01.3 GW Q2 Is the site within 100m of (i) a watercourse, (ii) a well (used or disused) or (iii) a potential spring line?

With reference to the Camden Geological, Hydrogeological and Hydrological Study (Figures (b), (c) and (d)),

(i) The nearest surface water feature is the Grand Union Canal, located, approximately 420m to the North of the site.

The Hampstead pond chains are located to the North West approximately 2900m from the site. The nearest 'lost' watercourse is the River Fleet which ran approximately 390m to the east of the site.

- (ii) From the British Geological Society 'Geoindex' the nearest water wells are on Pratt Street (approximately 390m to the East of the site) and on Camden Street (approximately 460m to the North of the site).
- (iii) The local geology suggests that the site is not located adjacent to a potential spring line.
- 3.01.4 GW Q3 Is the site within the catchment of the pond chains of Hampstead Heath?

No. With reference to the Camden Geological, Hydrogeological and Hydrological Study, the site is not within the catchment of the pond chains on Hampstead, nor the Golder's Hill Chain.



Figure (a) Aquifer Designation Map (Extract from Fig 8 of Camden Geological, Hydrogeological and Hydrological Study)



Figure (b) Watercourses (Extract from Fig 11 of Camden Geological, Hydrogeological and Hydrological Study -Lost Rivers of London by Barton)

Legend

Aquifer Designation

Secondary Aquiler Unproductive Strata

Outer Source Protection Z



3.01.5	GW Q4	Will the proposed basement development result in a change in the proportion of hard surface/paved areas?
		No. The site is currently fully occupied by buildings. In the proposed condition this will be generally be the case.
3.01.6	GW Q5	As part of the site drainage, will more surface water (e.g. rainfall and-runoff) than at present be discharged to the ground (e.g. via so akaways and /or SUDS)?
		No. Currently no surface water from the site is discharged to the ground, and this will also be true after the proposed works.
3.01.7	GW Q6	Is the lowest point of the proposed excavation (allowing for any drainage and foundation space under the basement floor) close to, or lower than, the mean water level in any local pond (not just the pond chains on Hampstead Heath) or spring line?
	No sit	b. The nearest ponds in the Hampstead Chain are not in close proximity to the e, nor is the site located adjacent to a spring line.
3.01.8	On the bas aspects ne	sis of items 3.01.1 to 3.01.7 above, and in reference to Figure 1 of CPG4, no ed to be carried forward to the scoping stage.

- 3.02 Stage 2: Scoping
- 3.02.1 No scoping is required as site investigations have been carried out on site by LBH Wembley in October 2015. Refer to their report LBH4318 Ver 1.8 of September 2016.



Figure (c) Surface Water Features (Extract from Fig 12 of Camden Geological, Hydrogeological and Hydrological Study)



Figure (d) Waterwells (also showing Infrastructure) (Extract from British Geological Survey)



Legend

- Railway Lines - A Roads - Sufara water * Site Location

▲ Water well locations



3.03 Stage 3: Site Investigation and Study

- 3.03.1 A site investigation was carried out by LBH Wembley in October 2015 which included trial pits and window sampling. Refer to their report LBH4318 Ver 1.8 of September 2016.
- 3.03.2 No groundwater was encountered during the investigations.

3.04 Stage 4: Impact Assessment

- 3.04.1 A hydrogeological assessment has been carried out by a chartered geologist and is included in section 5 of LBH Wembley's report. In summary it notes that no potential subterranean (groundwater) flow impacts associated with the construction of the proposed development have been identified.
- 3.04.2 It is however possible that perched water could be encountered during the excavation, at the interface of the made ground and the London Clay. Provision for this will need to be reflected in the proposed construction method refer Appendix E.



4.00	GROUN	D STABILITY	
4.01	Stage 1:	Screening	
4.01.1	GS Q1	Does the existing site include slopes, natural or manmade, greater than 7°?	Legend
		No. The site is generally level, with a slight slope from north to south and east to west. There are no slopes >7 degrees within the site.	A Baads A Baads Site Lacation BGS 1:10K Artificial Ground
4.01.2	GS Q2	<i>Will the proposed re-profiling of landscaping at site change slopes at the property boundary to more than</i> 7°?	BGS 1:10K Drift Geology ALLVVIM HIGHLEY SIGT FORMATION
		No. The basement construction will not change the profile of the ground at the boundaries of the property.	EVNOH HELL GRAVEL FORMATION STANAORE GRAVEL FORMATION BGS 1:10K Solid Geology BADSHOT FORMATION BUEL CLAYGATE MEMBER
4.01.3	GS Q3	Does the development neighbour land, including railway cuttings and the like, with a slope greater than 7°?	LONDON CLAY FORMATION
		No. With reference to the Camden Geological, Hydrogeological and Hydrological Study, (refer Figure (f)), the neighbouring areas also have slopes less than 7 degrees.	
4.01.4	GS Q4	Is the site within a wider hillside setting in which the general slope is greater than 7°?	
		No. With reference to the Camden Geological, Hydrogeological and Hydrological Study, (refer Figure (f)), the closest slopes that are greater than 7 degrees are located approximately 340m to the West.	
4.01.5	GS Q5	Is the London Clay the shallowest strata at the site?	
		Yes. With reference to Camden Geological, Hydrogeological and Hydrological Study, the underlying soil stratum is indicated as being the London Clay (Figure (e)).	Legend Slope 0°-7#
4.01.6	GS Q6	Will any trees be felled as part of the proposed development and/or are any works proposed within any tree protection zones where trees are to be retained?	> 10" > 10" London Borough of Camden
		No. There are no trees within the site boundary.	









Figure (e) Geological Map (Extract from Fig 4 of Camden Geological, Hydrogeological and Hydrological Study)

Figure (f) Slope Angle Map (Extract from Fig 16 of Camden Geological, Hydrogeological and Hydrological Study)

4.01.7	GS Q7	Is there a history of seasonal shrink-swell subsidence in the local area, and/or evidence of such effects at the site?	
		The London Clay strata is usually classified as having a high volume change potential and hence can lead to seasonal shrink-swell subsidence where buildings are founded in desiccated soils. We have however no specific evidence of subsidence having been experienced on site or in the immediate surrounding area.	
4.01.8	GS Q8	Is the site within 100m of a water course or a potential spring line?	
		No. With reference to the Camden Geological, Hydrogeological and Hydrological Study (refer Figures (b) and (c)), the site is located 390 metres from the subterranean River Fleet.	
4.01.9	GS Q9	Is the site within an area of previously worked ground?	
		Yes. Geological maps show an area of worked ground on the other side of Bayham St. With reference to the Camden Geological, Hydrogeological and Hydrological Study (figure (e)).	Legend
4.01.10	GS Q10	Is the site within an aquifer?	
		No. With reference to the Camden Geological, Hydrogeological and Hydrological Study (Figure (a)) the site is not above an aquifer.	
4.01.11	GS Q11	Is the site within 50m of the Hampstead Heath ponds?	
		No. With reference to the Camden Geological, Hydrogeological and Hydrological Study, the Hampstead pond chains are located to the North West approximately 2900m from the site.	
4.01.12	GS Q12	Is the site within 5m of a highway or pedestrian right of way?	
		Yes. The proposed basement will be less than 5m from the public highway.	
4.01.13	GS Q13	Will the proposed basement significantly increase the differential depth of foundations relative to neighboring properties?	
		Yes. It appears that no 73 Bayham Street has a lower ground floor approximately 1.4m below street level. With reference to survey drawings, we understand that the Pratt Mews properties do not have basements. It is not clear whether any of the other adjoining properties have basements. However in any event the proposed foundations will be deeper than those of the adjoining properties.	



Figure (g) Topography Map (Extract from Ordnance Survey Mapping)



Figure (h) 1873 Map



4.01.14	GS Q14	Is the site over (or within the exclusion zone of) any tunnels, e.g. railway
		lines?

No. With reference to Open Street Map (figure (i)) there are no tunnels located below the site. The nearest tunnel is the Northern Line located approximately 70m to the west of the site. The safeguarded zone for the proposed HS2 railway is approximately 350m to the south west of the site - refer figure (k).

- 4.01.15 On the basis of items 4.01.01 to 4.01.14 above and in reference to Figure 2 of CPG4, the aspects that should be carried forward to a scoping stage in respect of land stability are:
 - The increase in differential foundation depths. •
 - The basement being within 5m of a pedestrian highway.
 - The site being underlain by London Clay. •
 - The potential for being in an area of worked ground •

4.02 Stage 2: Scoping

- 4.02.1 With reference to the Camden Geological, Hydrogeological and Hydrological study Appendix F3, the potential impacts which will need to be considered will include:-
 - The risk of potential seasonal shrink-swell subsidence due to the underlying subsoils being London Clay.
 - The risk of structural damage to the adjoining properties during and following the basement construction.
 - The risk of damage to the road or pavement, or any underground services buried under.
 - Whether there are areas of extensive backfill across the site which might lead to ground instability
- 4.02.2 In response to the above issues: -
 - Trial pits were commissioned to the party walls. -
 - An outline construction method statement was prepared. -









Legend

Legend

Site Location

Rail Lines.

High Speed Rail Lini

Site Location

Rail Lines



Figure (i) Map of Underground Infrastructure (Extract from Open Street Map)

Figure (j) High Speed Rail Link (Extract from Open Street Map)

4.03	Stage 3: Site Investigation and Study	
4.03.1	The LBH Wembley Site Investigation of October is summarised in their report LBH4318 Ver 1.8 dated September 2016. In summary of the findings: -	
	 A varying thickness of made ground was encountered over London Clay to the full depth of the investigation. The made ground was deepest adjacent to the Bayham Street elevation, considered likely to be due to a former basement. Otherwise no significant areas of backfill were encountered The clay subsoils were found to have high plasticity. Existing foundations were conventional brick spread footings. Ground water was not encountered during the investigations 	Legend
4.04	Stage 4: Impact Assessment	Safeguarded Area: Surface
4.04.1	The proposed basement is around 4.25m deep and will be excavated through the made ground and then the well understood London Clay stratum. Provided appropriate construction methods are employed there should be no significant impact in terms of ground stability.	<u> </u>
4.04.2	The new basement will be constructed by underpinning the existing party walls. This is a well-established method and used successfully on numerous single storey basements within the London Clay.	
4.04.3	To the front elevation of the building the existing walls will be also underpinned. A reinforced concrete liner wall will be used in board of the underpinning which will span laterally between adjoining supports. Additional temporary propping will be provided to minimise any local ground movements which might affect services in the pavement. The services in the pavement will be scanned and marked prior to the commencement of the works. Further trial pits to the walls adjacent to the street will be carried out in advance of the works to confirm that these have similar depth and profile to the adjoining walls.	
4.04.4	The unloading of the ground due to the basement excavation may cause some heave of the underlying clay subsoils in both short and long term. To a certain extent, heave forces acting on the basement under the building will be counteracted by the weight of the building over. This is considered in more detail in LBH's report within the ground movement assessment, which shows that short term heave movements to the centre of the site will be up to 10mm, with smaller predicted movements for the party walls and beyond.	



Figure (k) High Speed Rail Safeguarding Map (Extract from gov.uk)



To mitigate the effect of heave on the building, the 'hybrid' approach as set out in the LBH report will be adopted:-

- The underpinning will be constructed with an enlarged toe. The heave pressures acting on this toe will be resisted by the weight of the building above.
- The main part of the basement will be constructed with a suspended slab laid on a layer of compressible material to allow the heave to occur.

The suspended slab will span across the building on top of the toes of the underpinning.

4.04.5 The new basement will not suffer from seasonal shrink swell subsidence as the depth of the proposed basement will be below the level of any tree root activity. The nearest trees are within Bayham St, and there is no reason to suggest that the construction of the basement will cause adjoining properties to become more susceptible to subsidence, particularly since the adjoining buildings to Bayham Street have been shown to have deeper foundations due to their part basements.

Ground Movements

- 4.04.6a Consideration has been given as to the foundation and slab levels of the adjoining properties, as described in clause 4.01.13. Where the floor levels to adjoining properties are not known, this information will be requested through the party wall process prior to commencement of construction.
- 4.04.6 To assist in determining the impact of the proposals, LBH have carried out a Ground Movement Analysis and Damage Assessment - refer sections 7 & 8 of their report respectively.
- 4.04.7 The report notes that it is hard to accurately predict the ground movements associated with basements formed by underpinning. However they suggest that the damage to adjoining properties could be 'Category 1-Very Slight' or worst case 'Category 2 -Slight' as defined by Burland.
- 4.04.8 In section 9 of LBH's report, they set out the methods by which ground movements - and hence building damage - will be mitigated. This has been reflected in the structural proposals.
- 4.04.9 An outline construction method has been developed, which is included in Appendix D. This sets out the measures which will be taken to mitigate the impact of the works, with specific reference to avoiding any adverse impact on the pavement or buried services.





(from LBH's ground movement assessment



Figure (I)

Short Term Ground Movement Contours (from LBH's ground movement assessment)

Figure (m) Long Term Ground Movement Contours

Monitoring

- 4.04.10 Measurement monitoring of the temporary works, Party Walls and adjoining structures will be carried out during the construction period. The precise scope of monitoring will be prepared in conjunction with the advisors to the Adjoining Owners.
- 4.04.11 The 'monitoring and contingency plan' will include trigger values for vertical and horizontal movement and frequency of measurement. There will be an increased frequency of monitoring during the excavation works to enable mitigation to be effectively implemented if trigger values are exceeded. If 'Amber' trigger values are exceeded then the monitoring frequency will be further increased and a detailed review of construction methods will be carried. If 'Red' trigger values are exceeded then all further excavation will be stopped, and the excavation made safe before a revised plan of works can be implemented.
- 4.04.12 The scope and locations of monitoring will be agreed with the neighbours through the party wall process.



5.00	SURFACE FL	OW AND F	LOODING
------	------------	----------	---------

5.01	Stage 1: Surface Flow and Flooding Screening
------	--

5.01.1 SF Q1 Is the site within the catchment of the pond chains on Hampstead Heath?

> No. With reference to the Camden Geological, Hydrogeological and Hydrological Study, the site is not within the catchment of the pond chains on Hampstead, nor the Golder's Hill Chain.

5.01.2 SF Q2 As part of the proposed site drain age, will surface water flows (e.g. volume of rainfall and peak run-off) be materially changed from the existing route?

> No. On completion of the development, the surface water flows will be routed in the same way as the existing condition, with rainwater run-off collected in a surface water drainage system and ultimately discharged to the combined sewer in Bayham Street (Refer to Thames Water Asset Search in Appendix B).

5.01.3 SF Q3 Will the proposed basement development result in a change in the proportion of hard surface/paved external areas?

> No. There will be no change in the proportion of hard landscaped areas. Refer figures A1 and A2 in Appendix A.

SF Q4 5.01.4 Will the proposed basement result in changes to the profile of inflows (instantaneous and long term) of surface water being received by adjacent properties or downstream watercourses?

No. There will be no change in the areas of hard landscaping.

5.01.5 SF Q5 Will the proposed basement result in changes to the quality of surface water being received by adjacent properties or downstrea m water courses?

> No. The surface water quality will not be affected by the development, as in the permanent condition collected surface water will be generally be from roofs, or external hard landscaping as existing.



Wales - From 1 April 2013 Natural Re This service is designed to inform members of the public, in line with our terms and conditions. For business or co

Figure (n) Areas at Risk of Flooding from Rivers or Sea (Extract from Environment Agency flood map)







Data search O

t Agency copyright and database rights 2015. © Ordnance Survey Crown copyright. All rights reserv Contains Royal Mail data © Royal Mail copyright and database right 2015.

nere - Hann T Agen auf a harboar neocodas norma ginning imm anna oran De neoponautones of participant ency copyright and database rights 2015. O Ordinance Surviya Crosin copyright, All rights reserved. Enviro Contains Royal Mail data & Royal Mail copyright and database right 2015. is of the public, in line with our terms and

Figure (o) Areas at Risk of Flooding from Reservoirs (Extract from Environment Agency flood map)

- 5.01.6 On the basis of items 5.01.1 to 5.01.5 above and in accordance with the Figure 3 in Camden Planning Guidance CPG 4 (2015 Revision), there are no aspects that should be carried forward to a scoping stage in respect of Surface Flow and Flooding.
- 5.01.7 SF Q6 Is the site in an area known to be at risk from surface water flooding, such as South Hampstead, West Hampstead, Gospel Oak and King's Cross, or is it at risk from flooding, for example because the proposed basement is below the static water level of a nearby surface water feature?

No. Bayham Street is not one of the streets noted within the Camden Planning Guidance CPG 4 (2015 Revision) as a street "at risk of surface water flooding" (Figure (p)).

A 'Sewer History' enquiry to Thames Water (Appendix A) gave no record of surcharge of sewers having previously affected this particular property.

With reference to the EA Rivers and Sea Flood Maps (Figure (n)), the site is not located within a flood risk zone. The EA Reservoir flood map (Refer figure (o)), shows that the site is not at risk of flooding from reservoirs.

With reference to the EA surface water flooding maps (Figure (q)) the site is at 'low risk' of flooding.

5.01.8 On the basis of the above and in accordance with the Figure 3 in Camden Planning Guidance CPG 4 (2015 Revision), a flood risk assessment in accordance with PPS25 is not required.



Figure (p) Flood Map (Extract from Fig 15 of Camden Geological, Hydrogeological and Hydrological Study)



Figure (q) Flooding from Surface Water (Extract from Environment Agency flood map)

Rooded Streets 2002

risk of surface water flooding

- Flooded Streets 1975



This service is designed to inform members of the public, in line with our terms and conditions. For business or commercial use, please contact us

`



APPENDIX A IMPERMEABLE AREA PLANS



Figure A1 - Existing Impermeable Area Plan

Figure A2 - Proposed Impermeable Area Plan







APPENDIX B THAMES WATER RECORDS



Figure B1 - Extract from Thames Water Asset Search showing a combined sewer

ALS Sev	ver Ma	р Кеу						
ublic Sewer Types daw	start 5. Martin	ned by Thamas Water)	Sew	er Fittings	Other	Symbols		
 Feed: A senser designed to curvey wade water have deneedic and initialize sources to a treatment water. 		A feature	A feature true secure that does not effect the fract the pipe. Compare μ such is a fitting as the function of a cost is to measure ensure gas.		Rymisels used on maps which its red Md under other persons untrageness.			
			Arvaia		Channel of the second state in the			
	expect to com		1	Date Chane		 Output output index (LOLI) 		
salar fam routs, yards and	car partici, lo no	et a selectures.				Intel Land		
And and A sure in fact	a far som en character		8	Maine	<	Durinet		
with Tory defeated, and re-	futilities sources	to a beament works.	0	Veril Column	Areas Lines dec	ing man if undergraph is		
Drim Trait Sufex Hear		Trans Paul	Ope	rational Controls		Agreement		
· Store Halad		Truck Contineed	A field	re tr a anner that changes or diverts the flow in the second Econopie strate lents the flow parcing downstream.	1222	Operational litre		
			x	Control Value		Charter		
Vard Pipe		Bo-antis chatget	Φ.	Drep Pape				
			8	Andlary	6666	Turner .		
Projected Thames Surface Ridar Sever	++	Proposed Transa Hider Find Second	-	the	1000	Canad Bridge		
Gatery	-	Final History Main	End	Rems	Other	Sewer Types and	perated or Ma	named by Themes Wate
A Saface Valler Room	-	Conternet Warry Main	End nys Undefini isrobited isrobited	clubs appear at the start or ent of a sever pipe. Examples: an el Diot at the start of a sever indicates that Thankes Waler has no ge of the position of the sever updream of that syntox. Cubiel on a valer sever indicates that the pipe discharges into a short series.		- Parl Deve		Safety Hate Seam
- Sudge Mang Shan	-1-4	Propused Durnes Hides	v	Dumi	•	- Contribut Texas		Outry
Verse			14.	Underweitind		Contract restances of	-	the second local
			~	-				
-								
Al south according with the plane are Al measurements on the plane are real Arrays (in: gravity feel sensers) or fact fine.	la Cristianica Dal Ni Ka dan daling ma	kun tauslyn. armi) Indicala direction of	the part of the part of the part of the part of the part of the	operating allangests a seven line indicates the internal disression of in milliontess. Text much to a marfate indicates the metabolic matter and stands not be labored on the plane, planes contact, a regardly set of a systemized parameter on the plane, planes contact, a regardly and that (2) take.				
these process paper are red shown on au	10.00	page the provinging has						

Figure B2 - Key to Thames Water Asset Search

ft far er Wan anne

NB. Levels quoted in metres Ordnance Newlyn Datum. The value -9999.00 indicates that no survey information is available

Manhole Reference	Manhole Cover Level	Manhole Invert Level
16BI	n/a	n/a
16BJ	n/a	n/a
16BC	n/a	n/a
16BD	n/a	n/a
15GH	n/a	n/a
15GI	n/a	n/a
1536	n/a	n/a
06FF	n/a	n/a
16CD	n/a	n/a
16DB	n/a	n/a
16DC	n/a	n/a
1602	n/a	22.3
1603	n/a	n/a
07BH	n/a	n/a
07BI	n/a	n/a
07CC	n/a	n/a
1701	27.65	23.85
07CD	n/a	n/a
15FE	n/a	n/a
05DA	n/a	n/a
15FC	n/a	n/a
05CA	n/a	n/a
051A	n/a	n/a
051B	n/a	n/a
06FA	n/a	n/a
06EB	n/a	n/a
06EC	n/a	n/a
0602	n/a	n/a
0618	n/a	n/a
061A	n/a	n/a
16CB	n/a	n/a
05EG	n/a	n/a
05EL	n/a	n/a
OSEE	n/a	n/a
0601	n/a	n/a
	1/4	n/a
0602	n/a	n/a
0005	n/a	n/a
0005		n/a
0765	n/a	n/a
0708	n/a	104
0/08	n/a	n/a

Figure B3 - Manhole Invert and Cover Levels







Search address supplied

Bayham Street London NW1 0AA

75

Your reference	P3096 75 Bayham Street NW1
Our reference	SFH/SFH Standard/2015_2969985
Received date	12 February 2015
Search date	12 February 2015

Themes Water Utilities Ltd Property Searches PO Box 3189 Slough SL1 4WW DX 151280 Slough 13

T 0118 925 1504 searches@thameswater.co.uk www.thameswaterpropertysearches.co.uk

raber Court, V rig PG 1 808

Page 1 of 3



Sewer Flooding **History Enquiry**

History of Sewer Flooding

Is the requested address or area at risk of flooding due to overloaded public sewers?

The flooding records held by Thames Water indicate that there have been no incidents of flooding in the requested area as a result of surcharging public sewers.

For your guidance:

- · A sewer is "overloaded" when the flow from a storm is unable to pass through it due to a permanent problem (e.g. flat gradient, small diameter). Flooding as a result of temporary problems such as blockages, siltation, collapses and equipment or operational failures are excluded.
- · "Internal flooding" from public sewers is defined as flooding, which enters a building or passes below a suspended floor. For reporting purposes, buildings are restricted to those normally occupied and used for residential, public, commercial, business or industrial purposes.
- · "At Risk" properties are those that the water company is required to include in the Regulatory Register that is presented annually to the Director General of Water Services. These are defined as properties that have suffered, or are likely to suffer, internal flooding from public foul, combined or surface water sewers due to overloading of the sewerage system more frequently than the relevant reference period (either once or twice in ten years) as determined by the Company's reporting procedure.
- · Flooding as a result of storm events proven to be exceptional and beyond the reference period of one in ten years are not included on the At Risk Register.
- · Properties may be at risk of flooding but not included on the Register where flooding incidents have not been reported to the Company.
- · Public Sewers are defined as those for which the Company holds statutory responsibility under the Water Industry Act 1991.
- · It should be noted that flooding can occur from private sewers and drains which are not the responsibility of the Company. This report excludes flooding from private sewers and drains and the Company makes no comment upon this matter.
- · For further information please contact Thames Water on Tel: 0800 316 9800 or website www.thameswater.co.uk

Page 3 of 3







Thames Water Utilities Ltd

Property Searches PO Box 3189 Slough SL1 4WW

DX 151280 Slough 13

T 0118 925 1504 searches@thameswater.co.uk www.thameswater-propertysearches.co.uk

water Court, Vastern Road



APPENDIX C PHOTOGRAPHS



Photograph 1



Photograph 2



Photograph 3



Photograph 4





Photograph 5- View of front of the building



Photograph 6 – View of front of the building



Photograph 7- Internal view of rear 'leg' of building



Photograph 8 – View from front building of lower roofs





APPENDIX D **OUTLINE STRUCTURAL DRAWINGS**



NC	TES				
1	This drawir	ng shall be read ir	conjunction wi	th all relevant	
_	Architects	& Engineers draw	ings and specif	ications.	
2	on site.	le any dimensions	. All dimension	S to de checke	a
LE	GEND				
-		Under			
		Under	binning		
		Existin	g walls to be de	emolished	
		New lo	adbearing wall	s	
		New p	artition walls		
P4	23.09.2016	ISSUED FOR B	IA REPORT		SP
P3	04.03.2016	ISSUED FOR B	IA REPORT		RJC
P2	23.10.2015	ISSUED FOR B	IA REPORT		SP
P1	13.10.2015	ISSUED FOR B	IA REPORT		SP
Rev.	Date	De	scription		Ву
	P	≺ELIN	IIINAI	ΥΥ	
Client					
V	/12 ST	UDIOS			
-					
Project	Title				
7	5 BAY	HAM ST	REET		
С	FFICE	SCHEN	IE		
Drawin	g Title				
R	ASEM	FNT			
С С	FNFR	AL ARR		IFNT	
e					
			Drawn SP	Sept 2	2015
			Checked		-
			IH	Sept 2	2015
Mi⊂	naelAl	exander	Scale 1:50	Size A	\1
4 Perc	URCENT NIZERUI		1:100	A	3
tel	+44 10120 8	1445 9115	Project No.	Drawing No.	Rev.
ilame Web	mail@maen; www.maen	gineers.com gineers.com	P3096	BIA 101	P4



NC	DTES				
1	This drawing shall be	read ir	conjunction wi	th all relevant	
2	Do not scale any dime		All dimension	s to be check	he
	on site.	511310113	. All dimension	s to be check	50
LE	GEND				
Ι.					
!		Exi	sting walls retai	ned	
		Exi	sting walls to be	edemolished	
		Nev	v loadbearing v	valls	
		No	-		
· ·		Nev	w partition waiis		
		RC	Slab on Metal I	Decking	
	FLN	-			
		Tim	iber floor joists		
		Nev	v Steel Beam		
	=;=;=	Dou	uble timber joist	trimmer	
P2	23.09.2016 ISSUED	FOR B	IA REPORT		SP
P1	13.10.2015 ISSUED	FOR B	IA REPORT		SP
Rev.	Date	De	scription		Ву
	DDEI	11		$\supset \lor$	
	FREL		IINAI		
Client					
V	V12 STUDIC	S			
Project		~ ~			
	5 BAYHAM	SI	REEI		
OFFICE SCHEME					
Drawin		~~			
G	ROUND FL	00		1	
L G	ENERAL A	RR/	ANGEN	IENT	
			Drawn	Sont	2015
			Checked	Sept	2013
			н	Sept	2015
Mic	haelAlexani	der	Scale 1:50	Size	\ 1
4 Perc	au Road n 112 880		1:100	,	43
tel	+44 10120 8445 9115	_	Project No.	Drawing No.	Rev.
web.	www.maeugineers.com mangineers.com	T	P3096	BIA 102	P2



| 200

	NC	DTES
	1	This drawing shall be read in conjunction with all relevant Architects & Engineers drawings and specifications.
	2	Do not scale any dimensions. All dimensions to be checked
		on site.
(A)		
Ť		
Existing wall		
TRIRIRIRI	P4	23.09.2016 ISSUED FOR BIA REPORT
ists	P3	07.03.2016 ISSUED FOR BIA REPORT
	P2	23,10,2015 ISSUED FOR BIA REPORT
	• <u>≁</u> ₽1	13.10.2015 ISSUED FOR BIA REPORT
Existing footing based	Rev	Date Description D.
on trial pit records taken on 23rd February 2015	Rev.	Date Description By
		PRELIMINARY
stem RC Underpinning	Client	+
	v	V12 510DIO5
	Projec	
	Drawir	ing Title
	P	PROPOSED SECTIONS
		Drawn SP Sont 2015
		Checked
		IH Sept 2015
	Mic	Interplay Scale Size 1:50 1
	4 Perc	ualuar nuise 1.00 A1
	tel tel	+44 0020 8445 9115 Project No. Drawing No. Rev.
	email web	meilemeengineerscom P3096 BIA 110 P4
		· · · · · · · · · · · · · · · · · · ·



PRELIMINARY CONSTRUCTION SEQUENCE FOR UNDERPINNING

Preliminary sequence to be developed in detail by the contractor following trial excavation.

1 2	120		
2	This drawing shall be read in	n conjunction with all relevant	
2	Architects & Engineers draw	vings and specifications.	d
	on site.	s. All dimensions to be checke	a
P3	07.03.2015 ISSUED FOR E	BIA REPORT	RJC
P3 P2	07.03.2015 ISSUED FOR E 23.10.2015 ISSUED FOR E	BIA REPORT BIA REPORT	RJC
P3 P2 P1	07.03.2015 ISSUED FOR E 23.10.2015 ISSUED FOR E 13.10.2015 ISSUED FOR E	BIA REPORT BIA REPORT BIA REPORT	RJC SP SP
P3 P2 P1 Rev.	07.03.2015 ISSUED FOR B 23.10.2015 ISSUED FOR B 13.10.2015 ISSUED FOR B Date Dec	BIA REPORT BIA REPORT BIA REPORT	RJC SP SP By
P3 P2 P1 Rev.	07.03.2015 ISSUED FOR B 23.10.2015 ISSUED FOR B 13.10.2015 ISSUED FOR B Date De	BIA REPORT BIA REPORT BIA REPORT BIA REPORT	RJC SP SP By
P3 P2 P1 Rev.	07.03.2015 ISSUED FOR E 23.10.2015 ISSUED FOR E 13.10.2015 ISSUED FOR E Date De PRELIN	BIA REPORT BIA REPORT BIA REPORT BIA REPORT BIA REPORT BIA REPORT	RJC SP SP By
P3 P2 P1 Rev.	07.03.2015 ISSUED FOR E 23.10.2015 ISSUED FOR E 13.10.2015 ISSUED FOR E Date De PRELIN	BIA REPORT BIA REPORT BIA REPORT BIA REPORT BIA REPORT BINARY	RJC SP SP By
P3 P2 P1 Rev.	07.03.2015 ISSUED FOR E 23.10.2015 ISSUED FOR E 13.10.2015 ISSUED FOR E Date De PRELIN	BIA REPORT BIA REPORT BIA REPORT Secription	RJC SP SP By
P3 P2 P1 Rev. Client	07.03.2015 ISSUED FOR E 23.10.2015 ISSUED FOR E 13.10.2015 ISSUED FOR E Date Date PRELIN	BIA REPORT BIA REPORT BIA REPORT Secription	RJC SP By
P3 P2 P1 Rev.	07.03.2015 ISSUED FOR E 23.10.2015 ISSUED FOR E 13.10.2015 ISSUED FOR E Date Date PRELIN	BIA REPORT SIA REPORT SIA REPORT Secription	RJC SP SP By
P3 P2 P1 Rev. Client V Projecc 7	07.03.2015 ISSUED FOR E 23.10.2015 ISSUED FOR E 13.10.2015 ISSUED FOR E Date De PRELIN /12 STUDIOS Title 5 BAYHAM ST	BIA REPORT BIA REPORT BIA REPORT SIGNIFICATION STINARY	RJC SP By
P3 P2 P1 Rev. Client V Projecc 7	07.03.2015 ISSUED FOR E 23.10.2015 ISSUED FOR E 13.10.2015 ISSUED FOR E Date De PRELIN /12 STUDIOS I Title 5 BAYHAM ST)FFICE SCHEM	BIA REPORT BIA REPORT BIA REPORT Sescription MINARY REET IE	RJC SP By
P3 P2 P1 Rev. Client V Projec 7 C	07.03.2015 ISSUED FOR E 23.10.2015 ISSUED FOR E 13.10.2015 ISSUED FOR E Date De PRELIN /12 STUDIOS : Title 5 BAYHAM ST DFFICE SCHEM o Title	BIA REPORT BIA REPORT BIA REPORT Sescription MINARY REET IE	RJC SP By
P3 P2 P1 Rev. Client V Projec Z C	07.03.2015 ISSUED FOR E 23.10.2015 ISSUED FOR E 13.10.2015 ISSUED FOR E Date De PRELIN /12 STUDIOS Title 5 BAYHAM ST PFICE SCHEN g Title	BIA REPORT BIA REPORT BIA REPORT BIA REPORT BIA REPORT MINARY	RJC SP SP By
P3 P2 P1 Rev. Client V Projec Z Drawir	07.03.2015 ISSUED FOR E 23.10.2015 ISSUED FOR E 13.10.2015 ISSUED FOR E Date De PRELIN V12 STUDIOS Title 5 BAYHAM ST DFFICE SCHEN INDERPINNING	BIA REPORT BIA REPORT	RJC SP SP By
P3 P2 P1 Rev. Client V Projec 7 C Drawir	07.03.2015 ISSUED FOR E 23.10.2015 ISSUED FOR E 13.10.2015 ISSUED FOR E Date De PRELIN V12 STUDIOS Title 5 BAYHAM ST DFFICE SCHEN INDERPINNING	BIA REPORT BIA REPORTA BIA REPORT BIA REPORT BIA REPORT BIA REPORT BIA R	RJC SP By
P3 P2 P1 Rev. Client V Projec Z Drawir	07.03.2015 ISSUED FOR E 23.10.2015 ISSUED FOR E 13.10.2015 ISSUED FOR E Date De PRELIN V12 STUDIOS Tritle 5 BAYHAM ST DFFICE SCHEM INDERPINNING	BIA REPORT BIA REPORTA BIA REPORT BIA REPORT BIA REPORT BIA REPORT BIA R	RJC SP By
P3 P2 P1 Rev. Client V Projec 7 C Drawir L	07.03.2015 ISSUED FOR E 23.10.2015 ISSUED FOR E 13.10.2015 ISSUED FOR E Date De PRELIN V12 STUDIOS Title 5 BAYHAM ST DFFICE SCHEM INDERPINNING	BIA REPORT SIA REPORTA SIA REPORT SIA REPORT SIA REPORT SIA REPORT SIA R	RJC SP By 2015
P3 P2 P1 Rev. Client V Projec 7 C Drawir	07.03.2015 ISSUED FOR E 23.10.2015 ISSUED FOR E 13.10.2015 ISSUED FOR E Date De PRELIN V12 STUDIOS Tritle 5 BAYHAM ST DFFICE SCHEM INDERPINNING	BIA REPORT BIA RE	RJC SP By 2015
P3 P2 P1 Rev.	07.03.2015 ISSUED FOR E 23.10.2015 ISSUED FOR E 13.10.2015 ISSUED FOR E Date De PRELIN V12 STUDIOS Tritle 5 BAYHAM ST DFFICE SCHEM INDERPINNING DERPINNING	BIA REPORT BIA RE	RJC SP By 2015 2015
P3 P2 P1 Rev. V Projec 7 C Drawir L Drawir L	07.03.2015 ISSUED FOR E 23.10.2015 ISSUED FOR E 13.10.2015 ISSUED FOR E Date De PRELIN V12 STUDIOS Title 5 BAYHAM ST DFFICE SCHEN INDERPINNING THE INDERPINNING THE THE STATE	BIA REPORT BIA RE	RJC SP By 2015 2015
P3 P2 P1 Rev. V Projec 7 C Drawir U Drawir U Drawir U Drawiz U Drawiz U Drawiz U	07.03.2015 ISSUED FOR E 23.10.2015 ISSUED FOR E 13.10.2015 ISSUED FOR E Date De PRELIN V12 STUDIOS Tritle 5 BAYHAM ST DFFICE SCHEN INDERPINNING Tritle INDERPINNING Tritle INDERPINNING Tritle INDERPINNING TRIE INDERPINNING	BIA REPORT BIA RE	RJC SP By 2015 2015 2015 A1 A3 Rev.
P3 P2 P1 Rev. Client V Projec 7 C Drawir L Drawir L Mitt Sanda tei amail tei	07.03.2015 ISSUED FOR E 23.10.2015 ISSUED FOR E 13.10.2015 ISSUED FOR E Date De PRELIN V12 STUDIOS Tritle 5 BAYHAM ST DFFICE SCHEN INDERPINNING Tritle INDERPINNING Tritle INDERPINNING Tritle INDERPINNING Tritle INDERPINNING	BIA REPORT BIA RE	RJC SP By 2015 2015 2015 A1 A3 Rev. P3



APPENDIX E **CONSTRUCTION METHOD STATEMENT**

CONSTRUCTION METHOD STATEMENT

- E.01 The following provides an outline Method Statement for the construction of the basement. This will be developed and finalised by the appointed Contractor, once the detailed design is complete. An outline construction programme has been included in Appendix G.
- E.02 Prior to works commencing, schedules of condition will be carried out to adjoining properties as part of the party wall process.
- E.03 Precise monitoring points will be fixed to the party walls and adjoining buildings in accordance with the agreed 'Monitoring and Contingency Plan'. Initial 'base' readings will be taken.
- E.04 The site and adjoining pavement will be scanned and marked for services prior to the commencement of any excavation works.
- E.05 A full depth trial excavation will be carried out by the Contractor prior to the commencement of the main excavation works. This will enable the Contractor to identify whether there is any perched water on the interface between the made ground and London Clay, and to check how readily the subsoil stands un-supported.

Any perched water should be collected in sumps during the excavation works and pumped.

Should the excavation sides be found locally to be unstable or there is unacceptable loss of material from the excavated face, then contingency plans will be developed, likely to include back shuttering behind the underpinning. These proposals will include measures to ensure no voids are left behind the back shuttering.

- E.06 The construction will commence with the underpinning works to the existing party walls. This will be carried out to an agreed sequence, to ensure there is at least 2m between any two open pins. A possible approach for the underpinning is shown on drawing P3096/11, which illustrates the propping that will be required during the excavation works. At this stage it is assumed that two levels of underpinning will be required, except for the part of the site adjoining Bayham Street, where the required underpinning depth will be less due to the existing and former basements. However this can be reviewed following the trial excavation.
- E.07 Lateral props will be installed within the existing buildings close to floor and roof levels prior to demolition of the existing structure. In general these will be installed full width across the building from party wall to party wall, or across corners.
- E.08 The warehouse mezzanine floor and roof structure will then be demolished, leaving the restrained party walls in place. The timing of the demolition, excavation and reconstruction works shall be to a continuous programme to minimise the heave of the clay subsoils that might result from the temporary unloading.
- E.09 The remaining sections of retaining structure can then be constructed. To the Bayham Street elevation, temporary works will be installed to ensure the stability of the adjoining pavement. Internally the retaining structure will be a reinforced concrete wall cast in sections.

- E.09a Preliminary trench excavations will be carried out to cast strip sections of the basement suspended slab to provide propping action to the base of RC underpinning in the temporary case.
- E.10 Bulk excavation will then commence. Any minor water inflows to the basement excavation will be collected in sumps and pumped. Temporary horizontal props will be installed as described previously. Permanent propping will be achieved by the ground floor slab. Regular monitoring readings will be taken and compared with 'Red' and 'Amber' trigger levels.
- E.11 When bulk excavation is complete to basement level, the bottom surface of the excavation will be immediately blinded.
- E.12 The basement suspended slab will then be constructed on top of the concrete underpin toes, to act as a permanent prop to the base of the underpinning. The sections of clay subsoil between these strips will be able to heave since the slab will be laid on layer of compressible material.
- E.13 Works can then proceed with the construction of the ground floor slab.
- E.14 Following completion of the ground floor slab, which acts as a permanent prop to the excavation, the propping can be removed.
- E.15 The superstructure of the new building can then be progressed. As each new floor level is constructed and tied into the party walls, the temporary lateral propping can be removed.
- E.16 At a later stage in the construction, once the majority of the heave has occurred, the remaining parts of the basement slab will be cast.





APPENDIX F PRELIMINARY STRUCTURAL CALCULATIONS

F1.00 INTRODUCTION

F1.01 These preliminary calculations are for planning purposes only. Detailed calculations will be developed in due course in respect of Part A of The Building Regulations

BRITISH STANDARDS F2.00

F2.01 The following Standards will be applied in the detailed design: -

BS648	Weights of Building Materials
BS5268: Part 2	Structural use of Timber: Permissible Stress design, materials and workmanship
BS5628: Part 1	Structural use of unreinforced masonry
BS5950:Part1	Structural Steelwork-Simple & continuous construction
BS5977:Part1	Lintels: Method for Assessment of Load
BS6399:Part 1	Code of Practice for Dead and Imposed Load
BS6399:Part 3	Code of Practice for Imposed Roof Load
BS8110:Part 1	Structural use of concrete

F3.00 LOADING

F3.01 New Flat Roof

Dead Load		
225mm Green Roof	4.25	kN/m ²
150mm Concrete Slab on Metal Decking	2.75	kN/m ²
Lighting and Services	0.25	kN/m ²
Total Dead Load	7.25	kN/m²
Total Live Load	0.60	kN/m ²

Existing Pitched Roof

Dead Load		
Roof Tiles	0.60	kN/m ²
Insulation	0.10	kN/m ²
Timber Structure and Boarding	0.35	kN/m ²
Lighting and Services	0.15	kN/m ²
Total Dead Load	1.20	kN/m²
Total Live Load	0.60	kN/m²

New Ground and Lower First Floors

Dead Load

150mm Concrete Slab on Metal Decking Lighting and Services **Total Dead Load** Total Live Load (+1.0 kN/m²)

Existing First and Second Floors

Dead Load

Timber Boards and Finishes Timber Joists Ceiling and Services **Total Dead Load** Total Live Load (+1.0 kN/m²)

Existing 400 thk External walls (Solid brick wall)

Dead Load 400mm thk Brick wall Finishes Total Dead Load on elevation

200mm Suspended Slab

Dead Load

200mm Concrete Slab Raised Floor

Total Dead Load Total Live Load (+1.0 kN/m²)



2.75	kN/m ²
0.25	kN/m ²
3.00	kN/m²
2.50	kN/m²

0.20	kN/m²
0.25	kN/m ²
0.35	kN/m²
0.80	kN/m ²
2.50	kN/m²

7.60	kN/m ²
0.10	kN/m ²
7.70	kN/m ²

4.80	kN/m²
0.50	kN/m²
5.30	kN/m²
2.50	kN/m²

F4.00 PRELIMINARY CALCULATIONS

F4.01 Calculation of Line Load on Underpinning (loads per linear meter)

@		
Ke	ey plan	
Loads from roof and floors in Zone A (grid I	line 1 to 2): tributary width= 2 45m	n
Wall Load:		-
7.70 kN/m ² x 8.40 m=	64.70 kN/m	
Existing Corbel (assumed)=	4.00 kN/m <u>68.70 kN/m</u>	
Roof= 2.45 m x (7.25 kN/m ² + 0.60 kN/m ²)=	= 19.25 kN/m	
Floors= 2 x 2.45 m x (3.00 kN/m ² + 2.50 kN	V/m^2)= 26.95 kN/m 46.20 kN/m	
	40.20 KW/III	
Total Load on Underpinning Walls=	<u>114.90 kN/m</u>	
Loads from roof and floors in Zone B (grid I	line 2 to 3): tributary width= 3.30m	<u>n</u>
<u>Wall Load:</u> 7.70 kN/m ² x 5.80 m=	44.70 kN/m	
Existing Corbel (assumed)=	4.00 kN/m	
	<u>40.70 NN/III</u>	
Root= $3.30 \text{ m x} (7.25 \text{ kN/m}^2 + 0.60 \text{ kN/m}^2)$ = Floors= $2 \times 3.30 \text{ m x} (3.00 \text{ kN/m}^2 + 2.50 \text{ kN})$	= 25.90 kN/m J/m²)= 36.30 kN/m	
	<u>62.20 kN/m</u>	
Total Load on Underpinning Walls=	<u>110.90 kN/m</u>	

<u>Wall Load:</u> 7.70 kN/m² x 11.70 m= Existing Corbel (assumed)=							
Roof= 3.30 m x (1.20 kN/m ² - Floors= 2 x 3.30 m x (0.80 kN Floors= 2 x 3.30 m x (3.00 kN	+ 0.60 kN/m²)= N/m² + 2.50 kN/m²)= N/m² + 2.50 kN/m²)=						
Total Load on Underpinning	Walls=						
TYPICAL UNDERPINNING I	DESIGN						
4.56 kN/m² Passive Pressure Diagram	Prop. @ 5100 Surcharge 0.886 kN Starbarge 0.						
Summary of Design Dat	a						
Notes Material Densities (kN/m ³) Concrete grade Concrete covers (mm) mm Reinforcement design Surcharge and Water Table † The Engineer must satisfy him/h practice	All dimensions are in mm Back soil 18.50, Front soil fcu 40 N/mm ² , Permissible Wall inner cover 50 mm, V fy 500 N/mm ² designed to Surcharge 2.50 kN/m ² , Ful herself to the reinforcement of						
Additional Loads Wall Propped at Base Level Additional Wall Prop Vertical Line Load † Dimensions	Therefore no sliding check Prop @ 5.1 m 110.9 kN/m @ X 0 mm an All props are measured fro Ties, line loads and partial the wall						
Soil Properties Soil bearing pressure Back Soil Friction and Cohesion Base Friction and Cohesion Front Soil Friction and Cohesion	Allowable pressure @ from $\phi = Atn(Tan(20)/1.2) = 16$ $\delta = Atn(0.75xTan(Atn(Tan))/1.2) = 25$						
	Wall Load: 7.70 kN/m² x 11.70 m= Existing Corbel (assumed)= Roof= 3.30 m x (1.20 kN/m² - Floors= 2 x 3.30 m x (0.80 kN Floors= 2 x 3.30 m x (3.00 kN Floors= 2 x 3.30 m x (3.00 kN Total Load on Underpinning N Total Load on Underpinning N TYPICAL UNDERPINNING I ***********************************						



5 5): tributary width= 3.30m

90.10 kN/m 4.00 kN/m 94.10 kN/m 6.00 kN/m 21.80 kN/m 36.30 kN/m 64.10 kN/m

<u>158.20 kN/m</u>



am and all forces are per meter run soil 18.00, Concrete 24.00 ible tensile stress 0.250 N/mm² n, Wall outer cover 50 mm, Base cover 50

to BS 8110: 1997 Fully drained nt detailing requirements of the relevant codes of

eck is required

and Y 0 mm - Load type Live from the top of the base tial loads are measured from the inner top edge of

Front 150.00 kN/m², @ back 150.00 kN/m² 16.87° Tan(20)/1.2))) = 12.82° 25.69°

Loading Cases						She
G _{Soil} - Soil Self Weight, G _{Wall} - Wall P _a - Active Earth Pressure, P _{surcharge} -	& Base Self Weight, Fv _{Heel} - V Earth pressure from surcharge	Vertical Loads over Heel, e, P _p - Passive Earth Pressu	ire		F6.00	FR
Case 1: Geotechnical Design Case 2: Structural Ultimate Design	1.00 G _{Soil} +1.00 G _{Wall} +1.00 Fv _l 1 40 G _{Soil} +1 40 G _{Wall} +1 60 Fv _l	Heel+1.00 Pa+1.00 Psurcharge Heal+1.00 Pa+1.00 Psurcharge	+1.00 P _p +1.00 P _n		F6 01	Но
Cuse 2. Structural Chimate Design	Geotechnical Des	sian	- 1.00 I p		0.01	<u></u>
Wall Stability - Virtual Ba	ack Pressure					Ba
Case 1 Overturning/Stabilising	291.079/493.505		0.590	OK		De
Wall Sliding - Virtual Bac	k Pressure					Inte
$Fx/(Rx_{Friction} + Rx_{Passive})$	0.000/(47.199+0.000)		0.000	OK		ka
Soil Pressure						
Virtual Back (No uplift)	Max(123.601/150, 68.953/150)) kN/m²	0.824	OK		VVI
Wall Back (No uplift)	Max(148.138/150, 44.416/150)) kN/m²	0.988	OK		
	Structural Desig	gn				pa
Prop Reactions		-				pa
Maximum Prop Reactions (Ultimat	e) 14	4.3 kN @ Base, 31.7 kN (@ 5.100 m			
Wall Design (Inner Steel)					Wł
Critical Section	Critical @ 0 mm from base,	Case 2				_
Steel Provided (Cover)	Main H16@200 (50 mm) D	Dist. H16@200 (66 mm)	1005 mm ²	OK		То
Compression Steel Provided (Cover)	Main H20@200 (50 mm) D	Dist. H16@200 (70 mm)	1571 mm ²			Fa
_everarm z=tn(d,b,As,ty,Fcu)	497 mm, 1000 mm, 1005 mm	n^2 , 500 N/mm ² , 40.0 N/mi	$m^2 4^2/2 \text{ mm}$			D 4
Ar=In(above,As,d,x,x/d)	1571 mm ² , 60 mm, 28 mm, 0 M 87.4 kN m Mr 206.5 kN r).00 m	200.5 KIN.M	OK	F6.02	De
Wall Axail Design (N/Ncap)	N 251.7 kN. Ncap 8880.0 kN	J	0.028	OK		П
Wall Slenderness λ	Leff/tk = $0.97x5200.0/555.0$		9.1	OK	I	RE
Wall Axail-Mom Design (M/MrAxial)	M 87.4 kN, Mr _{Axail} 276.8 kN.	m	0.316	OK	E6 03	Цr
Shear Capacity Check	F 114.8 kN, vc 0.411 N/mm ²	e, Fvr 204.3 kN	0.56	OK	-0.03	<u> </u>
Wall Design (Outer Steel)					То
Critical Section	Critical @ 3300 mm from ba	ase, Case 2				an
Steel Provided (Cover)	Main H20@200 (50 mm) I	Dist. H16@200 (70 mm)	1571 mm ²	OK		up
Compression Steel Provided (Cover)	Main H16@200 (50 mm) 1 140 mm 1000 mm 1571 mm	Dist. H16@200 (66 mm) p_{2}^{2} 500 N/mm ² 40.0 N/mi	1005 mm^2			То
Mr = fn(above As' d' x x/d)	140 mm, 1000 mm, 1371 mm 1005 mm^2 58 mm 43 mm () 31	82.6 kN m			Fo
Moment Capacity Check (M/Mr)	M 57.2 kN.m, Mr 82.6 kN.m	l	0.693	OK		Γu
Wall Axail Design (N/Ncap)	N 251.7 kN, Ncap 3200.0 kN	1	0.079	OK		Та
Wall Slenderness λ	Leff/tk =0.97x5200.0/200.0		25.1	OK		
Kmin = (Nuz-N)/(Nuz-Nbal)	Min(1.0, 3555.6 - 251.7)/(35	55.6 - 698.2)	1.0			106
$M_{add} = N.Kmin.h.\lambda^2/2000$	251.7x1.0x200.0x25.12/2000	9 I.N	-11.4kN.m	OV	F6 04	SI
Shear Canacity Check	$F = 89 \text{ kN} \text{ vc} (0.0999 \text{ N/mm}^2 \text{ F})^{-1}$	Svr 139 8 kN	0.731	OK	0.01	
Base Ton Steel Design	1 0.9 kiv, ve 0.999 ivilili , i	VI 159.0 KIV	0.00	0K		In
Steel Provided (Cover)	Main H16@200 (50 mm) D	0ist H16@200 (66 mm)	1005 mm^2	OK		pro
Compression Steel Provided (Cover)	Main H16@200 (50 mm) D	Dist. H16@200 (66 mm)	1005 mm^2	OR		flo
Leverarm z=fn(d,b,As,fy,Fcu)	542 mm, 1000 mm, 1005 mm	n ² , 500 N/mm ² , 40 N/mm ²	2 515 mm			sp
Mr=fn(above,As',d',x,x/d)	1005 mm ² , 58 mm, 28 mm, 0).05	225.2 kN.m		-	•
Moment Capacity Check (M/Mr)	M 0.0 kN.m, Mr 225.2 kN.m F 0.0 kN vc 0.391 N/mm ² F	l Fvr 211 8 kN	0.000	OK OK	F6.05	Re
Base Bottom Steel Desig	n		5.00			ТҺ
Steel Provided (Cover)	Main H16@200 (50 mm) D	Dist. H16@200 (66 mm)	1005 mm ²	OK		111 N/1*
Compression Steel Provided (Cover)	Main H16@200 (50 mm) D	Dist. H16@200 (66 mm)	1005 mm ²	~		IVI
Leverarm z=fn(d,b,As,fy,Fcu)	542 mm, 1000 mm, 1005 mm	n ² , 500 N/mm ² , 40 N/mm ²	2 515 mm			Th
Mr=fn(above,As',d',x,x/d)	1005 mm ² , 58 mm, 28 mm, 0).05	225.2 kN.m			111
Moment Capacity Check (M/Mr)	M 144.7 kN.m, Mr 225.2 kN	.m	0.643	OK		

	Shear Capacity Check	F 190.2 kN, vc 0.391 N/
6 .00	FRONT ELEVATION RETA	INING WALL
6.01	Horizontal load (during con	nstruction)
	Back soil to be London Clay Density ρ = 18.5 kN/m ³ Internal angle of friction Φ = 2 ka = (1-sin Φ) / (1+sin Φ)= (1-	20 degrees -sin20°) / (1+sin20°)=
	Where: Φ= internal angle of	friction & ρ= unit we
	$pa_1 = ka \times \rho \times h_1 = 0.49 \times 18.9$ $pa_2 = ka \times \rho \times h_2 = 0.49 \times 18.9$	5 kN/m³ × 2.00 m = 18 5 kN/m³ × 5.20 m = 4
	Where: ka= coefficient of act	ive pressure & h= h
	Total horizontal force on wal $Fa = 0.5 \times pa \times h = 0.5 \times 47.1$	l due to backfill is: 5 kN/m² x 5.2 m= 122
6.02	Design Check (during con	struction)
	Refer to Clause F5.01	
5.03	Horizontal load (permanen	t condition)
	To the horizontal load calcula applied as uniform face load	ated above (refer to cla to wall.
	Total horizontal force on wal $Fa= 0.5 \times pa \times h + Q \times h = 0.5$	l due to backfill is: 5 x 47.15 kN/m² x 5.2
	To avoid failure of the existin load and internal RC retainin	ng brickwork wall of its ng wall will resist the fa
6.04	Sliding Capacity and Over	turning Capacity Che
	In permanent conditions slidi propped at top and bottom b floor void the underpinning a span between points of later	ing and overturning ch y ground floor and bas nd retaining wall will b al restraint.
6.05	Retaining Wall Design	
	The total bending moment as $M^* = 0.06415 \times pa_2 \times h^2 + Q$	cting on the wall due to $h^2 / 8 = 0.06415 \times 47$.
	The moment will be rested b	y a 300mm RC wall re



/mm², Fvr 211.8 kN

0.90 OK

: (1-0.34) / (1+0.34)= 0.66 / 1.34= 0.492

eight of soil

18.13 kN/m² (at prop level)
 47.15 kN/m² (at the bottom of excavation)

height of retained fill

2.59 kN

lause F6.01) a surcharge Q= 20 kN/m² is

m + 20 x 5.2= 226.59 kN

s interface with the new underpinning ace loading.

eck (permanent condition)

hecks are not required as the wall will be asement slabs. Where there is a ground be reinforced laterally to enable them to

to the face loads (M*) is: 7.15 x 5.20² + 20 x 5.20² / 8= 149.38 *kNm*

einforced with T20 @200 c/c



APPENDIX G

OUTLINE CONSTRUCTION PROGRAMME

P3096 75 BAYHAM STREET, LONDON NW1 0AA						.0 Is	ued for BIA	4		07/03/2016																		
PROGRAMME/ACTION LIST																												
TASK		0	~			10	<i>(</i>)		~		0	5		2	ε	4	15	9	2		ი	c	2	5	52	53 53	54	
	Month	Month	Month	Month 4		Month	Month (Month	Month 8	Month (Month	Month		Month .	Month	Month	Month	Month	Month		Month	Month		Month	Month	Month	Month	
Planning			-																									
Planning Approval																												
			-																									
Design										<u>This proc</u>	gramme	is for	-															
Architectural Design			-						in	formation	only and	l subj	ect															
Architectural Design			_						<u>tc</u>	o detailed o	consider	ation	<u>by</u>															
Structural Design			_							the appoir	nted con	tracto	<u>or</u>															
Contractor appointment				•																								
Agreement of Detailed		<u> </u>													 													
Construction Method																												
			_												 													
Party Wall			_																									
De uter 187-11 Arriende Alemand			_																									
Party Wall Awards Agreed		<u>+</u>	_		<u> </u>																							
			_																									
Structural Works		+	_																									
Start on site			_																									
F achling and a			-												 													
Enabling works			-																									
Temporary works & demolition			-																									
of roof and floors			-																									
Underpinning & installation of		<u> </u>	-																									
temporary propping			_																									
Excavation of basement			-																									
Basement slab			-																									
Commence of steel frame		+	-																									
			-																									
Ground floor slab			_																									
Superstructure			-																									
			_												 		 								<u> </u>			
Completion		+	-																									
Finishes, M&E intallation, etc.			-			+			<u> </u>						 		 		1									
												1								1	1							