



Pre-development Arboricultural Survey and Report

Land at 12 Platts Lane, Hampstead London NW3 7NR

A report to: Orly Weinberger, 12 Platts lane NW3 7NR

Date: 8th February 2017

Report No: WAS42/2017 REV2

Table of Contents

Report Verification.....	4
Disclaimer.....	4
Validity of Data.....	4
Introduction and Scope of Report.....	5
Abbreviations:	5
Arboricultural Impact Assessment	6
Proximity of Proposed Development to existing Trees.....	6
Tree Protection Measures (Provisional).....	7
Excavation within RPA of Retained Trees	7
Tree Protection Barriers & Construction Exclusion Zone.....	7
Ground Protection of Existing Surfaces within Root Protection Area (RPA) of Retained Trees	7
Access Facilitation Pruning & Tree Works.....	7
Site Access and Construction Working Area (CWA).....	7
Site Storage and Accommodation.....	7
Installation of Services	8
Arboricultural Supervision (AS)	8
Conclusion	8
Tree Grading Categories.....	9
Trees categorized within this report:.....	9
References.....	11
Declaration	11
Addendum 1 – Tree Protection	12
Table 1 -Tree protection measurements	12
Protecting Root Zone of Trees (BS 5837:2012 section 6.2 Figs. 2 & 3):.....	13
The Root Protection Area (RPA).....	13
Key Points	13
Excavation within Root Protection Area of trees.....	13
Site Hoarding.....	14
Ground Protection System Specification:	14
Addendum 2 – Tree Works.....	15
Schedule of Tree Works	15

Office: 15 Norcombe House, Wedmore St., Islington N19 4RD

Tel: 07860 445380

Email: office@wassells.co.uk

www.wassells.co.uk

Addendum 3 - Schedule of Tree Survey Information – BS5837:2012 section 4.4 16

 TREE SURVEY KEY: 17

Addendum 4 – Tree Protection Barriers and Tree Care Flow Chart 19

Addendum 5 – Plans and Picture Gallery 23

Report Verification

This study has been undertaken in accordance with British Standard 5837:2012 “Trees in relation to design, demolition and construction - Recommendations”.

Disclaimer

The contents of this report are the responsibility of Wassells Arboricultural Services Ltd. It should be noted that, whilst every effort is made to meet the client’s brief, no site investigation can ensure complete assessment or prediction of the natural environment.

Wassells Arboricultural Services Ltd accepts no responsibility or liability for any use that is made of this document other than by the client for the purposes for which it was originally commissioned and prepared.

Validity of Data

The findings of this study are valid for a period of 12 months from the date of survey. If works have not commenced by this date, an updated site visit should be carried out by a suitably qualified and experienced arboriculturist to assess any changes to the trees and groups on site and to inform a review of the conclusions and recommendations made.

It should be noted that trees are dynamic living organisms that are subject to natural changes as they age or are influenced by changes in their environment. As such following any significant meteorological event or changes in the growing environment of the trees they should be re-assessed by a suitably qualified and experienced arboriculturist.

Introduction and Scope of Report

This document has been produced to provide a detailed survey of trees that could be affected by the proposed development and that are within, surrounding and nearby to this reports site demise.

The scope of this report follows the recommendations and guidance described within **BS 5837: 2012 *Trees in Relation to Design, Demolition and Construction – Recommendations*** which sets out the principles and procedures to be applied to achieve a harmonious and sustainable relationship between trees and structures.

The report will assess the quality, amenity and landscape value of all surveyed trees as described by the tree category system within BS 5837 (see section below).

The protection of all trees to be retained and where they are likely to be affected by the proposed development construction activities are described as provisional tree protection measures for information purposes only and shall require a site specific AMS once final plan are agreed.

The report will also indicate, where necessary, the likely impact the proposals may have on those trees in the future.

The report will also recommend any required tree works to enable access and also to mitigate potential damage from construction activity and for the future well being of the trees concerned.

This is intended to support the planning application for development of this site.

The tree survey for the site can be found in Addendum 3 below

Abbreviations:

RPA = root protection area

CEZ = construction exclusion zone

CWA = construction working area (including materials storage)

AMS = arboricultural method statement

Office: 15 Norcombe House, Wedmore St., Islington N19 4RD

Tel: 07860 445380

Email: office@wassells.co.uk

www.wassells.co.uk

Arboricultural Impact Assessment

Proximity of Proposed Development to existing Trees

Ref: Addendum 1 -Table 1, Addendum 3

All trees in or near the above site have been surveyed and that information is shown in addendum 3 below.

The proposed development of this site involves the construction of a new basement that extends into a sunken patio at the rear of the property.

There is a strong massing of trees along the rear boundary of the site, which act as a good local amenity and screening for the school and playground to the rear of the garden. There is a large and fine specimen Ash tree in the eastern rear corner of the site that is a dominant tree within the local area.

None of these trees comprising of T1 to T7 shall be affected by the proposed development.

Tree protection barrier should be erected across the rear garden at 2 metres behind the proposed rear of the sunken patio to protect the trees from construction activity and storage of waste/ materials.

At the front of the property there is a reasonable quality False Acacia T8 growing right in the northern corner within a raised bed. This tree has pushed out the front boundary wall due to proximity and is close to the adjoining property number 14. Some builder's rubble has been stacked around the base of this tree and should be removed ASAP to prevent damage to the stem of the tree.

It is proposed to retain this tree but shall require future pruning for encroachment to the next door property. The proposed basement light well to the front of the property is unlikely to impact the RPA of this tree but it just enters the edge of what is the typical RPA for the tree - please see provisional AMS in next section

Tree protection barrier for this tree shall be required to prevent any construction activity damage.

Tree Protection Measures (Provisional)

Ref: Addendum 1 & 2

**** These measures shall be seen as provisional for planning purposes and subject to a detailed follow up AMS submission as part of a construction plan once proposals are agreed and to conform to any specific planning conditions made ****

Excavation within RPA of Retained Trees

Ref: Addendum 1

* Please see addendum 1 section on Excavation within RPA of retained trees.

None for T1 to T7

Potential for T8 but unlikely to be significant – AS required when excavating the front basement lightwell

Tree Protection Barriers & Construction Exclusion Zone

*Please see specification for tree protection barriers shown below

Trees T1 to T7 shall be protected as shown in tree survey plan below in addendum 5 and using barrier as per figure 3 in addendum 4 below.

Tree T8 shall be protected using barrier as per figure 3 in addendum 4 below and constructed as 3 metre square around the tree on house side.

Ground Protection of Existing Surfaces within Root Protection Area (RPA) of Retained Trees

Ref: Addendum 1

* Please see addendum 1 section on Ground Protection System

Tree T8 to be protected using existing hard paving during construction phase

Access Facilitation Pruning & Tree Works

Ref: Addendum 2

Recommended tree works are shown in the end column of addendum 3 below

Site Access and Construction Working Area (CWA)

CWA to be outside of tree barriers and CEZ

Site Storage and Accommodation

Not within the RPA of retained trees.

Installation of Services

Arrangements for this element of the development of the site are unknown as at time of writing this report but are likely to remain as existing.

Changes to the service routes will be carefully considered using the AS below to advise on protection of nearby trees prior to commencement on site.

Arboricultural Supervision (AS)

AS shall be required during work within and adjacent to the RPA of retained trees. It must be undertaken at regular intervals with a written record of the meetings maintained with suitable photographic record in support.

The AS must include a pre-construction commencement site visit, to be arranged by the Site Manager under instruction from Architects, and thereafter at specific events that affect the retained trees on site to enable sign-off by the AS. These are typically as follows:

1. Erection of tree protection fencing
2. Installation of ground protection to retained trees whose RPA are effected by the CWA
3. Start of Excavation/piling of foundations within the RPA of retained trees
4. Tree pruning requirements to prevent crown damage from construction activity
5. Start of Excavation/installation of paths, roads and car parking within RPA of retained trees
6. Installation of underground services within the RPA of retained trees
7. Tree condition survey on completion of construction work

Conclusion

Provided the recommendations shown above and the methodology for protection of any retained trees are followed, there will not be an effect on the current or future condition of those trees that are retained as part of the proposed scheme.

Tree Grading Categories

Ref: Grading Category as per BS 5837:2012 Section 4.5 Table 1 & Table 2 – Tree quality assessment chart.
Tree Survey Schedule in Addendum3 below for description of trees categorized

The grading categories are based on the following criteria:

A= those trees of high quality and value suitable for retention for longer than 10years and worthy of being a material constraint to development

B= those trees of moderate quality and value suitable for retention for longer than 10years and worthy of being a material constraint to development

C= those trees of low quality and not worthy of being a material constraint to development

U=trees of such a condition that they cannot realistically be retained as living trees in the context of the current land use

NG = not graded. Those trees not considered to be in any of the above categories

Categories A, B and C have further sub-categories (not qualified in BS) with regards to the reasons for tree retention as follows:

- 1: Mainly arboricultural qualities.
- 2: Mainly landscape qualities.
- 3: Mainly cultural values, including conservation.

Trees categorized within this report:

- 1 Category A trees = T1
- 2 Category B trees = T8
- 3 Category C trees = T3, T4 and T6
- 4 Category U trees = T2, T5 and T7
- 5 NG = none

Age Categories and Distribution

Those trees assessed as being young (Y) in age can generally be considered to have significant growth potential. Whilst these specimens are not likely to make a substantial contribution to the landscape character of the site at present they will, if retained, provide succession for the eventual removal of mature or over-mature trees as a result of declining physiological or structural condition.

Semi mature trees (SM) will generally make a significant contribution to the landscape character and appearance of the site and their retention will provide more immediate succession. These trees will also have significant growth potential.

Mature trees (M) are not considered to have significant future growth potential and have generally reached their maximum expected size for the location. These trees will generally make the highest contribution to the landscape contribution of the site however a tree stock over dominated by mature trees will require careful management to ensure that continuation of canopy cover can be achieved.

Over-mature trees (OM) do not have the potential to increase in size and may in fact reduce in size as their crowns begin to break up. These trees will often make a significant contribution to the landscape character of the site and are likely to have ecological value. However the retention of these trees within new development must be carefully planned as they are approaching the end of their useful life expectancy and they will often have structural defects. Where over-mature trees are to be retained in new development it is essential that access is available for their eventual removal.

Veteran trees (V) are those that show features of biological, cultural or aesthetic value that are characteristic of an individual surviving beyond the typical age range for the species. These trees have negligible potential to increase in size. Veteran trees are usually of a high ecological value and they will require sensitive management where they are to be retained in new development. As such it is again essential that they are located in areas where access is available to undertake management operations and where there is a reduced risk of harm occurring from failure of the trees.

References

1. BS 5837:2012 Trees in Relation to Design, Demolition and Construction - Recommendations
2. BS3998:2010 Tree Work – Recommendations
3. NJUG Volume 4 Issue2 2007 – Guidelines for the planning, installation and maintenance of utility apparatus in proximity to trees.
4. NHBC Standards – Section 4.2 Building Near Trees
5. British Geological Survey – London & the Thames Valley
6. Principles of Tree Hazard Assessment – Lonsdale 2001
7. Diagnosis of Ill Health in Trees – Stouts & Winter 2004
8. Tree Survey Plan – at end of report
9. Existing and proposed plans – XUL Architecture drawings 1610 suite

Declaration

This Tree Survey, Impact Assessment and provisional tree protection measures have been written and checked by Richard Wassell of Wassells Arboricultural Services Ltd. and are provided without prejudice as an objective and professional assessment of the trees described.

Signed: *R.J.Wassell* Date: *08.02.MMXVII*

Richard Wassell. Director

MCIHort MArborA NDArb (RFS) Kew Diploma NEBOSHlevel3

Addendum 1 – Tree Protection

Ref: BS 5837:2012 in Tables C.1 & D.1 of annex C & D

Table 1 -Tree protection measurements

Tree Number As per tree survey plan & schedule	Stem Diameter @ 1.5 metres agl. Millimetres	Root Protection Area (RPA) - Radius *measured from centre of stem* Metres	Tree/Root Protection Area (RPA) Sq. Metres	Comment and potential affect of building proposal on the total RPA
T1	900	10.8	366	Not affected
T2	200	2.4	18	Proposed for removal
T3	275	3.3	34	Not affected
T4	450	5.4	92	Not affected
T5				Dead
T6	300	3.6	41	Not affected
T7	250	3	28	Proposed for removal
T8	400	4.8	72	Not affected. AS required when excavating front light well

Office: 15 Norcombe House, Wedmore St., Islington N19 4RD

Tel: 07860 445380

Email: office@wassells.co.uk

www.wassells.co.uk

Protecting Root Zone of Trees (BS 5837:2012 section 6.2 Figs. 2 & 3):

The Root Protection Area (RPA)

This is the area surrounding a tree that is deemed to contain sufficient roots and rooting volume to maintain the trees viability in the future. The root system is typically concentrated in the uppermost 600 – 1200mm of the soil and is not necessarily symmetrical around the tree, being dependant on a number of factors such as water, nutrients, oxygen, soil penetrability and physical obstructions such as existing foundations or changes in level (terracing).

The RPA is a design layout tool that is deemed to be a minimum area around a tree where the protection of roots and soil structure are treated as a priority. This area is envisaged as and portrayed with a circle around each tree but where there appears to be restrictions to root growth the circle is reshaped to reflect more accurately the likely distribution of the rooting area of the tree concerned.

Key Points

1. AVOID building works within the RPA if at all possible but if not then carefully consider the following: where the RPA is likely to be severely affected because of site design constraints then felling and planting replacement(s) trees in a more suitable location on the site will need to be considered.
2. Where possible do not use strip foundations within the RPA, if absolutely necessary consider using a trenching saw or excavate by hand to avoid 'shatter damage' to the root system.
3. Consider using piling techniques for foundations @ maximum 350 mm diameter with ground beams on or above the surface of the root zone.
4. Unless unavoidable, do not exceed entering the root zone by more than one fifth of RPA radius.
5. Do not trench tangentially across the root zone for footings and services unless it cannot be avoided.
6. Consider 'no dig' techniques for services installation, with radial service lines being preferable to tangential across the root zone. Where this is undertaken then boring must be carried out below 600mm deep.
7. Any hard surfacing, paths and roads need to have the same considerations for the RPA and as in the above points. Where possible paths and hard surfacing (patios etc) need to be surface constructed (cellular) and semi-porous to allow water penetration and gaseous exchange into the root system of trees.

Excavation within Root Protection Area of trees

Where trees are to be retained then any proposed foundation, underground services work and hard surfacing such as roads/paths falling within the RPA of trees that are to be retained shall be kept as far away from tree stems as possible(SEE NOTE 1 ABOVE). Where any such works are necessary within the RPA there will be a requirement to dig carefully by hand and ensure any roots encountered of maximum 25mm in diameter shall be exposed and correctly pruned back by a competent Arborist. Where larger roots are encountered of above 25mm in diameter then advice from the Arboricultural Supervisor (AS) for the site must be sought prior to any work being undertaken.

Office: 15 Norcombe House, Wedmore St., Islington N19 4RD

Tel: 07860 445380

Email: office@wassells.co.uk

www.wassells.co.uk

Any roots exposed/ pruned back as part of the above operation shall NOT be left exposed to drying out. All roots exposed/pruned shall be either covered with damp Hessian sacking prior to backfill or backfilled/covered immediately with a suitable open and free draining compost/loam.

Site Hoarding

Site hoarding shall be no closer than 1.5 metres away from the stem of retained trees and consist of 20mm plywood sheets supported by minimum 100mm square posts and 100 x 50mm rails with posts at 2.5 metre centres.

Post holes for site hoarding that are required within the RPA of nearby trees shall be dug by hand and are to be a maximum of 300 x 300mm and 450mm deep

Ground Protection System Specification:

- Level area of RPA concerned by blinding with sharp sand at maximum depth of 50mm
- Lay geo-textile membrane such as 'Terram' to cover area concerned
- Cover geo-textile with maximum of 100mm MOT Type 1 sub-base
- Retain MOT type 1 with edge restraint such as 30 x 100mm edging board pegged every 2 metres to prevent migration of the sub-base

Addendum 2 – Tree Works

Ref: Addendum 3

Schedule of Tree Works

1. All proposed tree removal and tree pruning works are described in the management recommendations of the tree survey in addendum 3

2. Tree work to be carried out to the following standards and guidelines:
 - BS 3998:2010 Recommendations for Tree Work

 - Tree pruning cuts will be carried out using the ‘Natural Target Pruning’ technique as defined by: *BS 3998:2010 section 7.2.5 and Fig. 2 The Pruning of Trees, Shrubs and Conifers: George E. Brown & Tony Kirkham – 2nd edition revised & enlarged 2004 and Section 3.1.27 of The Arboricultural Association Specification for Tree Works June 2008.*

 - Crown clean involves removal of dead, diseased & dying wood from tree crown, thinning of overcrowded crown, and removal of ivy and all epicormic growth within crown including stem & basal epicormic growth.

Addendum 3 - Schedule of Tree Survey Information – BS5837:2012 section 4.4

SITE: 12 Platts Lane NW3 7NR

DATE: 26th May 2016

Tree Number	Species	Diameter Class mm	RPA radius metres	Ht. M	Crown Spread metres	Crown height	Age Class	Grading Category	Estimated Life Expectancy	Structure	Physiology, Condition & other factors	Management recommendation
1	Common Ash	900	10.8	25	N=10 W=10 E=8 S=8	L/M	M	A2	>30	G	A Good specimen with wide spreading canopy. Some deadwood	RETAIN CC
2	Elderberry	200	2.4	5	N=2 W=3 E=0 S=0	L	M	U		P	Leaning towards the house and suppressed by T1	REMOVED JULY 2016
3	Norway Maple	275	3.3	12	N=4 W=4 E=4 S=4	M	SM	C2	>10	M	A Twin stem from 2 metres	RETAIN CC and remove Ivy
4	False Acacia	450	5.4	12	N=1 W=0 E=4 S=4	M	M	C2	>10	M	A. Ivy clad stem and leaning out over school playground to the rear	RETAIN CC and remove Ivy
5	Cherry							U		P	Dead	REMOVED JULY 2016
6	Silver Birch	300	3.6	12	N=3 W=8 E=4 S=4	M	M	C2	>10	M	A Ivy clad stem and lower crown	RETAIN CC and remove Ivy
7	Elderberry	250	3	6		L	M	U		P	Twin stem from 1 metre	REMOVED JULY 2016
8	False Acacia	400	4.8	11	N=4 W=4 E=3 S=3	M	M	B2	>20	M	A. Growing in raised bed right in the corner of front boundary wall with next door. Wall has been pushed out over pavement and damaged. Crown v. close to No. 14 next door. Deadwood	RETAIN CC RC on No. 14 side by 2M and balance

*RPA = bold dashed red circle around centre of tree. ** Crown spread shown as line around tree and shaded as per grading category above

TREE SURVEY KEY:

Tree Number and Species = number of tree on plan and Common Name as per reference book: A Field Guide to the Trees of Britain and Northern Europe by Alan Mitchell 1974 ISBN: 0 00 219213 6

Height = estimated height of tree from surrounding ground level +/- 3 metres

Diameter Class = diameter of main stem @ 1.5 metres above ground level

Crown Spread = maximum extent of branches measured radially from the base of the tree, trees with asymmetrical crowns are shown with distances in relation to compass points. N = north etc.

Crown Height = height of canopy and/or first major branch above ground level. Low (L) = below 3 metres | Medium (M) = 3 to 6 metres | High (H) = above 6 metres

Age Class = Young(Y): age less than 1/3rd life expectancy | Semi-mature(SM): 1/3rd to 2/3rd life expectancy | Mature (M): Over 2/3rd life expectancy | Over mature (OM): mature and in state of decline | Veteran (V): Surviving beyond typical age range for species

Grading Category: As per BS 5837:2012 Table 1 – Tree quality assessment, which refers to tree quality and landscape/amenity value; A=high, B=moderate, C=low, U = not suitable for retention, NG= not graded

Estimated Life Expectancy = estimated useful and remaining contribution to the site in years

Structure = structural condition of the tree based on roots, trunk, and major stems/branches along with the presence of any structural defects and decay organisms. Categories are: Very Good (VG); Good (G); Moderate (M); Poor (P); Hazardous (H)

Physiology/Condition = Overall health, condition and function of the tree in comparison to a 'normal' specimen of its species and age. Categories are: Above average (AA); Average (A); Declining (D)

Other factors = any other physical/environmental factors that could influence the tree now/in the future

Management Recommendations: **N** = no work required. **CC** = removal of dead, diseased & dying wood from tree crown, thinning of overcrowded crown, removal of Ivy from crown & stem and removal of all epicormic growth within crown including stem & basal epicormic growth on Lime trees. **LC** = lift crown. **TC** = thin crown. **RC** = reduce crown. **P** = pollard. **SP** = scaffold pollard. **RE** = remove epicormic and basal growth. **FP** = Formative prune **F** = fell to ground level. **FG** = fell and grind out stump. **R** = carry out replacement planting. **AI** = 3 yearly Arboricultural inspection

RPA radius = radius of typical root protection area, described as a circle and measured around centre of the tree

N/K = not known

= estimated data

NDG = Next door garden

g.l. = ground level

Alan Mitchell System = Estimate of tree age based on open grown tree with full crown. Age in years = Girth (circumference) in centimetres measured at 1.5 metres above ground level and divided by 2.5 i.e. Tree of girth 250 cm = 100years old

Office: 15 Norcombe House, Wedmore St., Islington N19 4RD

Tel: 07860 445380

Email: office@wassells.co.uk

www.wassells.co.uk

Addendum 4 – Tree Protection Barriers

6.2.2.4 All-weather notices should be attached to the barrier with words such as: "CONSTRUCTION EXCLUSION ZONE – NO ACCESS".

Figure 2 Default specification for protective barrier





Figure 3 Examples of above-ground stabilizing systems








Wassell, Wassells Arboricultural Services, Version correct as of 17.05.2012, (c) The British Standards Institution 2012

Addendum 5 – Plans and Picture Gallery

- *Proposed and existing site plans
- *Tree survey details
- *Tree protection measures

Tree Survey Plan Overlay

9th June 2016
Updated 8th February 2017



Ground Floor Office
33 Belize Lane
London NW3 5AS

Office: +44 (0) 207 431 9014
s.sandler@xularchitecture.co.uk
www.xularchitecture.co.uk

PLEASE NOTE:

1. ALL DIMENSIONS TO BE CHECKED ON SITE BEFORE FABRICATION.
2. CONTRACTOR TO REFER TO ENGINEERS DRAWINGS BEFORE PROCEEDING WITH WORKS.
3. ALL DRAWINGS AND DESIGNS ARE COVERED BY DESIGN RIGHT (INTELLECTUAL PROPERTY), AND MAY NOT BE DISTRIBUTED, COPIED OR ISSUED WITHOUT WRITTEN PERMISSION OF XUL ARCHITECTURE.
4. ALL DESIGN CONCEPTS ARE THE SOLE PROPERTY OF XUL ARCHITECTURE AND NO ADAPTATIONS, REPRODUCTIONS OR COPIES MAY BE MADE WITHOUT WRITTEN PERMISSION OF XUL ARCHITECTURE.
5. THESE DRAWINGS ARE SUBJECT TO ANY VARIATION REQUIRED OR RECOMMENDATION BY ANY STATUTORY AUTHORITY OR FOR THE BETTER CARRYING OUT OF THE WORKS.
6. SAMPLES TO BE PROVIDED BY CONTRACTOR FOR XUL ARCHITECTURE APPROVAL.
7. ALL FINISHES TO XUL ARCHITECTURE SATISFACTION.
8. ALL DRAWINGS TO BE APPROVED BY XUL ARCHITECTURE BEFORE CONSTRUCTION.

ADDITIONAL NOTES:

REVISIONS		
No	Date	Description Issue For
00	25/05/16	INFORMATION
01	26/05/16	INFORMATION
02	27/05/16	INFORMATION
03	01/06/16	INFORMATION

Client		Issue By
PRIVATE CLIENT		JH
Project		
12 Platts Lane		
NW3 7NR		
Title		
PROPOSED		
Ground Floor Plan		

Scale		Dwg. No.	Rev.
1/100@A3		PA-02	03
Date			
24/05/16			
Drawn			
JH			
Checked			
CC			

PLEASE NOTE:

1. ALL DIMENSIONS TO BE CHECKED ON SITE BEFORE FABRICATION.
2. CONTRACTOR TO REFER TO ENGINEER'S DRAWINGS BEFORE PROCEEDING WITH WORKS.
3. ALL DRAWINGS AND DESIGNS ARE COVERED BY DESIGN RIGHT (INTELLECTUAL PROPERTY), AND MAY NOT BE DISTRIBUTED, COPIED OR ISSUED WITHOUT WRITTEN PERMISSION OF XUL ARCHITECTURE.
4. ALL DESIGN CONCEPTS ARE THE SOLE PROPERTY OF XUL ARCHITECTURE AND NO ADAPTATIONS, REPRODUCTIONS OR COPIES MAY BE MADE WITHOUT WRITTEN PERMISSION OF XUL ARCHITECTURE.
5. THESE DRAWINGS ARE SUBJECT TO ANY VARIATION REQUIRED OR RECOMMENDATION BY ANY STATUTORY AUTHORITY, OR FOR THE BETTER CARRYING OUT OF THE WORKS.
6. SAMPLES TO BE PROVIDED BY CONTRACTOR FOR XUL ARCHITECTURE APPROVAL.
7. ALL FINISHES TO XUL ARCHITECTURE SATISFACTION.
8. ALL DRAWINGS TO BE APPROVED BY XUL ARCHITECTURE BEFORE CONSTRUCTION.

ADDITIONAL NOTES:

REVISIONS

No	Date	Description Issue For	Issue By
00	25/05/16	INFORMATION	JH
01	27/05/16	INFORMATION	JH
02	03/06/16	INFORMATION	JH
03	07/06/16	INFORMATION	AM

Client
PRIVATE CLIENT


Project
12 Platt's Lane
NW3 7NR

Title
EXISTING
Ground Floor Plan

Scale 1/100@A3	Dwg. No. EX-01	Rev. 03
-------------------	-------------------	------------


Date 07/06/16	Drawn JH	Project Number 1610
------------------	-------------	------------------------

Checked
CC



EXISTING TREES / PLANTING TO BE RETAINED

REAR GARDEN




This tree not there when site surveyed?
RJW 26.05.2016

EXISTING
Ground Floor Plan
SCALE 1/200@A3 EX-01




EXISTING
Ground Floor Plan
SCALE 1/100@A3 EX-01



Tree
9th J
Upd

W:
Lender




Tree protection barrier

REAR GARDEN

8th February 2017

Extract of proposed plan
showing RPA of
potentially impacted trees

Wassells
London's Urban Tree Specialist



Tree protection barrier

CROWN
T8

T8


RPA T8



PROPOSED
Ground Plan
SCALE 1/200@A3 PA-02



Ash tree T1 from rear of house



View of rear of garden trees from house



False Acacia T8 with front of number 12 on RHS