

Existing projecting entrance surround to be retained, with new full width fascia sign. DDA WC 3.3 sqm 35 sqft 1500 Doc M Pack. New Steel Door PB with external tracking handle. Spy Hole Gross Bolt Ø1500 Area New Door 99 FD30s VP SC 80 Mag Lock with enlergency release 22.4 sqin 241 saft Combined Staff Area Allow for 1no internal roller shutter across 13.6 şqn 146 sqft entrance doors and adjacent glazing panels. GROSS AREA 159.4 sqm 1715 sqft SALES AREA Entrance and internal ramp moved towards 130.3 sqm 1402 sqft column to increase circulation to front of cosmetics. New shop front and sliding entrance doors as revised retail layout, as Superdrug NFOS New Sliding Door Sec as part of shop front with 1920mm long ramped access to accommodate 183mm change in level additional cut out required to form channel for sliding doors to open into to sides. Existing tiled projection retained, pilasters tiled as Superdrug NFOS with full width folded aluminium fascia sign across shop

The contractor must verify all dimensions on site before any works are undertaken, discrepancies are to reported to the project architect/designer for clarification.

the relevant contractor before commencement of work.

All works will be carried out in accordance with the SUPERDRUG NFOS document & are to comply with the

tenants fit out guidelines following landlords approval. HVAC, M&E layouts are indicative & must be verified with

All works to be carried out in accordance with the fire

strategy and fire cert application schedule produced by the landlord team issued at tender.

The existing\proposed sprinkler system is to be assessed

This drawing remains the property of ASWATSON/SUPERDRUG & may not be reproduced in any way without prior consent.

## SCHEDULE OF RISKS Standard risks and hazards normally associated with

the types of work detailed on this drawing, include:

• Electrocution: M&E installation/alterations. • Working at height: Falls from scaffolds,

building regs part B.

platforms & ladders. Falling materials.

Noise: Use of power tools & demolition equipment.

Dust: Use of power tools & demolition

Suffocation: Fume inhalation from

installation/alterations to incoming services,

working with hazardous materials/solvents.

• Trip hazards: Loose cables & materials.

• Working in close proximity to the public.

 Risks associated with structural works will be assessed be a structural engineer.

It is assumed that all works on this drawing will

be carried out by a competent contractor working, where appropriate to an approved method statement.

160/1722 Gross Area 130.3/1402 Total Sales 23/247 - Staff Room (combined BoH area) 14.1 / 151 Managers Office 4.9 / 53 3.3/35 - Warehouse - Circulation Area

DOOR SCHEDULE									
Door	Location	Leaf Size	Comments						
DG01	Entrance doors		Installed as part of new sho front						
DG02	BoH access door	926 x 2040	FD30s VP SC Mag lock with emergency overide						
DG03	Managers Office	926 x 2040	FD30s VP SC Digi Lock						
DG04	Delivery/Exit	1000 x 2040	Steel door, PB, external lock handle & Spy Hole						
DG05	DDA Compliant WC	950 x 2040	DDA Doc M Pack						
DG06									
DG07									
DG08									
DG09									
DG10									
DG11									
DG12									
DG13									
DG14									
DG15									

## ALL NEW DOOR SIZES TO BE CONFIRMED ON SITE BY CONTRACTOR PRIOR TO MANUFACTURE.

KLV	DAIL	01	REVISION NOTE

## PROPOSED GA PLAN - Planning Issue

CPS 16 078 010						
SCALE 1:50 @ A1	DATE 03.10.16	DRAWN <b>LK</b>	CH.			

133 CLERKENWELL ROAD

LONDON

Superdrug.