USE IN CONJUNCTION WITH FINISHES SCHEDULE AND DETAIL DRAWINGS

FLOOR FINISHES LAYOUT LEGEND

Symbols shown are not to scale
some symbols may not appear on the layout plan

- **WDF-1** - Engineered Timber Floor
- **WDF-2** - Engineered Timber Floor Herringbone
- **WDF-3**- Engineered Timber Floor to ramps. Stained to colour as contrast to denote change in level
- **BM1** - Barrier mat
- **CP-1a, b, c** etc - Carpet (tile) SEE FINISHES SCHEDULE FOR ACTUAL DETAILS PER ROOM
- **CP-2a, b, c** etc - Carpet (tile) SEE FINISHES SCHEDULE FOR ACTUAL DETAILS PER ROOM
- **VT-1** - Loose lay vinyl. ply underneath to level TBC
- **VT-2** - Anti-Static tile Loose lay vinyl tile to allow access.
- **VT-3** - Inset vinyl to floor boxes. *See LLS Design Intent drawing for locations.*
- **RFT** - Exposed raised floor tiles
- **CT-1** - Ceramic floor tiles SEE SEPARATE DETAIL DRAWINGS.
- **CO-1** - Cork tile flooring SEE SEPARATE DETAIL DRAWINGS.
- **EX-1** Existing carpet flooring Reused / relocated
- Minimal or no works to these areas. Notes shown in red.

FT-1	Transition detail (lift core areas etc.)
FT-2	Main floor trim.
FT-3	Expansion trim to perimeter of timber flooring.
FT-4	Transition trims various - see FS.
FT-5	Partition floor track to doors. No additional flooring transition trim required. See detail Drawing.
FT-6	Diminishing strip from timber to carpet - details TBC
FT-7	Feature Brass transition strip
FT-8	Feature Black transition strip
ST-1	Stair nosing

Rev	Descriptive amendments	Drawn by	Date
G	Flooring revised to nooks & community bar, floor access panels added to WCs	AN	23.09.16
F	Revised to Client's comments WC block revised	GH	19.09.16
E	Revised to Client's "approved with comments" & issue to construction	GP	01.09.16
	Entire drawing updated to new Bulkhead's width of 175mm as per Client's request.	KR/GP	18.08.16
D	Updated to GA Rev__J	AN	09.08.16
C	Revised to building survey & to Client's comments - updated to GA Rev__	GP	03.08.16
B	Revised to building survey & to Client's comments - updated to GA Rev__F	AN/GP	19.07.16

Pre-Design - Construction - As Built

CONSTRUCTION

Client
WeWork

Client Contact

Site Address
03 Waterhouse Square - PHASE 2
Holborn Bars
London

Drawing Title
Ground Floor - Floor Finishes

Account Manager
Rob Gregory

Designer/ Senior Tech, Designer / Project Manager
Claire Elliott / Glenda Puntel / Martin Leeper

Scale	Drawn by	First Drawing Date
1:100@A1	**GP**	**10/06/2016**

Contract Number	Building	Floor	Detail	Revision
1041	**01**	**0G**	**FF**	**G**

ltb.
1st Floor
322 High Holborn
London WC1V 7PB
T: +44 (0)20 7553 9500

NOTES: This drawing is the exclusive Copyright of Ltb and may not be copied or handed to any Third parties without prior consent. All dimensions must be checked on site and not scaled from the drawing. All drawings and proposals are subject to approvals by statutory authorities