## PORFAN —METALWORK LTD—

## 1.0 Description of Works

The design, manufacture, supply and installation of an external staircase with | flights and | platforms at 11 Boscastle Road, NW5 1EE.

We require 50% of the total in advance. The remaining balance must be paid promptly within two weeks of completion.

Description	$\textbf{Cost £}_{\textbf{proposed}}$
Works listed above	£8,800
Additional spring -loaded aluminium section	£2,000
VAT @ 20%	10,500
VAI & 20//	MAT. 12,960 13 m.

## 2.0 Lead Time

These works will take 5-6 weeks to complete from receipt of 50% advance deposit and sign off of designs.

## 3.0 Important Provisions

- to be made of anti-slip, durbar tread
- to include a metre long platform at the top level to allow for door opening outwards
- to include a platform in the centre
- approximately 29 steps in total, risers and going to be determined
- simple handrail and balustrade along one side
- adjustments to be made for existing waste pipe (most likely a break in the stringer)
- to be supplied spray painted black
- client to confirm that a concrete step will be installed at the entrance of the gate so as to lessen the angle of the staircase
- client to inform us when the builder has drilled the hole through the wall so we can get exact measurements
- client to determine whether they require the aluminium spring-loaded section to allow easy access under the staircase