



CEILING FINISHES LEGEND	
Symbols shown are not to scale some symbols may not appear on the layout plan	
C1	Exposed ceiling area
C7	Existing suspended ceiling and plasterboard margins to remain
C2	New MF plasterboard ceiling and bulkhead set at varying heights from finished floor level - see drawings.
C3	New joinery ceiling / metal structure with mesh - see detail drawing
C4-A	Plasterboard margins with full height upstand - refer to detail A.
C4-B	Plasterboard margins with small upstand & light detail - refer to detail B.
C4-C	Plasterboard margins with small upstand - refer to detail C.
	Refer to standard details and joinery detail drawings for meeting rooms, phone booths, seating & print nooks.
C5	Minimal works to these areas. Notes shown in red.
C6	New moisture resistant MF plasterboard ceiling to WC's set at 2700mm AFFL, see detail drawings.
C7	New MF plasterboard ceiling over water dispensers at 2000mm from raised access floor.
C8	New 600x600mm suspended ceiling set at 2700mm AFFL, standard Armstrong Dune fire rated if required.
C9	Existing ceilings to be spray finished subject to cost & landlord approval.
C10	New acoustic panels set at varying heights AFFL, see detail drawings
	Blue lines denote 175mm wide MF bulkhead over glazed partitions to underside of exposed slab - see partition details. Bulkhead will be sprayed in feature colour. Bulkhead will be used as return air path - see details. Height f.f.l to underside of bulkhead set at 2700mm.
C11	New Joinery metal structure with expanded metal & denim acoustic insulation
C12	New MF plasterboard ceiling with cork panels applied directly to it - see drawings.
C13	Camouflaged netting - see drawings.
C14	New timber trellis suspended ceiling

USE IN CONJUNCTION WITH FINISHES SCHEDULE AND DETAIL DRAWINGS & HIGH LEVEL DRAWINGS.

NOTES:
- All subject to high level co-ordination , survey check and lighting, alarm, emergency scheme.
- Access panel locations TBC & coordinated on site.
- All New MF ceilings will be painted to feature colour , please refer to finishes schedule.

B	Revised to SD pack	GH	04.11.16
A	Bulkheads removed	DS	06.10.16
-	Drawing first produced	AN	16.08.16

Rev	Descriptive amendments	Drawn by	Date
Pre-Design - Construction - As Built			
PRE-DESIGN			

Client
WeWork

Client Contact

Site Address
**03 Waterhouse Square - PHASE 3
Holborn Bars
London**

Drawing Title
Fourth Floor - Ceiling Strategy

Account Manager
Rob Gregory

Designer/ Senior Tech. Designer / Project Manager
Claire Elliott / Glenda Puntel / Kane Cummins

Scale
1:100@A1

First Drawing Date
16/08/2016

Contract Number
1076

Building
01

Floor
04

Detail
CL

Revision
B

ltb.
1st Floor
322 High Holborn
London WC1V 7PB
T: +44 (0)20 7553 9500