

APPENDIX A

BS 5837: 2012 TREE SURVEY

Advanced Tree Services

Arboricultural Survey - Definitions

Hgt

Tree Height (height in metres, measured with a clinometer)

SD

Stem diameter at 1.5 metres above ground level (in millimetres)

N-E-S-W

Branch spread taken at four compass points (in metres)

Crown clearance

Height of crown clearance above adjacent ground level (in metres)

Life Stage

Y- Young **SM** - Middle Aged **M** - Mature **OM** - Over Mature **V** - Veteran

P.Cond

Physiological condition **G** - Good **F** - Fair **P** - Poor **D** - Dead

S.Cond

Structural condition - General comment on safety of tree

Radius

Root Protection radius (m)

RPA

Root protection area (m²)

ERC

Estimated remaining contribution in years

Category grading

Trees are categorized in accordance with the cascade chart given as Table 1 in B.S.5837:2012.

A - High quality & value (40 yrs+)

B - Moderate quality & value (20 yrs+)

C - Low quality & value (10 yrs+)

U - Those trees in such a condition that they cannot realistically be retained as living trees in the context of the current land use for longer than 10 years

(NB. Any value suffixed with '#' is an estimated value)

ADVANCED TREE SERVICES

Table 2 - BS 5837:2012 - Trees in Relation to design, demolition and construction - Recommendations - Cascade chart for tree quality assessment

TREES FOR REMOVAL		Criteria		Identification on plan	
Category and definition	<u>Category U</u>	2 Mainly landscape values	3 Mainly cultural values, including conservation	Identification on plan	
Those in such a condition that any existing value would be lost within 10 years and which should in the current context, be removed for reasons of sound arboricultural management	<u>Category U</u>	Trees that have a serious, irremediable, structural defect, such that their early loss is expected due to collapse, including those that will become unviable after removal of other U category trees (i.e. where, for whatever reason, the loss of companion shelter cannot be mitigated by pruning).	Trees that are dead or are showing signs of significant, immediate and irreversible overall decline. Trees infected with pathogens of significance to the health and/or safety of other trees nearby, or very low quality trees suppressing adjacent trees of better quality. NOTE:- Category U trees can have existing or potential conservation value which it might be desirable to preserve.	RED	
TREES TO BE CONSIDERED FOR RETENTION					
Criteria - Subcategories					
Category and definition	<u>Category A</u>	1 Mainly Arboricultural values	2 Mainly landscape values	3 Mainly cultural values, including conservation	Identification on plan
<u>Category A</u>	<u>Category A</u>	Trees that are particularly good examples of their species, especially if rare or unusual, or essential components of groups, or of formal or semi-formal arboricultural features (e.g. the dominant and/or principal trees within an avenue)	Trees, groups or woodlands of particular visual importance as arboricultural and/or landscape features	Trees, groups or woodlands of significant conservation, historical, commemorative or other value (e.g. veteran trees or wood pasture)	GREEN
<u>Category B</u>	<u>Category B</u>	Trees that might be included in category A but are downgraded because of impaired condition (e.g. presence of remediable defects including unsympathetic past management and storm damage), such that are unlikely to be suitable for retention for beyond 40 years; or trees lacking the special quality necessary to merit the category A designation.	Trees present in numbers, usually growing as groups or woodlands, such that they attract a higher collective rating than they might as individuals; or trees occurring as collectives but situated so as to make little visual contribution to the wider locality	Trees with material conservation or other cultural value	BLUE
<u>Category C</u>	<u>Category C</u>	Unremarkable trees of very limited merit or such impaired condition that they do not qualify in higher categories	Trees present in groups or woodlands but without this conferring on them significantly greater collective landscape value and/or trees offering low or only temporary / transient landscape benefits	Trees with no material conservation or other cultural value	GREY


Site: 31 Briardale Gardens NW3 7PN
 Client: Mr M/s Patel
 Date of Survey: 23/05/2014
 Tagged: No
 Surveyor: DB
 Build Stage: Pre-construction
 Weather: Fair

**ADVANCED TREE SERVICES
 TREE SURVEY SCHEDULE**

Tree ID	Species	Height (m)	SD (mm)	Crown Spread (N)	Crown Spread (E)	Crown Spread (S)	Crown Spread (W)	Age Class	P.Cond	Structural Condition	Radius	RPA	Sq.Sides	ERC	Category Grading	Category Criteria	Works required for Proposal
T1	Magnolia	7.5	250	3.8	2	3	3	Mature	Good	Good. Even canopy. No external indications of weakness or decay.	3	28	5	10-20 yrs	B	1	See AMS

APPENDIX B

TREE CONSTRAINTS PLAN



Key



Root Protection Area



Effect of shade



Category B tree

1.0m

Branch Spread (NESW)

T1 - Magnolia



Advanced Tree Services
01483 210066

enquiries@advancedtreeservices.co.uk

Tree Constraints Plan

SCALE :
1 : 100

DATE :
23/05/2014

MAP FILE REFERENCE :
31 Briardale Gdns TCP.mpd



Pear Technology Services Ltd: Email info@peartechtechnology.co.uk
Maps based on Ordnance Survey MasterMap or 1:25000 Mid-scale data with the permission of the Controller of HMSO. © Crown Copyright

APPENDIX C

TREE PROTECTION PLAN

Orange hazard fencing mounted on scaffold poles made fast in the ground

CEZ

1m

T1

Side butting scaffold boards on compressible layer (100mm bark mulch)

Key



Tree to be retained



Ground protection measures



Outline of proposed extension



Orange hazard fencing



Timber hoarding



Advanced Tree Services
01483 210066

enquiries@advancedtreeservices.co.uk

Tree Protection Plan

SCALE :
1 : 100

DATE :
27/05/2014

MAP FILE REFERENCE :
31 Briardale Gdns TPP.mpd

Pear Technology Services Ltd: Email info@peartechology.co.uk
Maps based on Ordnance Survey MasterMap or 1:25000 Mid-scale data with the permission of the Controller of HMSO. © Crown Copyright



APPENDIX D

SITE PHOTOGRAPHS

31 Briardale Gardens (23.05.14)



T1 - Magnolia



T1 in relation to the rear of property

31 Briardale Gardens (23.05.14)



T1 - Magnolia

APPENDIX E

SITE INSPECTION CHECKLIST



BS 5837:2012 – Trees in Relation to Design, Demolition and Construction – Recommendations

ARBORICULTURAL SITE SUPERVISION - SUMMARY

1. Once retained as Arboricultural Consultants for a specific development site, all site monitoring will be undertaken by a suitably qualified and experienced Arboriculturalist.
2. Our Arboriculturalist will be present throughout the key operations to ensure compliance with the Arboricultural Method Statement and Tree Protection Plan. Key operational points will be agreed in writing with the client and LPA prior to commencement of works. Typically these will include;
 - Remedial tree works
 - Installation of protective measures (fences and ground)
 - Installation of site facilities
 - Demolition works
 - Installation of services
 - Landscaping within RPA's
 - Site completion
3. Monitoring will be undertaken on a fortnightly basis as well as ongoing communications with the Client, Site Manager and LPA. A checklist will be completed (*appendix a*) and a copy will be retained by the Site Manager with a copy sent to the LPA.
4. Monitoring visits will generally be unannounced. Upon arrival the Arboriculturalist will check in at the site office and inspect the tree protection measures in conjunction with the Site Manager. The Arboriculturalist will also visit the site at pre-determined dates to view specific operational issues (see above).
5. Any defects requiring attention will be notified to the Site Manager and Client (copied to the LPA by e-mail). Any emergencies will be notified to the Client and LPA by phone.
6. Day to day site supervision will be the responsibility of the Site Manager. They will be aware of the tree protection measures and significant steps in the development process which have arboricultural implications. To ensure compliance the Site Manager will undertake a site briefing with the retained Arboriculturalist before the commencement of works.
7. A final sign off visit will be carried out at the end of the development and a formal letter sent both to the client and the LPA to indicate the end of the monitoring period.



Arboricultural Monitoring Report Sheet

(BS 5837:2012 Trees in Relation to Design, Demolition and Construction - Recommendations)

Client		Planning Ref:	
Planning Authority		Date of inspection	

Site Address	
---------------------	--

Site Checklist	
Protective fencing in place	
Protective fencing to specification	
Ground protection in place (if applicable)	
Site Foreman briefed	
Tree(s) damaged?	
Remedial works required	

General Comments:

Recommendations:

Report sent to LPA:

Inspection by:




APPENDIX F
TRIAL PIT LOCATION

Site Analytical Services Ltd.

Site
31 BRIARDALE GARDENS, LONDON, NW3 7PN

Trial Pit Number
TT1


Excavation Method HAND EXCAVATION	Dimensions 2000mm (L) x 250mm (W) x 1000mm (D)	Ground Level (mOD)	Client MR AND MRS PATEL	Job Number 1422633
	Location TQ 251 861	Dates 01/12/2014	Engineer MANN WILLIAMS STRUCTURAL ENGINEERS	Sheet 1/1

Depth (m)	Sample / Tests	Water Depth (m)	Field Records	Level (mOD)	Depth (m) (Thickness)	Description	Legend	Water
0.25	D1				0.04	MADE GROUND : Crazy paving		
0.25	R1				0.06	MADE GROUND : Sand		
0.50	D2				(0.94)	MADE GROUND : Brown silty sandy clay with brick fragments and roots up to 20mm in diameter located sporadically within strata		
0.50	R2							
0.75	D3							
1.00	D4		01/12/2014:DRY		1.00	Complete at 1.00m		

Plan .	Remarks D = Disturbed Sample R = Root Sample Groundwater was not encountered during the excavation		
	<table border="1"> <tr> <td>Scale (approx) 1:50</td> <td>Logged By APS</td> <td>Figure No. 1422633.TT1</td> </tr> </table>	Scale (approx) 1:50	Logged By APS
Scale (approx) 1:50	Logged By APS	Figure No. 1422633.TT1	

Site Analytical Services Ltd.

Site 31 BRIARDALE GARDENS, LONDON, NW3 7PN	Trial Pit Number TT1
Method Trial Pit	Dimensions 2000mm (L) x 250mm (W) x 1000mm (D)
Ground Level (mOD)	Client MR AND MRS PATEL
Orientation	Location TQ 251 861
Dates 01/12/2014	Engineer MANN WILLIAMS STRUCTURAL ENGINEERS
Job Number 1422633	Sheet 1/1



Strata			Samples and Tests		
Depth (m)	No.	Description	Depth (m)	Type	Field Records
0.00-0.04	1	MADE GROUND : Crazy paving			
0.04-0.06	2	MADE GROUND : Sand			
0.06-1.00	3	MADE GROUND : Brown silty sandy clay with brick fragments and roots up to 20mm in diameter located sporadically within strata	0.25 0.25 0.50 0.50 0.75 1.00	D1 R1 D2 R2 D3 D4	
			Excavation Method: HAND EXCAVATION Shoring / Support: N/A Stability: Good Backfill: Arisings		

Remarks
D = Disturbed Sample
R = Root Sample
Groundwater was not encountered during the excavation

Logged By : APS
Checked By : APS
Figure No. : 1422633.TT1