

General Notes

H8 U bars.

PRINCIPLES.

- Drawings shall be referred to for structural work only unless otherwise stated and read in conjuction with Architect's, Service Engineer's and Sub-Contractor's drawings.
- 2. The Contractor shall check all levels and dimensions, any errors or omissions are to be reported at once to the Engineer.
- 3. Existing layouts and levels based upon Murphy's surveys information received to date (February 2016)
- 4. For Key and Member Schedules refer to drawing no. 9100-DRG-99YY-
- 5. For General Notes refer to drawing no. 9100-DRG-99YY-

FOR BUILDERSWORK HOLES ASSOCIATED WITH NEW SERVICES REFER TO M & E DRAWINGS.

NOTE
ALL SERVICES SIZES AND POSITIONS ARE TO BE CONFIRMED BY THE ARCHITECT/M&E CONSULTANT PRIOR TO CONSTRUCTION.

NOTE
Reinforcement Estimate for Ground Bearing Slab:22kg/m² using A.393 mesh reinforcement and

REFER TO DRG No. 9100-DRG-00YY-DE007 FOR GROUND BEARING SLAB REINFORCEMENT

ISSUED FOR CONSTRUCTION OF UNDERPINNING WORKS ONLY

B 24.08.16 Issued for Construction of underpinning works DA TP only. Reinforcement estimate note revised. A 22.06.16 Underpinning sequence added. Repair Schedule, notes and locations added. Key and DA AT lintel schedules removed. General notes

BY CHK'D

First Issue. REV DATE DESCRIPTION

NOTE
Refer to General Notes Drawing
9100-DRG-99YY-GN002 for underpinning specification.

NUMBERS BY UNDERPINNING SECTIONS DENOTE SEQUENCE OF UNDERPINNING

ASSUMED IN THE DESIGN. THE CONTRACTOR

IS TO PREPARE HIS OWN PROPOSALS FOR SEQUENCING THE WORKS AND PREPARE A METHOD STATEMENT, FOR WHICH THEY SHALL REMAIN ENTIRELY RESPONSIBLE.

to assess the condition of the existing structure to be underpinning prior to confirming their proposed sequence of works. Where the masonry structure is in a poor condition, such as where cracks exist in the brickwork, the contractor shall highlight this to the Engineer. Allowance should be made for making good cracked masonry prior to commencing

There is potential for the underpinning works to cause disturbance to structure over. Allowance to be made in the programme for making good cracks

PRIOR TO NEW OPENINGS IN WALLS BEING

IN NO INSTANCE SHOULD ANY SERVICE TRENCHES BE FORMED WHICH MAY UNDERMINE EXISTING OR UNDERPINNED

PROVISIONAL REPAIR ALLOWANCES SHOWN

ON THIS DRAWING RELATE TO BOTH THE

SOUTHERN AND NORTHERN PORTIONS OF

EACH AREA AND REMOVAL OF STUD WALL

PLASTER FINISHES WHERE WALL IS TO BE

REMOVED. ENGINEER TO INSPECT EACH FLOOR IN TURN AND CONFIRM EXTENT OF

for underpinning. Trial pit to be dug at each

shown and trial holes and logs prepared to be reviewed by Structural Engineer to confirm this and

underpin location 1 within sequence of underpinning

THE BUILDING AT THIS LEVEL THE ALLOWANCES WILL BE CONFIRMED

REPAIRS REQUIRED.

drawings updated accordingly.

which may appear in the structure once underpinning works has been completed.

underpinning.

FORMED.

FOOTINGS.

NOTE REFER TO DRG No. 9100-DRG-00YY-DE007 FOR GROUND BEARING SLAB REINFORCEMENT PRINCIPLES.

CONSTRUCTION

Maynard Wing Level LG Proposed Floor Plan Sheet 1 of 2

Project No. 11581 Kidderpore Avenue

SCALE: A1@ 1-50 DATE: March '16 DRAWN: DA CHK'D: TP

9100-DRG-03MW-LG001

consultants

Engineering at its Best

T: 01342 828 000 E: info@tullydeath.com W: www.tullydeath.com