

NOTES

DO NOT SCALE DIMENSIONS OFF THIS DRAWING
CHECK ALL DIMENSIONS ON SITE BEFORE FABRICATION
REPORT ALL ERRORS OR OMISSIONS TO SPRUNT LIMITED
ANY DISCREPANCY TO BE VERIFIED WITH SPRUNT LIMITED BEFORE
PROCEEDING WITH THE WORKS
THIS DRAWING IS PROTECTED UNDER COPYRIGHT AND
SHALL NOT BE REPRODUCED IN PART OR WHOLE WITHOUT PRIOR
EXPRESSED PERMISSION OF SPRUNT LIMITED

CDM 2015

ALL CURRENT DRAWINGS AND SPECIFICATIONS FOR THE
PROJECT MUST BE READ IN CONJUNCTION WITH THE
DESIGNER'S HAZARD AND ENVIRONMENT ASSESSMENT
RECORD

1. 25mm RIGID INSULATION AS PER SPEC. P10/240A
2. TIMBER SKIRTING BOARD WITH 10mm SHADOW GAP AS PER SPEC. P20
3. 75mm SCREED WITH UNDERFLOOR HEATING AS PER SPEC. M10/115A
4. VAPOUR CONTROL BARRIER AS PER SPEC. P10/310
5. 150mm RIGID FLOOR INSULATION AS PER SPEC. P10/240A
6. SELF ADHESIVE DPM MEMBRANE AS PER SPEC. J40/190
7. WINDOW/ CW AS PER SPEC. L10/H11
8. FULL BRICK RETURN
9. ACO DRAIN AS PER SPEC. R10
10. EXTERNAL PAVER AS PERS SPEC.
11. 120mm EXTRUDED POLYSTYRENE AS PER SPEC. F30/150B
12. LEAN MIX FILLET@ 105.5mm CAVITY
13. 105mm BRICKWORK AS PER SPEC. F10/110
14. EPDM AS PER WINDOW MANUFACTURER SPEC.
15. CONCRETE SLAB AS PER S.E. DESIGN AND SPEC.
16. 75x150mm CONTINUOUS STEEL ANGLE FIXED TO THE TOPOF UPSTAND AS PER SPEC. Z11
17. 100x100mm CONTINUOUS STEEL ANGLE FIXED TO THE SIDE OF UPSTAND AS PER SPEC. Z11
18. 30x30mm CONTINUOUS STEEL ANGLE TO FIX THE THRESHOLD AS PER SPEC. Z11
19. DPM - PILE CAP SEALER AS PER SPEC. J40/120A
20. PRE APPLIED DPM MEMBRANE AS PER SPEC. J40/120A
21. 50mm SMOOTH CONCRETE BLINDING AS PER SPEC. J40/120A
22. PRECAST CONCRETE THRESHOLD AS PER SPEC. F30
23. 50x50mm CONCRETE FILLET
24. 300mm SELF- ADHESIVE MEMBRANE TO REINFORCE ABUTMENTS AS PER SPEC. J40/140
25. PROTECTION BOARD
26. 15mm PLASTERBOARD AS PER SPEC. K10/205K
27. CAVITY CLOSER AS PER SPEC. F30/180
28. BREATHER MEMBRANE AS PER SPEC. P10/320
29. BRICK SLIP LINTEL AS PER SPEC. F30/755B AND PER S.E. SCHEDULE
30. WEEP HOLE AS PER SPEC. F30
31. CAVITY TRAY AS PER SPEC. F30/345A
32. 120mm FULL FILL INSULATION AS PER SPEC. F30/155
33. EPDM MEMBRANE AS PER WINDOW MANUFACTURER
34. 100mm BLOCKWORK AS PER SPEC. F10/355
35. CONCRETE UP-STAND AS PER S.E. DESIGN
36. SILICONE MASTIC AS PER WINDOW MANUFACTURER SPEC.
37. STEEL WINDOW LINTEL AS PER SPEC. F30/755C AND PER S.E. SCHEDULE
38. WALL TIE AS PER SPEC. F30/211

