

	EXTERNAL SERVICES					INTERNAL SERVICES							
	RAINWATER GOODS	VENTS	FLUES	EXTRACTS	OTHER	VENTS	FLUES	EXTRACTS	CABLING	HEATING	SERVICE CUPBOARDS	RISERS	OTHER
DESCRIPTION	Rainwater pipe positions retained. RWP's renewed in black painted cast iron to match existing where original. New C1 RWP's and hopper to extension to positions as shown.	Existing terracotta and C1 vents retained.	No flues are required.	New black painted Cast Iron Air Bricks added to serve mechanical extract system.	Redundant external SVP's removed. All new services for data, satellite, TV, etc, brought in below ground in ducts. SVP's are terminated in an inline slate vent not visible above the pitch line.	Mechanical ventilation ductwork to run above new false ceilings, or behind new wall linings.	No flues are required.	Extract grilles in new false ceilings to sanitary accommodation, and utility areas, ducted to mechanical ventilation.	Cables to be run behind new wall lining clipped to existing; above false ceilings; or within floor construction. Where no new linings, chase in existing brick walls and plaster made good.	Radiators to be Victorian segmental type. Heating pipework run behind new wall linings; in new partitions; above false ceilings etc. Where depth of wall lining insufficient, partially chase existing brick wall behind. Pipework fixed to existing walls. Underfloor heating to main areas of lower ground and ground floor, within new floor build-up. First floor within new screed to existing concrete floor, replacing existing damaged boards and battens.	Service intake and plant in new service cupboard iwn lower ground floor	Services rise from intake cupboard to serve all floors in combination of new risers through existing floors and behind wall boxing.	All SVP's and waste pipes are boxed in as part of new linings. Builders work holes formed in existing floors for vertical service runs (SVP's, Risers, etc)
DRAWINGS	9000-DRG-03SK-LG010 9000-DRG-03SK-GF010 9000-DRG-03SK-01010 9000-DRG-03SK-MZ010 9000-DRG-03SK-02010 9000-DRG-03SK-RF010 9000-DRG-04SK-SE001 9000-DRG-04SK-SE002 9000-DRG-02SK-EL001 9000-DRG-02SK-EL002 9000-DRG-02SK-EL003 9000-DRG-00GN-AL040	9000-DRG-02SK-EL001 9000-DRG-02SK-EL002 9000-DRG-02SK-EL003	-	9100-DRG-02SK-EL001 9100-DRG-02SK-EL002 9100-DRG-02SK-EL003 9100-DRG-00GN-AL040 9100-DRG-00GN-DE022	9000-DRG-03SK-LG010 9000-DRG-03SK-GF010 9000-DRG-03SK-01010 9000-DRG-03SK-MZ010 9000-DRG-03SK-02010 9000-DRG-00GN-DE023	9000-DRG-03SK-LG010 9000-DRG-03SK-GF010 9000-DRG-03SK-01010 9000-DRG-03SK-MZ010 9000-DRG-03SK-02010 9000-DRG-04SK-SE001 9000-DRG-04SK-SE002	-	9000-DRG-03SK-LG010 9000-DRG-03SK-GF010 9000-DRG-03SK-01010 9000-DRG-03SK-MZ010 9000-DRG-03SK-02010 9000-DRG-04SK-SE001 9000-DRG-04SK-SE002	9000-DRG-23SK-LG010 9000-DRG-23SK-GF010 9000-DRG-23SK-01010 9000-DRG-23SK-MZ010 9000-DRG-23SK-02010 9000-DRG-04SK-SE001 9000-DRG-04SK-SE001	9000-DRG-03SK-LG010 9000-DRG-03SK-GF010 9000-DRG-03SK-01010 9000-DRG-03SK-MZ010 9000-DRG-03SK-02010	9000-DRG-03SK-LG010	9000-DRG-03SK-LG010 9000-DRG-03SK-GF010 9000-DRG-03SK-01010 9000-DRG-03SK-MZ010 9000-DRG-03SK-02010	9000-DRG-03SK-LG010 9000-DRG-03SK-GF010 9000-DRG-03SK-01010 9000-DRG-03SK-MZ010 9000-DRG-03SK-02010