


GATE A1 - Folding


Dimensions : 7500(W) x 2400(H)



01 Gates Key Plan 1/1000



02 Gate A1 Elevation 1/25



03 Gate A1 Plan 1/25

KEY

T0118/12/15Issued for ERs

REV	DATE	DESCRIPTION
-----	------	-------------

CONSULTANTS	
CLIENT:	Stanley Sidings
CONTRACTOR:	Mace
STRUCTURAL ENGINEER:	Walsh Group
MECHANICAL ENGINEER:	Hoare Lea
COST CONSULTANT:	Gardiner & Theobald
PROJECT MANAGER:	Gardiner & Theobald
ACOUSTIC CONSULTANT:	Arup
TRANSPORT CONSULTANT:	Arup
PLANNING CONSULTANT:	Gerald Eve
LANDSCAPE ARCHITECT:	Fabrik
CDM CO-ORDINATOR:	MSA Safety

NOTE

1. Do not scale from this drawing.

2. All dimensions to be checked on site by the contractor and such dimensions to be his responsibility.
Report all drawing errors, omissions and discrepancies to the architect.

3. This document may be issued in an uncontrolled CAD format to enable others to use it as background information to make alterations and/or additions. In that instance the file will be accompanied by a PDF version. It is for those making such alterations and additions to ensure that they make use of current background information.

4. AHMM Ltd accepts no liability for any such alterations or additions to the background information or arising out of changes to background information which occur prior to alterations of additions being made.

Note

All gates to meet accessibility requirements for widths and opening force

All gates within residential circulation routes to be provided with fob access and handles to permit free escape from inside

Handles / mechanisms etc.to be suitable for use by people with limited strength and dexterity

Opening / closing force to be within 30N or gate will require automatic opening

All door casing assemblies to be tamper proof and external hinges to be provided with welded cover plates to prevent climbing

Emergency escape sign and statutory signage to be provided to gates within door casing zone

Gate lettering design is indicative only - design TBC

The height of the gates will be reviewed during Stage E to ensure coordination with transom heights of adjacent buildings

LOCATION

ALFORD HALL MONAGHAN MORRIS

ARCHITECTS Ltd

5-23 OLD STREET, LONDON, EC1V 9HL

TEL 020 7251 5261 FAX 020 7251 5123 WEB WWW.AHMM.CO.UK

job title

Camden Lock Village

drawing title / location

Gate A1

drawn by	checked	scale	status
FG	AH	As indicated @ A1	ERs Issue

project	drawing no.	revision
14045	MX_(67)_1112	T01