

VO 23 - COURTYARD ELEVATION REPAIRS

ITEM	ELEVATION	DESCRIPTION OF WORK AREA	LENGTH	DEPTH	HEIGHT	REPAIR	CODE	RATING	LENGTH	DEPTH	HEIGHT	NO	QTY
Courtyard facing Russell Square													
1		Repoint under parapet full length of elevation				Repoint	RR	R					38.000
2		Repoint lead flashing to full length of elevation				Repoint	RR	R					38.000
3		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					2.000
4		Replace damaged brick and repoint around it.				Replace brick	B:ID	R					1.000
5		Replace coping section with new Portland Stone Coping				Replace coping	ID	R					0.000
6		Replace coping section with new Portland Stone Coping				Replace coping	ID	R					0.000
7		Replace coping section with new Portland Stone Coping also repair dislodged brick under coping				Replace coping and brick repair	ID, MR	R					0.000
8		Replace coping section with new Portland Stone Coping also replace 1 no damaged brick under coping				Replace coping and brick repair	ID, MR	R					0.000
9		Replace coping section with new Portland Stone Coping				Replace coping	ID	R				1	1.000
10		Repoint approx. 5 m2 of wall				Repoint	RR	R	5.000		1.000	1	5.000
11		Repoint approx. 2 m2 of wall				Repoint	RR	R	2.000		1.000	1	2.000
12		Repoint perpend				Repoint	RR	R					4.000
13		Repair stone and point around.				Mortar repair and repoint	MR, RR	R	0.400	0.200	0.500		0.040
14		Repoint approx. 4 m2 of wall				Repoint	RR	R	4.000		1.000	1	4.000
15		Remove redundant cables complete and make good all fixing holes to all levels.				Remove cables and fixings, mortar repair	RF, MR	R					18.000
16		Repoint approx. 2 m2 of wall				Repoint	RR	R	2.000		1.000	1	2.000
17		Replace coping section with new Portland Stone Coping				Replace coping	ID	R					0.000
18		Repoint approx. 10 m2 of wall. Top five courses of parapet.				Repoint	RR	R	10.000		1.000	1	10.000
19		Replace coping section with new Portland Stone Coping				Replace coping	ID	R					0.000
20		Replace failed brick with new glazed brick to match existing.				Replace brick	B:ID	R					1.000
21		Replace coping section with new Portland Stone Coping				Replace coping	ID	R					0.000

ITEM	ELEVATION	DESCRIPTION OF WORK AREA	LENGTH	DEPTH	HEIGHT	REPAIR	CODE	RATING	LENGTH	DEPTH	HEIGHT	NO	QTY
22		Replace coping section with new Portland Stone Coping to masard coping.				Replace coping	ID	R	0.5	0.9	0.2		0.090
23		Abrasive clean Portland Stone detail full length of elevation.				Abrasive clean portland detail, 5" spinner variable speed							1.000
24		Repair redundant scaffold fixing.				Remove fixings and mortar repair	RF	R	0.050		0.050		2.000
25		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R	0.050		0.050		4.000
26		Repoint Arch over window.				Repoint	RR	R					1.000
27		Replace rendered bricks with new glazed bricks to match main elevation brickwork.				Replace brick	B:ID	R					1.000
28		Remove redundant air grille and patch hole with new glazed bricks to match existing main elevation brickwork.				Remove grille and indent with brick	B:ID	R					1.000
29		Remove fixings and make good.				Changed to:Replace 1 No brick	B	R					1.000
30		Replace rendered bricks with new glazed bricks to match main elevation brickwork. Also repair scaffold fixing.				Replace bricks, remove fixing and mortar repair	B:ID, RF and MR	R					1.000
31		Replace rendered bricks with new glazed bricks to match main elevation brickwork.				Replace brick	B:ID	R					1.000
32		Repoint Arch over window.				Repoint	RR	R					1.000
33		Repair redundant scaffold fixing.				Remove fixings and mortar repair	RF, MR	R					1.000
34		Repoint approx. 1 m2 of wall				Repoint	RR	R	1.000		1.000	1	1.000
35		Repair redundant scaffold fixing.				Remove fixings and mortar repair	RF, MR	R					1.000
36		Repair redundant scaffold fixings.				Remove fixings and mortar repair	RF, MR	R					2.000
37		Repair redundant scaffold fixing.				Remove fixings and mortar repair	RF, MR	R					1.000
38		Repoint approx. 4 m2 of wall				Repoint	RR	R					4.000
39		Repoint Arch over window.				Repoint	RR	R					1.000
40		Repair redundant scaffold fixing.				Remove fixings and mortar repair	RF, MR	R					1.000
41		Repair redundant scaffold fixing.				Remove fixings and mortar repair	RF, MR	R					1.000
42		Repoint Arch over window.				Repoint	RR	R					1.000
43		Carry out repairs to split window cill, return cill to original profile.				Pin and resin and Mortar Repair	PR, MR	R					1.000

ITEM	ELEVATION	DESCRIPTION OF WORK AREA	LENGTH	DEPTH	HEIGHT	REPAIR	CODE	RATING	LENGTH	DEPTH	HEIGHT	NO	QTY
44		Repair redundant scaffold fixing.				Remove fixings and mortar repair	RF, MR	R	0.500		,50		1.000
45		Repair redundant scaffold fixing. Also remove and make good timber plug.				Remove fixings and mortar repair	RF, MR	R					5.000
46		Repair redundant scaffold fixings. Also remove and make good timber plug.				Remove fixings and mortar repair	RF, MR	R					7.000
47		Repair redundant scaffold fixing.				Remove fixings and mortar repair	RF, MR	R					1.000
48		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					4.000
49		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					4.000
50		Replace rendered bricks with new glazed bricks to match main elevation brickwork.				Replace brick	B:ID	R					4.000
51		Remove redundant air grille and patch hole with new glazed bricks to match existing main elevation brickwork.				Remove grille and indent with brick	B:ID	R					4.000
52		Replace rendered brick with new glazed brick to match main elevation brickwork.				Replace brick	B:ID	R					1.000
53		Repair redundant scaffold fixing.				Remove fixings and mortar repair	RF, MR	R					1.000
54		Repoint Arch over window and 1 m2 of brickwork above.				Repoint	RR	R					1.000
55		Repoint Arch over window and 1 m2 of brickwork above.				Repoint	RR	R					1.000
56		Repair redundant scaffold fixing.				Remove fixings and mortar repair	RF, MR	R					1.000
57		Repoint Arch over window and 1 m2 of brickwork above.				Repoint	RR	R					1.000
58		Repoint Arch over window and 1 m2 of brickwork above.				Repoint	RR	R					1.000
59		Repair redundant scaffold fixing.				Remove fixings and mortar repair	RF, MR	R					1.000
60		Repoint Arch over window and 1 m2 of brickwork above.				Repoint	RR	R					1.000
61		Repoint Arch over window and 1 m2 of brickwork above.				Repoint	RR	R					1.000
62		Repair redundant scaffold fixing.				Remove fixings and mortar repair	RF, MR	R					1.000
63		Repoint entire pier between adjacent windows.				Repoint	RR	R					1.000
64		Repoint wall approx 3 m2.				Repoint	RR	R	3.000		1.000	1	3.000
65		Repair redundant scaffold fixing.				Remove fixings and mortar repair	RF, MR	R					17.000

ITEM	ELEVATION	DESCRIPTION OF WORK AREA	LENGTH	DEPTH	HEIGHT	REPAIR	CODE	RATING	LENGTH	DEPTH	HEIGHT	NO	QTY
66		Repair redundant scaffold fixing.				Remove fixings and mortar repair	RF, MR	R					1.000
67		Repoint Arch over window and 1 m2 of brickwork above.				Repoint	RR	R					1.000
68		Repoint Arch over window and 2 m2 of brickwork above.				Repoint	RR	R					2.000
69		Repair redundant scaffold fixings.				Remove fixings and mortar repair	RF, MR	R					2.000
70		Repoint wall approx 5 m2.				Repoint	RR	R	5.000		1.000	1	5.000
71		Repoint Arch over window and 2 m2 of brickwork above.				Repoint	RR	R					2.000
72		Repoint Arch over window and 2 m2 of brickwork above.				Repoint	RR	R					2.000
73		Repair redundant scaffold fixing.				Remove fixings and mortar repair	RF, MR	R					1.000
74		Repoint Arch over window and 1 m2 of brickwork above.				Repoint	RR	R					1.000
75		Repoint Arch over window and 1 m2 of brickwork above.				Repoint	RR	R					1.000
76		Repair redundant scaffold fixing.				Remove fixings and mortar repair	RF, MR	R					1.000
77		Repair redundant scaffold fixing.				Remove fixings and mortar repair	RF, MR	R					1.000
78		Repair redundant scaffold fixing.				Remove fixings and mortar repair	RF, MR	R					1.000
79		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					3.000
80		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					3.000
81		Repoint Arch over window and 1 m2 of brickwork above.				Repoint	RR	R					1.000
82		Remove redundant air grille and patch hole with new glazed bricks to match existing main elevation brickwork.				Remove grille and indent with brick	B:ID	R					4.000
83		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					4.000
84		Repoint wall approx 1 m2.				Repoint	RR	R	1.000		1.000	1	1.000
85		Repoint Arch over window.				Repoint	RR	R					1.000
86		Repoint Arch over window and 2 m2 of brickwork above.				Repoint	RR	R					2.000
87		Repoint Arch over window and 1 m2 of brickwork above.				Repoint	RR	R					1.000
88		Repoint Arch over window and 1 m2 of brickwork above.				Repoint	RR	R					1.000
89		Repair redundant scaffold fixing.				Remove fixings and mortar repair	RF, MR	R					16.000
90		Repair redundant scaffold fixing.				Remove fixings and mortar repair	RF, MR	R					1.000
91		Repair redundant scaffold fixing.				Remove fixings and mortar repair	RF, MR	R					1.000

ITEM	ELEVATION	DESCRIPTION OF WORK AREA	LENGTH	DEPTH	HEIGHT	REPAIR	CODE	RATING	LENGTH	DEPTH	HEIGHT	NO	QTY
92		Remove cable clips and make mortar good.				Remove fixings and repoint	RF, RR	R					2.000
93		Repoint Arch over window and 1 m2 of brickwork above.				Repoint	RR	R					1.000
94		Repoint Arch over window and 2 m2 of brickwork above.				Repoint	RR	R					2.000
95		Remove cable clips and make mortar good.				Remove fixings and repoint	RF, RR	R					4.000
96		Repoint Arch over window and 2 m2 of brickwork above.				Repoint	RR	R					2.000
97		Repoint Arch over window and 2 m2 of brickwork above.				Repoint	RR	R					2.000
98		Repoint wall approx 3 m2.				Repoint	RR	R	3.000		1.000	1	3.000
99		Replace rendered brick with new glazed brick to match main elevation brickwork.				Replace brick	B:ID	R					1.000
100		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					4.000
101		Repair redundant scaffold fixing.				Remove fixings and mortar repair	RF, MR	R					1.000
102		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					4.000
103		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					4.000
104		Repoint wall approx 6 m2.				Repoint	RR	R	6.000		1.000	1	6.000
105		Replace rendered brick with new glazed brick to match main elevation brickwork.				Replace brick	B:ID	R					12.000
106		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					8.000
107		Repair redundant scaffold fixing.				Remove fixings and mortar repair	RF, MR	R					1.000
108		Repair redundant scaffold fixing.				Remove fixings and mortar repair	RF, MR	R					1.000
109		Repoint wall approx 6 m2.				Repoint	RR	R	6.000		1.000	1	6.000
110		Repoint entire pier between adjacent windows.				Repoint	RR	R					2.000
111		Repair redundant scaffold fixing.				Remove fixings and mortar repair	RF, MR	R					1.000
112		Repoint wall approx 6 m2.				Repoint	RR	R	6.000		1.000	1	6.000
113		Repoint entire pier between adjacent windows.				Repoint	RR	R					2.000
114		Repoint wall approx 4 m2.				Repoint	RR	R	4.000		1.000	1	4.000
115		Repoint Arch over window and 3 m2 of brickwork above.				Repoint	RR	R					3.000
116		Repoint Arch over window and 2 m2 of brickwork above.				Repoint	RR	R					2.000
Courtyard facing Herbrand Street													
117		Repair redundant scaffold fixing.				Remove fixings and mortar repair	RF, MR	R					2.000
118		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					12.000

ITEM	ELEVATION	DESCRIPTION OF WORK AREA	LENGTH	DEPTH	HEIGHT	REPAIR	CODE	RATING	LENGTH	DEPTH	HEIGHT	NO	QTY
119		Repair redundant scaffold fixing.				Remove fixings and mortar repair	RF, MR	R					1.000
120		Repoint wall approx 1 m2.				Repoint	RR	R	1.000		1.000	1	1.000
121		Repoint wall approx 3 m2.				Repoint	RR	R	3.000		1.000	1	3.000
122		Repair redundant scaffold fixing.				Remove fixings and mortar repair	RF, MR	R					1.000
123		Repoint entire pier between adjacent windows.				Repoint	RR	R					1.200
124		Repoint wall approx 5 m2.				Repoint	RR	R	5.000		1.000	1	5.000
125		Repair redundant scaffold fixing.				Remove fixings and mortar repair	RF, MR	R					1.000
126		Repoint entire pier between adjacent windows.				Repoint	RR	R					1.200
127		Repoint wall approx 4 m2.				Repoint	RR	R	4.000		1.000	1	4.000
128		Repair redundant scaffold fixing.				Remove fixings and mortar repair	RF, MR	R					2.000
129		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					2.000
130		Carry out repairs to split window cill, return cill to original profile.				Pin and resin and Mortar Repair	PR, MR	R					1.000
131		Carry out repairs to split window cill, return cill to original profile.				Pin and resin and Mortar Repair	PR, MR	R					1.000
132		Carry out repairs to stone blocks, return to original profile. Repoint around stone detail.				Mortar Repair, repoint	MR, RR	R					1.000
133		Repoint entire gable down to scaffold level.				Repoint	RR	R					2.000
134		Carry out repairs to stone blocks, return to original profile. Repoint around stone detail.				Mortar Repair, repoint	MR, RR	R					1.000
135		Carry out further abrasive cleaning to window surround. Paint grille with new gloss paint finish.				Abrasive clean surround, 5" spinner variable speed, paint grille		R					1.000
136		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					4.000
425		Remove redundant pipework and make good wall with replacement bricks.				Remove pipe and indent with brick	B:ID	R					4.000
426		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R	0.100		0.100		2.000
427		Carry out further abrasive cleaning to window surround. Paint grille with new gloss paint finish.				Abrasive clean surround, 5" spinner variable speed, paint grille		R					1.000
428		Repoint under coping stones for full length of elevation.				Repoint	RR	R					6.000
429		Repoint Arch over window.				Repoint	RR	R					1.000

ITEM	ELEVATION	DESCRIPTION OF WORK AREA	LENGTH	DEPTH	HEIGHT	REPAIR	CODE	RATING	LENGTH	DEPTH	HEIGHT	NO	QTY
430		Repoint wall approx 2 m2. Refix rainwater goods.				Repoint, refix rainwater goods	RR	R	2.000		1.000	1	2.000
431		Repoint wall approx 3 m2.				Repoint	RR	R	3.000		1.000	1	3.000
432		Repoint wall approx 3 m2.				Repoint	RR	R	3.000		1.000	1	3.000
433		Repoint wall approx 5 m2.				Repoint	RR	R	5.000		1.000	1	5.000
434		Repoint wall approx 5 m2.				Repoint	RR	R	5.000		1.000	1	5.000
449		Repoint wall approx 5 m2.				Repoint	RR	R	5.000		1.000	1	5.000
450		Repoint wall approx 2 m2.				Repoint	RR	R	2.000		1.000	1	2.000
451		Repoint flashing for the entire length of elevation.				Repoint	RR	R					0.000
452		Repoint wall approx 2 m2.				Repoint	RR	R	2.000		1.000	1	2.000
453		Repoint Arch over window.				Repoint	RR	R					1.000
454		Repoint Arch over window.				Repoint	RR	R					1.000
455		Repoint wall approx 4 m2.				Repoint	RR	R	4.000		1.000	1	4.000
456		Repoint wall approx 3 m2.				Repoint	RR	R	3.000		1.000	1	3.000
457		Repoint Arch over window.				Repoint	RR	R					1.000
458		Repoint wall approx 5 m2.				Repoint	RR	R	5.000		1.000	1	5.000
459		Repoint wall approx 5 m2.				Repoint	RR	R	5.000		1.000	1	5.000
460		Refix existing pipework				Refix existing pipework		R					0.000
461		Refix existing pipework				Refix existing pipework		R					0.000
462		Repoint wall approx 2 m2.				Repoint	RR	R	2.000		1.000	1	2.000
463		Repoint wall approx 1 m2.				Repoint	RR	R	1.000		1.000	1	1.000
464		Repoint wall approx 1 m2.				Repoint	RR	R	1.000		1.000	1	1.000
465		Refix existing pipework				Refix existing pipework		R					0.000
466		Repair redundant scaffold fixing.				Remove fixings and mortar repair	RF, MR	R					1.000
467		Repoint Arch over window.				Repoint	RR	R					1.000
468		Repoint wall approx 2 m2.				Repoint	RR	R	2.000		1.000	1	2.000
469		Repoint wall approx 2 m2.				Repoint	RR	R	2.000		1.000	1	2.000
470		Repoint Arch over window.				Repoint	RR	R					1.000
471		Repoint wall approx 2 m2.				Repoint	RR	R	2.000		1.000	1	2.000
472		Repoint Arch over window.				Repoint	RR	R					1.000
473		Repoint wall approx 2 m2.				Repoint	RR	R	2.000		1.000	1	2.000
474		Repoint wall approx 2 m2.				Repoint	RR	R	2.000		1.000	1	2.000
475		Repoint wall approx 2 m2.				Repoint	RR	R	2.000		1.000	1	2.000
476		Repoint wall approx 2 m2.				Repoint	RR	R	2.000		1.000	1	2.000
477		Repoint wall approx 3 m2.				Repoint	RR	R	3.000		1.000	1	3.000
478		Repoint wall approx 3 m2.				Repoint	RR	R	3.000		1.000	1	3.000
479		Repoint wall approx 2 m2.				Repoint	RR	R	2.000		1.000	1	2.000
480		Repoint wall approx 3 m2.				Repoint	RR	R	3.000		1.000	1	3.000
481		Repair redundant scaffold fixing.				Remove fixings and mortar repair	RF, MR	R					1.000
482		Repair redundant scaffold fixing.				Remove fixings and mortar repair	RF, MR	R					1.000
483		Rebed and repoint copings plus repoint top two courses for entire length of elevation.				Rebed and repoint copings plus repoint top two courses for entire length of elevation.	RR	R					2.600

ITEM	ELEVATION	DESCRIPTION OF WORK AREA	LENGTH	DEPTH	HEIGHT	REPAIR	CODE	RATING	LENGTH	DEPTH	HEIGHT	NO	QTY
484		Remove redundant insulator and make good.				Remove insulator and mortar repair	RF, MR	R					8.000
485		Remove redundant insulator and make good.				Remove insulator and mortar repair	RF, MR	R					1.000
486		Remove redundant insulator and make good.				Remove insulator and mortar repair	RF, MR	R					1.000
487		Rebed and repoint copings plus repoint top two courses for entire length of elevation.				Rebed and repoint copings plus repoint top two courses for entire length of elevation.	RR	R					3.000
488		Remove redundant insulator and make good.				Remove insulator and mortar repair	RF, MR	R					1.000
489		Remove redundant insulator and make good.				Remove insulator and mortar repair	RF, MR	R					2.000
490		Remove redundant insulator and make good.				Remove insulator and mortar repair	RF, MR	R					2.000
491		Refix existing pipework				Refix existing pipework		R					
492		Repoint Arch over window.				Repoint	RR	R					1.000
493		Rebuild small parapet using new bricks and using existing coping stones.				Rebuild small parapet using new bricks and using existing coping stones.	B:ID, RR	R					1.000
494		Repair redundant scaffold fixing.				Remove fixings and mortar repair	RF, MR	R					1.000
494A		Broken cill repair Pin & Resin				Pin & resin repair	PR, MR	PR					1.000
495		Repoint wall approx 6 m2.				Repoint	RR	R	6.000		1.000	1	6.000
496		Repoint wall approx 6 m2.				Repoint	RR	R	6.000		1.000	1	6.000
497		Repoint entire parapet including rebedding of coping stones.				Repoint entire parapet including rebedding of coping stones.	RR	R					1.000
498		Repoint entire end of gable wall.				Repoint	RR	R					2.000
499		Rebed and repoint copings plus repoint top two courses for entire length of elevation.				Rebed and repoint copings plus repoint top two courses for entire length of elevation.	RR	R					1.400
500		Repoint wall approx 0.5 m2.				Repoint	RR	R	0.500		1.000	1	0.500
508		Repoint wall approx 3 m2.				Repoint	RR	R	3.000		1.000	1	3.000
509		Repoint Arch over window.				Repoint	RR	R					1.000
510		Repair redundant scaffold fixing.				Remove fixings and mortar repair	RF, MR	R					1.000
511		Repair redundant scaffold fixing.				Remove fixings and mortar repair	RF, MR	R					1.000
512		Repoint wall approx 2 m2.				Repoint	RR	R	2.000		1.000	1	2.000
513		Repoint Arch over window.				Repoint	RR	R					1.000
514		Repoint Arch over window.				Repoint	RR	R					1.000
515		Remove fixings and make good. Repoint wall 1 m2				Remove fixings and mortar repair, repoint	RF, MR & RR	R	1.000		1.000	2	2.000
516		Remove fixings and make good. Repoint wall 1 m2				Remove fixings and mortar repair, repoint	RF, MR & RR	R	1.000		1.000	2	2.000

ITEM	ELEVATION	DESCRIPTION OF WORK AREA	LENGTH	DEPTH	HEIGHT	REPAIR	CODE	RATING	LENGTH	DEPTH	HEIGHT	NO	QTY
517		Repair redundant scaffold fixing.				Remove fixings and mortar repair	RF, MR	R					1.000
518		Remove fixings and make good. Repoint wall 1 m2				Remove fixings and mortar repair, repoint	RF, MR & RR	R	1.000		1.000	2	2.000
519		Remove fixings and make good. Repoint wall 1 m2				Remove fixings and mortar repair, repoint	RF, MR & RR	R	1.000		1.000	2	2.000
520		Refix existing pipework				Refix existing pipework		R					
521		Repoint wall approx 3 m2.				Repoint	RR	R	3.000		1.000	1	3.000
522		Repair redundant scaffold fixing.				Remove fixings and mortar repair	RF, MR	R					1.000
523		Repoint wall approx 2 m2.				Repoint	RR	R	2.000		1.000	1	2.000
524		Repoint wall approx 1 m2.				Repoint	RR	R	1.000		1.000	1	1.000
525		Repoint wall approx 2 m2.				Repoint	RR	R	2.000		1.000	1	2.000
526		Repoint wall approx 3 m2.				Repoint	RR	R	3.000		1.000	1	3.000
527		Repoint Arch over window.				Repoint	RR	R					1.000
528		Repoint wall approx 4 m2.				Repoint	RR	R	3.000		1.000	1	4.000
529		Repair redundant scaffold fixing.				Remove fixings and mortar repair	RF, MR	R					1.000
530		Repoint Arch over window.				Repoint	RR	R					1.000
531		Repoint Arch over window.				Repoint	RR	R					1.000
532		Repoint wall approx 6 m2.				Repoint	RR	R	6.000		1.000	1	6.000
533		Repair redundant scaffold fixing.				Remove fixings and mortar repair	RF, MR	R					1.000
534		Repoint Arch over window.				Repoint	RR	R					1.000
535		Refix existing pipework				Refix existing pipework		R					0.000
536		Repoint Arch over window.				Repoint	RR	R					1.000
537		Repoint wall approx 4 m2.				Repoint	RR	R	4.000		1.000	1	4.000
538		Repoint wall approx 3 m2.				Repoint	RR	R	3.000		1.000	1	3.000
546		Repoint Arch over window.				Repoint	RR	R					1.000
547		Repoint wall approx 4 m2.				Repoint	RR	R	4.000		1.000	1	4.000
548		Repoint wall approx 2 m2.				Repoint	RR	R	2.000		1.000	1	2.000
548A		M/R to Cill				Mortar repair to cill	MR		0.100		0.100		1.000
549		Remove existing plugs and make good				Remove fixings and mortar repair	RF, MR	R					1.000
550		Repoint Arch over window.				Repoint	RR	R					1.000
551		Repoint wall approx 3 m2.				Repoint	RR	R	2.000		1.000	1	3.000
552		Repoint wall approx 2 m2.				Repoint	RR	R	2.000		1.000	1	2.000
553		Repoint Arch over window.				Repoint	RR	R					1.000
554		Refix existing pipework				Refix existing pipework		R					
555		Remove fixings and make good. Repoint wall 1 m2				Remove fixings and mortar repair, repoint	RF, MR & RR	R	1.000		1.000	2	2.000
556		Repoint Arch over window.				Repoint	RR	R					1.000
557		Remove fixings and make good. Repoint wall 1 m2				Remove fixings and mortar repair, repoint	RF, MR & RR	R	1.000		1.000	4	4.000
558		Repoint Arch over window.				Repoint	RR	R					1.000
559		Refix existing pipework				Refix existing pipework		R					
560		Refix existing pipework				Refix existing pipework		R					
561		Repair redundant scaffold fixing.				Remove fixings and mortar repair	RF, MR	R					1.000
562		Repoint wall approx 3 m2.				Repoint	RR	R	3.000		1.000	1	3.000

ITEM	ELEVATION	DESCRIPTION OF WORK AREA	LENGTH	DEPTH	HEIGHT	REPAIR	CODE	RATING	LENGTH	DEPTH	HEIGHT	NO	QTY
563		Repoint wall approx 2 m2.				Repoint	RR	R	2.000		1.000	1	2.000
564		Repoint wall approx 2 m2.				Repoint	RR	R	2.000		1.000	1	2.000
565		Repoint wall approx 3 m2.				Repoint	RR	R	3.000		1.000	1	3.000
566		Repair redundant scaffold fixing.				Remove fixings and mortar repair	RF, MR	R					1.000
567		Repoint wall approx 2 m2.				Repoint	RR	R	2.000		1.000	1	2.000
568		Repoint Arch over window.				Repoint	RR	R					1.000
569		Repoint wall approx 8 m2.				Repoint	RR	R	8.000		1.000	1	8.000
570		Repoint Arch over window.				Repoint	RR	R					1.000
571		Repoint wall approx 4m2.				Repoint	RR	R	4.000		1.000	1	4.000
572		Repair redundant scaffold fixing.				Remove fixings and mortar repair	RF, MR	R					1.000
573		Repair redundant scaffold fixing.				Remove fixings and mortar repair	RF, MR	R					1.000
574		Repoint wall approx 25m2.				Repoint	RR	R	25.000		1.000	1	25.000
575		Repoint wall approx 4m2.				Repoint	RR	R	4.000		1.000	1	4.000
576		Carry out repairs to split window cill, return cill to original profile.				Pin and resin and Mortar Repair	PR, MR	R					1.000
577		Repoint wall approx 3 m2.				Repoint	RR	R	3.000		1.000	1	3.000
578		Repair redundant scaffold fixing.				Remove fixings and mortar repair	RF, MR	R					2.000
579		Repair redundant scaffold fixing.				Remove fixings and mortar repair	RF, MR	R					1.000
580		Repair redundant scaffold fixing.				Remove fixings and mortar repair	RF, MR	R					2.000
581		Repoint wall approx 3 m2.				Repoint	RR	R	3.000		1.000	1	3.000
582		Repoint wall approx 3 m2.				Repoint	RR	R	3.000		1.000	1	3.000
593		Repoint wall approx 4 m2.				Repoint	RR	R	4.000		1.000	1	4.000
594		Repoint wall approx 3 m2.				Repoint	RR	R	3.000		1.000	1	3.000
595		Repoint wall approx 3 m2.				Repoint	RR	R	3.000		1.000	1	3.000
596		Refix existing pipework				Refix existing pipework		R					
597		Repoint wall approx 3 m2.				Repoint	RR	R	3.000		1.000	1	3.000
598		Refix existing pipework				Refix existing pipework		R					
599		Repoint wall approx 3 m2.				Repoint	RR	R	3.000		1.000	1	3.000
600		Repoint wall approx 2 m2.				Repoint	RR	R	3.000		1.000	1	2.000
601		Repoint wall approx 3 m2.				Repoint	RR	R	3.000		1.000	1	3.000
602		Remove fixings and make good. Repoint wall 1 m2. Replace spalled brickwork.				Remove fixings and mortar repair, repoint. Replace spalled bricks	RF, MR, RR & B:ID	R	1.000		1.000	3	4.000
603		Refix existing pipework				Refix existing pipework		R					0.000
604		Repair redundant scaffold fixing.				Remove fixings and mortar repair	RF, MR	R					1.000
605		Repoint wall approx 10m2.				Repoint	RR	R	10.000		1.000	1	10.000
613		Repoint wall approx 4m2.				Repoint	RR	R	4.000		1.000	1	4.000
614		Repoint Arch over window.				Repoint	RR	R					1.000
615		Repoint wall approx 6m2.				Repoint	RR	R	6.000		1.000	1	6.000
616		Repoint wall approx 6m2.				Repoint	RR	R	6.000		1.000	1	6.000
617		Repoint Arch over window.				Repoint	RR	R					1.000

ITEM	ELEVATION	DESCRIPTION OF WORK AREA	LENGTH	DEPTH	HEIGHT	REPAIR	CODE	RATING	LENGTH	DEPTH	HEIGHT	NO	QTY
618		Refix existing pipework				Refix existing pipework		R					
619		Repoint wall approx 4m2. Remove fixings and make good.				Repoint Remove fixings and mortar repair, repoint	RR RF, MR & RR	R	4.000		1.000	1	4.000
620		Repoint wall 1 m2				Repoint	RR	R					2.000
621		Repoint Arch over window.				Repoint	RR	R					1.000
622		Repoint Arch over window.				Repoint	RR	R					1.000
623		Refix existing pipework				Refix existing pipework		R					
624		Repoint entire wall including rebedding coping stones.				Repoint entire wall including rebedding coping stones.	RR	R					7.000
625		Repoint entire wall including rebedding coping stones.				Repoint entire wall including rebedding coping stones.	RR	R					12.000
626		Remove fixings conduits and battens, make good wall behind.				Remove fixings and mortar repair	RF, MR	R					12.000
627		Replace coping stone and rebed.				Replace coping stone and rebed.	ID, RR	R					0.000
628		Replace coping stone and rebed.				Replace coping stone and rebed.	ID, RR	R					0.000
Courtyard facing Bernard Street													
137		Repoint entire wall around duct.				Repoint	RR	R					5.000
138		Repoint entire parapet on this stretch of the elevation.				Repoint	RR	R					5.000
139		Abrasive clean stone corbel along full length of elevation.				Abrasive clean corbel, 5" spinner variable speed		R					1.000
139A		Damage to copings				Pin and resin and Mortar Repair	PR, MR						2.000
140		Repoint entire chimney side.				Repoint	RR	R					1.000
141		Repoint entire chimney side. Also attempt to clean these particularly discoloured bricks.				Repoint, clean discoloured bricks	RR	R					1.500
142		Repoint entire chimney side.				Repoint	RR	R					1.500
143		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					2.000
144		Remove existing failing coating to parapet, once stripped, access what options we have to clean up and point brickwork or reapply new coating system.				Remove existing failing coating to parapet, once stripped, access what options we have to clean up and point brickwork or reapply new coating system.	INV	R					1.000
145		Repoint entire wall around duct.				Repoint	RR	R					4.000
146		Repoint entire pier between adjacent windows.				Repoint	RR	R					2.000
147		Repoint entire chimney side.				Repoint	RR	R					3.000
148		Repoint entire chimney side.				Repoint	RR	R					3.000
149		Repoint entire chimney side.				Repoint	RR	R					2.000
150		Repoint wall approx 6 m2.				Repoint	RR	R	6.000		1.000	1	6.000

ITEM	ELEVATION	DESCRIPTION OF WORK AREA	LENGTH	DEPTH	HEIGHT	REPAIR	CODE	RATING	LENGTH	DEPTH	HEIGHT	NO	QTY
151		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					2.000
152		Repoint wall approx 2 m2.				Repoint	RR	R	2.000		1.000	1	2.000
153		Repoint wall approx 3 m2.				Repoint	RR	R	3.000		1.000	1	3.000
154		Remove fixings and make good. Also repair/replace 3 no bricks. Also remove paint streaks.				Remove fixings and mortar repair, repair/replace 3 no bricks. Also remove paint streaks.	RF, MR, B:ID, ST	R					4.000
155		Replace 3 no damaged bricks with glazed bricks that match existing wall.				Replace brick	B:ID	R				3	3.000
156		Remove fixings and make good. Replace brick				Remove fixings and mortar repair	RF, MR	R					1.000
157		Remove fixings and make good. Also repair replace 3 no bricks.				Remove fixings and mortar repair. Replace brick	RF, MR & B:ID	R					5.000
158		Remove fixings and make good. Also repair/replace 3 no bricks. Also remove paint streaks.				Remove fixings and mortar repair, repair/replace 3 no bricks. Also remove paint streaks.	RF, MR, B:ID, ST	R					4.000
159		Replace 3 no damaged bricks with glazed bricks that match existing wall.				Remove fixings and mortar repair	RF, MR	R					5.000
160		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					2.000
161		Repoint entire wall around duct.				Repoint	RR	R					2.000
162		Repoint Arch over window.				Repoint	RR	R					1.000
163		Repoint entire pier between adjacent windows.				Repoint	RR	R					2.000
164		Repoint entire pier between adjacent windows.				Repoint	RR	R					2.000
165		Repoint entire chimney side.				Repoint	RR	R					2.000
166		Repoint entire chimney side.				Repoint	RR	R					3.000
167		Repoint entire chimney side.				Repoint	RR	R					2.000
168		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					14.000
169		Replace 2 no damaged bricks with glazed bricks that match existing wall.				Replace brick	B:ID	R				2	2.000
170		Repoint Arch over window and 1 m2 of brickwork above.				Repoint	RR	R					1.000
171		Repoint wall approx 4 m2.				Repoint	RR	R	4.000		1.000	1	4.000
172		Repoint Arch over window.				Repoint	RR	R					1.000
173		Repoint wall approx 4 m2.				Repoint	RR	R	4.000		1.000	1	4.000
174		Remove paint splashes				Repoint	RR	R					0.000
175		Repoint wall approx 7 m2.				Repoint	RR	R	7.000		1.000	1	7.000
176		Remove paint splashes				Remove paint splashes	ST	R					0.000
177		Repoint Arch over window.				Repoint	RR	R					1.000
178		Repoint entire wall around duct.				Repoint	RR	R					2.000

ITEM	ELEVATION	DESCRIPTION OF WORK AREA	LENGTH	DEPTH	HEIGHT	REPAIR	CODE	RATING	LENGTH	DEPTH	HEIGHT	NO	QTY
179		Repoint Arch over window and 2 m2 of brickwork above.				Repoint	RR	R	2.000		1.000	1	2.000
180		Repoint Arch over window and 2 m2 of brickwork above.				Repoint	RR	R	2.000		1.000	1	2.000
181		Repoint entire chimney side.				Repoint	RR	R					2.000
182		Repoint entire chimney side.				Repoint	RR	R					3.000
183		Repoint entire chimney side.				Repoint	RR	R					2.000
184		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					6.000
185		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					6.000
186		Replace 8 no damaged bricks with glazed bricks that match existing wall.				Replace brick	B:ID	R				8	8.000
187		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					4.000
188		Repoint wall approx 6 m2.				Repoint	RR	R	6.000		1.000	1	6.000
189		Repoint Arch over window.				Repoint	RR	R					1.000
190		Remove paint splashes				Remove paint splashes	ST	R					
191		Repoint Arch over window. Remove paint splashes				Repoint, remove paint splashes	RR, ST	R					1.000
192		Repoint Arch over window. Remove paint splashes				Repoint, remove paint splashes	RR, ST	R					1.000
193		Repoint wall approx 4 m2.				Repoint	RR	R	4.000		1.000	1	4.000
194		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					22.000
195		Replace 10 no damaged bricks with glazed bricks that match existing wall.				Replace brick	B:ID	R				10	10.000
196		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					2.000
197		Repoint entire wall around duct.				Repoint	RR	R					2.000
198		Repoint wall approx 2 m2.				Repoint	RR	R	2.000		1.000	1	2.000
199		Remove cable clips and make mortar good.				Remove fixings and repoint	RF, RR	R					8.000
200		Repoint entire chimney side.				Repoint	RR	R					2.000
201		Repoint entire chimney side.				Repoint	RR	R					3.000
202		Repoint entire chimney side.				Repoint	RR	R					2.000
203		Replace 5 no damaged bricks with glazed bricks that match existing wall.				Remove fixings and repoint	RF, RR	R	Remove fixings and repoint	RF, RR	R	Remove fixings and repoint	5
204		Remove paint splashes				Remove paint splashes	ST	R					0.000
205		Repoint wall approx 5 m2.				Repoint	RR	R	5.000		1.000	1	5.000
206		Carry out repairs to split window cill, return cill to original profile.				Pin and resin and Mortar Repair	PR, MR	R					1.000
207		Repoint entire pier between adjacent windows.				Repoint	RR	R					6.000
208		Repoint entire pier between adjacent windows.				Repoint	RR	R					2.000

ITEM	ELEVATION	DESCRIPTION OF WORK AREA	LENGTH	DEPTH	HEIGHT	REPAIR	CODE	RATING	LENGTH	DEPTH	HEIGHT	NO	QTY
209		Repoint entire pier between adjacent windows.				Repoint	RR	R					2.000
210		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					4.000
211		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					2.000
212		Replace 5 no damaged bricks with glazed bricks that match existing wall.				Replace brick	B:ID	R				5	5.000
213		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					2.000
214		Remove cable clips and make mortar good.				Remove fixings and mortar repair	RF, MR	R					2.000
215		Remove cable clips and make mortar good.				Remove fixings and mortar repair	RF, MR	R					4.000
216		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					8.000
217		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					2.000
218		Repoint wall approx 10 m2.				Repoint	RR	R	10.000		1.000	1	10.000
219		Repair redundant scaffold fixing.				Remove fixings and mortar repair	RF, MR	R					2.000
220		Repoint Arch over window.				Repoint	RR	R					1.000
221		Repoint wall approx 3 m2.				Repoint	RR	R	3.000		1.000	1	3.000
222		Repoint wall approx 3 m2.				Repoint	RR	R	3.000		1.000	1	3.000
223		Repair redundant scaffold fixing.				Remove fixings and mortar repair	RF, MR	R					1.000
224		Repoint entire chimney side.				Repoint	RR	R					2.000
225		Repoint entire chimney side.				Repoint	RR	R					3.000
226		Repoint entire chimney side.				Repoint	RR	R					2.000
227		Replace 5 no damaged bricks with glazed bricks that match existing wall. Also redundant fixings in locality.				Replace 5 No brick, remove 4 No fixings and mortar repair	B:ID, RF and MR	R					5.000
228		Repair redundant scaffold fixing.				Remove fixings and mortar repair	RF, MR	R					1.000
229		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					5.000
230		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					5.000
231		Repoint wall approx 1 m2.				Repoint	RR	R	1.000		1.000	1	1.000
232		Repoint wall approx 3 m2.				Repoint	RR	R	3.000		1.000	1	3.000
233		Replace 5 no damaged bricks with glazed bricks that match existing wall. Also remove paint spalshes				Replace brick and remove paint splashes	B:ID & ST	R					5.000
234		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					6.000
419		Repoint wall approx 4 m2.				Repoint	RR	R	4.000		1.000	1	4.000
420		Repoint flashing full length of elevation.				Repoint	RR	R					

ITEM	ELEVATION	DESCRIPTION OF WORK AREA	LENGTH	DEPTH	HEIGHT	REPAIR	CODE	RATING	LENGTH	DEPTH	HEIGHT	NO	QTY
421		Repoint wall approx 1 m2.				Repoint	RR	R	1.000		1.000	1	1.000
422		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					2.000
423		Carry out further abrasive cleaning to window surround. Paint grille with new gloss paint finish.				Abrasive clean surround, 5" spinner variable speed, paint grille		R					1.000
424		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					4.000
501		Remove old clips and make good.				Remove fixings and mortar repair	RF, MR	R					20.000
502		Replace with 5 No new bricks				Replace with 5 No new bricks	B	B					5.000
503		Repoint Arch over window.				Repoint	RR	R					1.000
504		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					2.000
505		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					2.000
506		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					2.000
507		Repoint wall approx 2 m2.				Repoint	RR	R	2.000		1.000	1	2.000
539		Repoint wall approx 6 m2.				Repoint	RR	R	6.000		1.000	1	6.000
540		Remove existing plugs and make good 1 no brick & 4no mortar repairs				1 No brick 4 No mortar repairs	RF, MR	B					4.000
541		Remove old pipe clips and make good.				Remove fixings and mortar repair	RF, MR	R					22.000
542		Remove old clips and make good.				Remove fixings and mortar repair	RF, MR	R					2.000
543		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					5.000
544		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					5.000
545		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					5.000
583		Repoint wall approx 6 m2.				Repoint	RR	R	6.000		1.000	1	6.000
584		Repoint Arch over window.				Repoint	RR	R					1.000
585		Remove cable clips and make mortar good.				Remove fixings and mortar repair	RF, MR	R					2.000
586		Remove old clips and make good.				Remove fixings and mortar repair	RF, MR	R					3.000
587		Remove cable clips and make mortar good.				Remove fixings and mortar repair	RF, MR	R					6.000
588		Seal up redundant services hole with new brickwork.				Brick indents	B:ID	R					2.000
589		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					4.000
590		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					4.000
591		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					4.000

ITEM	ELEVATION	DESCRIPTION OF WORK AREA	LENGTH	DEPTH	HEIGHT	REPAIR	CODE	RATING	LENGTH	DEPTH	HEIGHT	NO	QTY
592		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					4.000
606		Repoint wall approx 4 m2.				Repoint	RR	R	4.000		1.000	1	4.000
607		Remove old clips and make good.				Remove fixings and mortar repair	RF, MR	R					10.000
608		Reinstate cut service pipe.				Reinstate cut service pipe.		R					
609		Repoint Arch over window.				Repoint	RR	R					1.000
610		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					4.000
611		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					4.000
612		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					4.000
Courtyard facing Herbrand Street													
235		Repair redundant scaffold fixing.				Remove fixings and mortar repair	RF, MR	R					4.000
236		Contractor to reinstate lead pipework to original condition. (bent over to clear scaffold)				Reinstate lead pipework to original condition. (bent over to clear scaffold)		R					
237		Provide and fix new lead flashing to entire length of elevation. Point joint above flashing.				Provide and fix new lead flashing to entire length of elevation. Point joint above flashing.	RR	R					7.000
238		Repoint parapet wall under coping including the top 3 no. courses, entire length of elevation.				Repoint	RR	R					2.100
239		Refix rainwater goods after correcting spalled brickwork.				Defrass brickwork and refix rainwater goods	DF	R					1.000
261		Repoint Arch over window plus 1 m2 above.				Repoint	RR	R					1.000
262		Repoint Arch over window plus 1 m2 above.				Repoint	RR	R					1.000
263		Repoint Arch over window plus 1 m2 above.				Repoint	RR	R					1.000
264		Abrasive clean stone corbel along full length of elevation.				Abrasive clean corbel, 5" spinner variable speed		R					1.000
265		Repoint Arch over window plus 1 m2 above.				Repoint	RR	R					1.000
266		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					2.000
267		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					3.000
268		Repoint wall approx 2 m2.				Repoint	RR	R	2.000		1.000	1	2.000
269		Remove cable clips and make mortar good.				Remove fixings and mortar repair	RF, MR	R					4.000
290		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					4.000
291		Repoint Arch over window plus 1 m2 above.				Repoint	RR	R					1.000
292		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					4.000

ITEM	ELEVATION	DESCRIPTION OF WORK AREA	LENGTH	DEPTH	HEIGHT	REPAIR	CODE	RATING	LENGTH	DEPTH	HEIGHT	NO	QTY
294		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					4.000
295		Repoint wall approx 2 m2.				Repoint	RR	R	2.000		1.000	1	2.000
296		Repoint entire pier between adjacent windows.				Repoint	RR	R					1.000
297		Repoint Arch over window plus 2 m2 above.				Repoint	RR	R					2.000
315		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					6.000
316		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					2.000
317		Repoint wall approx 2 m2.				Repoint	RR	R	2.000		1.000	1	2.000
318		Repoint Arch over window.				Repoint	RR	R					1.000
319		Replace 3 no damaged bricks with glazed bricks that match existing wall.				Replace brick	B:ID	R				3	3.000
320		Repair redundant scaffold fixing.				Remove fixings and mortar repair	RF, MR	R					2.000
321		Repoint Arch over window plus 2 m2 above.				Repoint	RR	R					2.000
322		Repoint Arch over window plus 1 m2 above.				Repoint	RR	R					1.000
351		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					2.000
352		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					1.000
353		Repoint wall approx 5 m2.				Repoint	RR	R	5.000		1.000	1	5.000
354		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					3.000
355		Replace window cill to original profile.				Mortar Repair	MR	R					1.000
356		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					2.000
357		Return period lead pipe to pristine condition.				Return period lead pipe to pristine condition.		R					
384		Repoint wall approx 2 m2.				Repoint	RR	R	2.000		1.000	1	2.000
385		Replace damaged bricks with glazed bricks that match existing wall.				Replace brick	B:ID	R					2.000
386		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					2.000
387		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					4.000
388		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					4.000
389		Repoint wall approx 2 m2.				Repoint	RR	R	2.000		1.000	1	2.000
390		Return period lead pipe to pristine condition.				Return period lead pipe to pristine condition.		R					
391		Repoint wall approx 1 m2.				Repoint	RR	R	1.000		1.000	1	1.000
392		Repoint wall approx 2 m2.				Repoint	RR	R	2.000		1.000	1	2.000
393		Repoint Arch over window.				Repoint	RR	R					1.000

ITEM	ELEVATION	DESCRIPTION OF WORK AREA	LENGTH	DEPTH	HEIGHT	REPAIR	CODE	RATING	LENGTH	DEPTH	HEIGHT	NO	QTY
394		Remove cable clips and make mortar good.				Remove fixings and mortar repair	RF, MR	R					4.000
Courtyard facing Guilford Street													
240		Repoint parapet wall under coping including the top 3 no. courses, entire length of elevation.				Repoint	RR	R					2.400
241		Repoint above lead flashing full length of elevation.				Repoint	RR	R					2.400
242		Provide 6 no lead patches on existing flashing to prevent water ingress into projecting stonework.				Provide 6 no lead patches on existing flashing to prevent water ingress into projecting stonework.		R					
243		Repoint entire chimney side.				Repoint	RR	R					2.000
244		Repoint entire chimney side.				Repoint	RR	R					1.500
245		Repoint above lead flashing full length of elevation.				Repoint	RR	R					
246		Repoint entire chimney side.				Repoint	RR	R					2.000
247		Repair portland stone coping, also repair existing scaffolding fixing.				Mortar Repair, and remove fixings	MR and RF	R					2.000
248		Repair portland stone coping, also repoint under coping for full length of elevation.				Mortar repair and repoint	MR and RR	R					1.000
249		Replace 2 no damaged bricks with glazed bricks that match existing wall.				Replace brick	B:ID	R				2	2.000
250		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					4.000
251		Repair portland stone coping.				Mortar Repair	MR	R					1.000
252		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					4.000
253		Repoint above lead flashing full length of elevation.				Repoint	RR	R					
254		Repoint wall approx 1 m2.				Repoint	RR	R	1.000		1.000	1	1.000
255		Repoint above lead flashing full length of elevation.				Repoint	RR	R					2.000
256		Repoint entire elevation facet.				Repoint	RR	R					2.000
257		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					5.000
258		Repoint Arch over window.				Repoint	RR	R					1.000
259		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					12.000
260		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					1.000
270		Refix rainwater goods.				Refix rainwater goods.		R					
271		Repoint wall approx 2 m2.				Repoint	RR	R	2.000		1.000	1	2.000
272		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					4.000

ITEM	ELEVATION	DESCRIPTION OF WORK AREA	LENGTH	DEPTH	HEIGHT	REPAIR	CODE	RATING	LENGTH	DEPTH	HEIGHT	NO	QTY
273		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					4.000
274		Remove cable clips and make mortar good.				Remove fixings and repoint	RF, RR	R					4.000
275		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					4.000
276		Repair redundant scaffold fixing.				Remove fixings and mortar repair	RF, MR	R					1.000
277		Repair redundant scaffold fixing.				Remove fixings and mortar repair	RF, MR	R					1.000
278		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					4.000
279		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					4.000
280		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					4.000
281		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					5.000
282		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					4.000
283		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					6.000
284		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					4.000
285		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					2.000
286		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					5.000
287		Remove cable clips and make mortar good.				Remove fixings and repoint	RF, RR	R					4.000
288		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					4.000
289		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					3.000
293		Repoint wall approx 2 m2.				Repoint	RR	R	2.000		1.000	1	2.000
298		Repoint wall approx 3 m2.				Repoint	RR	R	3.000		1.000	1	3.000
299		Repoint Arch over window plus 1 m2 above.				Repoint	RR	R					2.000
300		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					4.000
301		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					4.000
302		Repoint Arch over window plus 1 m2 above.				Repoint	RR	R					2.000
303		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					5.000
304		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					4.000
305		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					4.000
306		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					4.000

ITEM	ELEVATION	DESCRIPTION OF WORK AREA	LENGTH	DEPTH	HEIGHT	REPAIR	CODE	RATING	LENGTH	DEPTH	HEIGHT	NO	QTY
307		Remove numerous fixings and make good.				Remove fixings and mortar repair	RF, MR	R					7.000
308		Remove numerous fixings and make good.				Remove fixings and mortar repair	RF, MR	R					11.000
309		Remove numerous fixings and make good.				Remove fixings and mortar repair	RF, MR	R					5.000
310		Repoint Arch over window plus 1 m2 above.				Repoint	RR	R					2.000
311		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					4.000
312		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					6.000
313		Repoint Arch over window plus 1 m2 above.				Repoint	RR	R					2.000
314		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					2.000
323		Repoint wall approx 3 m2.				Repoint	RR	R	3.000		1.000	1	3.000
324		Repoint wall approx 3 m2.				Repoint	RR	R	3.000		1.000	1	3.000
325		Repoint wall approx 3 m2.				Repoint	RR	R	3.000		1.000	1	3.000
326		Repair redundant scaffold fixing.				Remove fixings and mortar repair	RF, MR	R					1.000
327		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					4.000
328		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					4.000
329		Repoint Arch over window.											1.000
330		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					3.000
331		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					4.000
332		Repoint wall approx 2 m2.				Repoint	RR	R	2.000		1.000	1	2.000
333		Repoint wall approx 4 m2.				Repoint	RR	R	4.000		1.000	1	4.000
334		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					4.000
335		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					4.000
336		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					1.000
337		Repoint Arch over window plus 2 m2 above.				Repoint	RR	R					3.000
338		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					8.000
339		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					7.000
340		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					4.000
341		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					10.000
342		Remove numerous fixings and make good.				Remove fixings and mortar repair	RF, MR	R					9.000
343		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					4.000

ITEM	ELEVATION	DESCRIPTION OF WORK AREA	LENGTH	DEPTH	HEIGHT	REPAIR	CODE	RATING	LENGTH	DEPTH	HEIGHT	NO	QTY
344		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					4.000
345		Repair redundant scaffold fixing.				Remove fixings and mortar repair	RF, MR	R					1.000
346		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					8.000
347		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					2.000
348		Repoint Arch over window.				Repoint	RR	R					1.000
349		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					4.000
350		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					4.000
358		Repoint wall approx 3 m2.				Repoint	RR	R	3.000		1.000	1	3.000
359		Remove cable clips and make mortar good.				Remove fixings and mortar repair	RF, MR	R					2.000
360		Repair redundant scaffold fixing.				Remove fixings and mortar repair	RF, MR	R					1.000
361		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					4.000
362		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					4.000
363		Repair redundant scaffold fixing.				Remove fixings and mortar repair	RF, MR	R					1.000
364		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					4.000
365		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					4.000
366		Repoint wall approx 5 m2.				Repoint	RR	R	5.000		1.000	1	5.000
367		Repoint wall approx 5 m2.				Repoint	RR	R	5.000		1.000	1	5.000
368		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					4.000
369		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					4.000
370		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					9.000
371		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					8.000
372		Replace 2 no damaged bricks with glazed bricks that match existing wall.				Replace brick	B:ID	R				2	2.000
373		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					9.000
374		Repoint wall approx 1 m2.				Repoint	RR	R	1.000		1.000	1	1.000
375		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					9.000
376		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					5.000
377		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					6.000
378		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					4.000

ITEM	ELEVATION	DESCRIPTION OF WORK AREA	LENGTH	DEPTH	HEIGHT	REPAIR	CODE	RATING	LENGTH	DEPTH	HEIGHT	NO	QTY
379		Repair redundant scaffold fixing.				Remove fixings and mortar repair	RF, MR	R					1.000
380		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					3.000
381		Repair redundant scaffold fixing.				Remove fixings and mortar repair	RF, MR	R					1.000
382		Repair redundant scaffold fixing.				Remove fixings and mortar repair	RF, MR	R					1.000
383		Return period lead pipe to pristine condition.				Return period lead pipe to pristine condition.		R					
384		Repoint wall approx 2 m2.				Repoint	RR	R	2.000		1.000	1	2.000
385		Replace damaged bricks with glazed bricks that match existing wall.				Replace brick	B:ID	R					2.000
386		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					2.000
387		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					4.000
395		Repoint wall approx 2 m2.				Repoint	RR	R	2.000		1.000	1	2.000
396		Repoint wall approx 6 m2.				Repoint	RR	R	6.000		1.000	1	6.000
397		Repoint wall approx 4 m2.				Repoint	RR	R	4.000		1.000	1	4.000
398		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					2.000
399		Repoint wall approx 2 m2.				Repoint	RR	R	2.000		1.000	1	2.000
400		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					2.000
401		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					4.000
402		Repoint Arch over window.				Repoint	RR	R					1.000
403		Repoint wall approx 5 m2.				Repoint	RR	R	5.000		1.000	1	5.000
404		Repoint wall approx 6 m2.				Repoint	RR	R	6.000		1.000	1	6.000
405		Repoint wall approx 5 m2.				Repoint	RR	R	5.000		1.000	1	5.000
406		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					4.000
407		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					4.000
408		Repoint Arch over window.				Repoint	RR	R					1.000
409		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					8.000
410		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					2.000
411		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					10.000
412		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					4.000
413		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					5.000
414		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					6.000
415		Remove fixings and make good.				Remove fixings and mortar repair	RF, MR	R					4.000

VO 45 - Recess area to new link bridge

ITEM	ELEVATION	DESCRIPTION OF WORK AREA	LENGTH	DEPTH	HEIGHT	REPAIR	CODE	RATING	LENGTH	DEPTH	HEIGHT	NO	QTY
500		Pointing below coping				Repoint	RR	R				1	12.700
501		Remove vegetation				Repoint	RR	R				1	1.000
502		Remove pie bracket and make good.				Remove fixings and mortar repair	RF, MR	R				1	
503		Remove pie bracket and make good.				Remove fixings and mortar repair	RF, MR	R				1	
504		Displaced Brickwork structural engineer to advise				Repoint Brickwork	RR	R					6.000
505		Repoint Glazed Bricks				Repoint Brickwork	RR	R					4.000
506		Repoint Glazed Bricks				Repoint Brickwork	RR	R					4.000
507		Repoint coping and ensure copings are secure				Repoint copings	RR	R				Inc	
508		Remove pipe bracket and make good.				Remove fixings and mortar repair	RF, MR	R				6	
509		Remove pipe bracket and make good.				Remove fixings and mortar repair	RF, MR	R				5	
510		Repoint brickwork to stack				Repoint	RR	R				Inc elsewhere	
511		Repoint brickwork				Repoint & 4 No mortar reapirs	RR	R				4	
512		Replace Flaununching				Flaunching	FL	R				Inc elsewhere	
513		Replace Flaununching				Flaunching	FL	R				Inc elsewhere	
514		Repointing top 7 courses of chimney stack				Repointing to stack	RR	R				Inc elsewhere	
515		Pointing to brickwork				Repoint	RR	R				Inc elsewhere	
516		Pointing to Brickwork				Repoint	RR	R				Inc elsewhere	
517		Pointing to brickwork				Repoint	RR	R				Inc elsewhere	6.000
518		Pointing to brickwork				Repoint	RR	R					6.000
519		Remove pipe bracket and make good.				Remove pipe bracket and make good inc clean off paint	RF RR	R	0.100	0.100		1	
520		Remove old Fixings & make good mortar repair				Remove old fixings and make good	RF MR	R	0.075	0.075		18	
521		Remove old Fixings & make good mortar repair				Remove old fixings and make good	RF MR	R	0.075	0.075		4	
522		Remove old Fixings & make good mortar repair				Remove old fixings and make good	RF MR	R	0.05	0.05		2	
523		Remove old Fixings & make good mortar repair				Remove old fixings and make good	RF MR	R	0.100	0.100		1	
524		Remove redundant window				Brick up window with glazed bricks externally and engineering bricks to inside face bonded into existing	BI	BI					

ITEM	ELEVATION	DESCRIPTION OF WORK AREA	LENGTH	DEPTH	HEIGHT	REPAIR	CODE	RATING	LENGTH	DEPTH	HEIGHT	NO	QTY
525		Repair concrete window jamb				Re render	R	R	1.300	0.600		2	
526		Pointing to glazed bricks				Repoint wall	RR	R				4	
527		Failed mastic cap				By others							
528		Pointing to glazed bricks				Repoint wall	RR	R				2	
529		Reglaze damaged windows				By others							
530		Redecorate window frames				By others							
531		Remove old Fixings				Remove old fixings and make good	RF MR	R	0.100	0.100		4	
532		Remove redundant pipe				Remove redundant pipe and make good wall with Glazed bricks	B:ID	BI				5	
533		Remove old Fixings & make good mortar repair				Remove old fixings and make good	RF MR	R	0.075	0.075		14	
534		Remove old Fixings & make good mortar repair				Remove old fixings and make good	RF MR	R	0.05	0.05		8	
535		Remove old Fixings & make good mortar repair				Remove old fixings and make good	RF MR	R	0.100	0.100		2	
536		Remove old Fixings & make good mortar repair				Remove old fixings and make good	RF MR	R	0.05	0.05		5	
537		Remove old Fixings & make good mortar repair				Remove old fixings and make good	RF MR	R	0.100	0.100		5	
538		Replace soil pipe				Replace 6 No new bricks	B:ID	BI				6	
539		Remove old Fixings & make good mortar repair				Remove old fixings and make good	RF MR	R	0.05	0.05		2	
540		Make good render wall				Break back to a sound base re-render incorporating a sound base and apply a masonry paint (Paint by others)	RR	R	4.200	1.300	0.500		
541		Make good render wall				Break back to a sound base re-render incorporating a sound base and apply a masonry paint	RR	R	Refer to 540				
542		Repointt arch				Repoit brickwork forming arch	RP	RP				1	
543		Remove old Fixings & make good mortar repair				Remove old fixings and make good	RF MR	R	0.075	0.075		4	
544		Clean stone string course				Clean stone string course as rest of court yard							
545		Repoint below stone string course				Repoint brickwork below length of string course	RR	R				2	
546		Repar coating				Repair coating as main part of courtyard							
547		Pointing to glazed bricks				Repoint wall	RR	R				2	
548		Pointing to glazed bricks				Repoint wall	RR	R				4	

ITEM	ELEVATION	DESCRIPTION OF WORK AREA	LENGTH	DEPTH	HEIGHT	REPAIR	CODE	RATING	LENGTH	DEPTH	HEIGHT	NO	QTY
549		Remove Redundant window				Brick up window with glazed bricks externally and engineering bricks to inside face bonded into existing	BI	BI					
550		Pointing to glazed bricks				Repoint wall	RR	R				6	
551		Remove redundant pipe				Remove redundant pipe and make good wall with Glazed bricks	B:ID	BI				4	
552		Remove old Fixings & make good mortar repair				Remove old fixings and make good	RF MR	R	0.050	0.050		4	
553		Repir concrete window jambs				Remove and re- render	RR	R	1.000	0.650		2	
554		Redecorate window frames				Redecorate with gloss paint			By Others				
555		Make good render wall				Break back to a sound base re-render incorporating a sound base and apply a masonry paint (Paint by others)	RR	R	4.200	1.300	0.500		
556		Pointing to glazed bricks				Repoint wall	RR	R				2	
557		Pointing to glazed bricks				Repoint wall	RR	R				4	
558		Remove old Fixings & make good mortar repair				Remove old fixings and make good	RF MR	R	0.100	0.100		16	
559		Reglaze damaged windows				By others							
560		Remove old Fixings & make good mortar repair				Remove old fixings and make good	RF MR	R	0.100	0.100		1	
560a		Remove old Fixings & make good mortar repair				Remove old fixings and make good	RF MR	R	0.075	0.075		20	
561		Pointing to glazed bricks				Repoint wall	RR	R				4	
562		Remove Redundant window				Brick up window with glazed bricks externally and engineering bricks to inside face bonded into existing	BI	BI					
563		Remove old Fixings & make good mortar repair				Remove old fixings and make good	RF MR	R	0.075	0.075		20	
564		Redecorate window frames				Redecorate with gloss paint			By Others				
565		Repair concrete window jambs				Remove and re- render	RR	R	1.000	0.650		2	
566		Repair concrete window jambs				Remove and re- render	RR	R	1.000	0.650		See 560	
567		Pointing to glazed bricks				Repoint wall	RR	R				4	
568		Repointt arch				Repoit brickwork forming arch	RP	RP				1	
569		Remove old Fixings & make good mortar repair				Remove old fixings and make good	RF MR	R	0.050	0.050		4	

ITEM	ELEVATION	DESCRIPTION OF WORK AREA	LENGTH	DEPTH	HEIGHT	REPAIR	CODE	RATING	LENGTH	DEPTH	HEIGHT	NO	QTY
570		Repointt arch				Repoit brickwork forming arch	RP	RP				1	
571		Remove old Fixings & make good mortar repair				Remove old fixings and make good	RF MR	R	0.050	0.050		2	
572		Repointt arch				Repoit brickwork forming arch	RP	RP				1	
573		Remove old Fixings & make good mortar repair				Remove old fixings and make good	RF MR	R	0.075	0.075		12	
574		Remove old Fixings & make good mortar repair				Remove old fixings and make good	RF MR	R	0.075	0.075		16	
575		Pointing to glazed bricks				Repoint wall	RR	R				4	
576		Remove old Fixings & make good mortar repair				Remove old fixings and make good	RF MR	R	0.075	0.075		20	
577		Remove Redundant window				Brick up window with glazed bricks externally and engineering bricks to inside face bonded into existing	BI	BI					
578		Make good render wall				Break back to a sound base re-render incorporating a sound base and apply a masonry paint (Paint by others)	RR	R	4.200	1.300	0.500		
578a		Make good render wall				Break back to a sound base re-render incorporating a sound base and apply a masonry paint (Paint by others)	RR	R	1.200	0.650	0.500		
579		Pointing to glazed bricks				Repoint wall	RR	R				4	
580		Repointt arch				Repoit brickwork forming arch	RP	RP				1	
581		Pointing to glazed bricks				Repoint wall	RR	R				1	
582		Pointing to glazed bricks				Repoint wall	RR	R				2	
583		Remove old Fixings & make good mortar repair				Remove old fixings and make good	RF MR	R	0.075	0.075		8	
584		Pointing to glazed bricks				Repoint wall	RR	R				2	
585		Remove old Fixings & make good mortar repair				Remove old fixings and make good	RF MR	R	0.075	0.075		12	
586		Remove old Fixings & make good mortar repair				Remove old fixings and make good	RF MR	R	0.075	0.075		20	
587		Pointing to glazed bricks				Repoint wall	RR	R				4	
588		Pointing to glazed bricks				Repoint wall	RR	R				4	
589		remove redundant pipe				remocve redundant pipe and make good wall with new glazed bricks	BI	BI				8	

ITEM	ELEVATION	DESCRIPTION OF WORK AREA	LENGTH	DEPTH	HEIGHT	REPAIR	CODE	RATING	LENGTH	DEPTH	HEIGHT	NO	QTY
590		Repair concrete window jamb				Hack of existing and re-new in render	RR	R	1.200	0.650		2	
591		Replace soil pipe				By Others							
592		Redecorate window frames				By Others							
593		Make good render wall				Break back to a sound base re-render incorporating a sound base and apply a masonry paint (Paint by others)	RR	R	1.200	1.300	0.500		
594		Pointing to glazed bricks				Repoint wall	RR	R				4	
595		Remove old Fixings & make good mortar repair				Remove old fixings and make good	RF MR	R	0.075	0.075		3	
596		Remove old Fixings & make good mortar repair				Remove old fixings and make good	RF MR	R	0.075	0.075		6	
597		Remove old Fixings & make good mortar repair				Remove old fixings and make good	RF MR	R	0.075	0.075		4	
598		Remove old Fixings & make good mortar repair				Remove old fixings and make good	RF MR	R	0.075	0.075		4	
599		Remove old Fixings & make good mortar repair				Remove old fixings and make good	RF MR	R	0.075	0.075		4	
600		Remove old Fixings & make good mortar repair				Remove old fixings and make good	RF MR	R	0.075	0.075		6	
601		Remove old Fixings & make good mortar repair				Remove old fixings and make good	RF MR	R	0.075	0.075		10	
602		Remove old Fixings & make good mortar repair				Remove old fixings and make good	RF MR	R	0.075	0.075		6	
603		Remove old Fixings & make good mortar repair				Remove old fixings and make good	RF MR	R	0.500	0.500		2	
604		Pointing to glazed bricks				Repoint wall	RR	R				2	
605		Remove Redundant window				Brick up window with glazed bricks externally and engineering bricks to inside face bonded into existing	BI	BI					
606		Pointing to glazed bricks				Repoint wall	RR	R				2	
607		Pointing to glazed bricks				Repoint wall	RR	R				2	
608		Redecorate window frames				By Others							
609		Pointing to glazed bricks				Repoint wall	RR	R				4	
610		Repointt arch				Repoit brickwork forming arch	RP	RP				1	
611		Pointing to glazed bricks				Repoint wall	RR	R				2	
612		Repointt arch				Repoit brickwork forming arch	RP	RP				1	

ITEM	ELEVATION	DESCRIPTION OF WORK AREA	LENGTH	DEPTH	HEIGHT	REPAIR	CODE	RATING	LENGTH	DEPTH	HEIGHT	NO	QTY
613		Remove old Fixings & make good mortar repair				Remove old fixings and make good	RF MR	R	0.500	0.500		4	
614		Remove old Fixings & make good mortar repair				Remove old fixings and make good	RF MR	R	0.500	0.500		3	
615		Pointing to glazed bricks				Repoint wall	RR	R				2	