



The replacement windows are to be manufactured from slow grown Swedish pine/joinery quality redwood or British Columbian pine with hardwood window sills. All the windows are to be wet glazed with clear double glazed units using traditional glazing putty and finished with hand painting using Dulux weather-shield paint system/white finish internally and to match the existing paint colour externally. The proposed U-value of the glazing is 1.9.

- 1 The Contractor must check and confirm all dimensions
- 2 All discrepancies must be reported and resolved by the architect before works commence
- 3 This drawing is not to be scaled
- 4 All work and materials to be in accordance with current applicable Statutory Legislation, Codes of Practice, British Standards and EU Regulations
- 5 Drawings show design intent only. It is the Contractor's responsibility to ensure that the construction is sound and fit for use, in accordance with the Client's requirements.

Revisions.