

15mm British Gypsum Soundbloc or similar to each side. All joints to be taped and jointed, giving a smooth and seamless finish ready for

smooth and seamless finish, ready for decoration.

Type P3M. As type P3, but with outer layer replaced with 15mm

Gyproc SounBloc Moisture Resistant plasterboard ('wet' side).

Type P2M. As type P2, but with outer layer replaced with 15mm Gyproc Soundbloc Moisture Resistant plasterboard ('wet' side). **Type P2M2**. As type P2, but with outer layers replaced with 15mm Gyproc Soundbloc Moisture Resistant plasterboard (both sides)

at 600mm centres with 1 layer of 15mm British Gypsum Gyproc SoundBloc. Fully filled with unfaced mineralwool with min. density Type P6. Separating Wall Gypwall Quiet IWL (Community Facility) -10kg/m3 between studs. All joints to be taped and jointed, giving a 2 no. layer of 15mm British Gypsum Duraline (both sides). All joints

Resistant. All joints to be taped and jointed, giving a smooth and

Type P5 & P5M. SVP Boxing. 2 no. layers 15mm SoundBloc plasterboard, on 60mm Gypframe studwork generally to svp casings. All joints to be taped and jointed, giving a smooth and seamless finish, ready for decoration. Pipework to be wrapped in 50mm unfaced mineral wool. NB. 15mm Soundblock MR to replace outer layer of boxing in 'Wet' areas (Bathrooms, WCs, Utility Cupboards, Kitchens, etc.). Boxings to be fully filled with insulation when adjoining Type P3. Independent Wall Lining Generally to cores - Gyplyner IWL

to be taped and jointed, giving a smooth and seamless finish ready

Type P8M. As type P8, but with Wallboard replaced with 12.5mm proc Wallboard Moisture Resistant plasterboard.

Type P9. Load-bearing studwork to external Wall (Rosalind Franklin) 2 no. layers of 15mm British Gypsum Soundbloc on Vapour Control layer. All joints to be taped and jointed, giving a smooth and seamless finish ready for decoration

Type P9M. As type P9, but with Soundbloc replaced with 15mm Gyproc Soundbloc Moisture Resistant plasterboard. Type P10. Separating Wall Gypwall Quiet IWL (Pavilions) - 2 no.

layer of 15mm British Gypsum Soundbloc or similar to each side. All $\,\cdot\,$ joints to be taped and jointed, giving a smooth and seamless finish

taped and jointed, giving a smooth and seamless finish, ready for Type P10M. As type P10, but with one side of Soundbloc replaced with 15mm Gyproc Soundbloc Moisture Resistant plasterboard ('wet'

Gyproc SoundBloc to both sides. All joints to be taped and jointed, giving a smooth and seamless finish, ready for decoration.

Type P20M. As type P20, but with one side of SoundBloc replaced with 12.5mm Gyproc Soundbloc Moisture Resistant plasterboard

Type P20M2. As type P20, but with both layers replaced with

Type P21. Internal Partition width 155mm. 92mm Gypframe 'C' studs at max. 600mm centres with 1 layer of 12.5mm British Gypsum Gyproc SoundBLoc on 18mm Plywood to both sides. All joints to be

12.5mm Gyproc Soundbloc Moisture Resistant plasterboard (both

Type P21M. As type P21, but with one side of SoundBloc replaced with 12.5mm Gyproc Soundbloc Moisture Resistant plasterboard ('wet' side).

Type P23. Timber stud braced wall. 140mm timber studs at 600mm centres with 1 layer of 18mm Plywood to both sides and 1 layer of 12.5mm Gyproc SoundBloc plasterboard to both sides. All joints to

be taped and jointed, giving a smooth and seamless finish, ready for Type P23M.As type P23, but with one side SoundBloc replaced with 12.5mm Gyproc Soundbloc Moisture Resistant plasterboard ('wet'

Type P24. Internal Partition width 122mm. 70mm Gypframe 'C' studs at max, 600mm centres with 2 layers of 12.5mm British Gypsum Gyproc SoundBLoc to each side. All joints to be taped and jointed, giving a smooth and seamless finish, ready for decoration.

Type P24M.As type P24, but with one side of SoundBloc replaced

with 12.5mm Gyproc Soundbloc Moisture Resistant plasterboard

Resistant plasterboard on opposite side. All joints to be taped and iointed, giving a smooth and seamless finish, ready for decoration.

Type P26M2. Internal Partition width 141mm. As P26M but with 12mm Plywood to both sides.

> and seamless finish, ready for decoration. **Type P42M.** As type P42 but with the layer of Plasterboard replaced

seamless finish, ready for decoration.

jointed, giving a smooth and seamless finish, ready for decoration.

Type P41M. As type P41 but with the layer of Plasterboard replaced with Gyproc Moisture Resistant plasterboard to 'wet' area. **Type P42.** Typical Sacrificial Wall (Generally for 40mm Drainage runs) - Gyplyner Universal GL1 channel with offset of 75mm at 600mm centres (GL2 fixing brackets) with 1 layer of 12.5mm British Gypsum wallboard. All joints to be taped and jointed, giving a smooth

with Gyproc Moisture Resistant plasterboard to 'wet' area.

Type P43. Typical Sacrificial Wall (Generally for WC Drainage runs) Gyplyner Universal GL1 channel with offset of 125mm at 600mm centres (GL9 fixing brackets) with 1 layer of 12.5mm British Gypsum wallboard. All joints to be taped and jointed, giving a smooth and

12.5mm Gyproc SoundBloc on dabs. All joints to be taped and

prior to commencement of work.

jointed, giving a smooth and seamless finish ready for decoration. **Type P45M -** As type P45 but with outer layer replaced by 12.5mm SoundBloc MR Board on dabs. All joints to be taped and jointed, giving a smooth and seamless finish ready for decoration. Type P46. Plaster to Leisure Area (not to pool). Thistle HardWall by

Type P47. Tiling to pool Area. Microtec Fibre reinforced floor

existing. Plaster to be feathered with existing and made good. If type

of plaster does not correspond as noted, please contact the architect

and replace plasterboard on both sides with 12.5mm British Gypsum adhesive (Ardex X 77) or similar. Thickness varies depending on tile Wallboard. types (to pool specialist's specification) Type P48/P49. Assumed plaster repair or Lime Plaster repair respectively to existing Walls. Extent of existing damage to be assessed on site - removal to be agreed. New plaster to match

Type P51M. As type P51 but with Plasterboard replaced with Gyproc

Type P52. Drained Cavity with mesh system (generally within

manufactures recommendations.

basements) with 10mm Cavity membrane & 15mm Plaster finish to

Type P53. Assumed existing plasterboard on studwork - Remove

DIMENSION AT ORIGINAL SHEET SIZE Contractors must check all dimensions on site. Only figured dimensions are to be worked from. Discrepancies must be reported to the Architect before proceeding.© This drawing is Copyright

KEY PLAN

ALL DIMENSIONS WITH * (STAR) ARE ANTICIPATED AND SHOULD BE CHECKED AND CONFIRMED ON SITE PRIOR TO CONSTRUCTION **General Notes:**

1. All types noted below are based on the British Gypsum range. 'Similar and approved' products will be considered by the client. Any alterations to the specifications below are to be approved by the client PRIOR to order.

2. Drylining drawings are to be read in conjunction with all relevant AQP GA and M&E consultant drawings.

3. Moisture resistant plasterboard is to be used in all wet areas (Kitchens, Bathrooms, En-suites and Utility Cupboards). Areas requiring moisture resistant board are identified with the 'M' prefix in the partition type. Tiled surfaces: MR Plasterboard to be replaced

with 12.5mm Glasroc H Tilebacker boards. 4. 18mm WBP plywood support patresses on proprietary service

i. Kitchens (Full height) ii.Bathrooms (A band between 300-1800mm) iii.Living Rooms (1500mm(wide) x 1035mm(high) behind wall mounted TV positions, exact locations to be agreed on site with

5. Additional noggings/supports etc are to be provided as necessary for radiators, kitchen units, wall mounted TVs, shower mixers &

6.Deflection head details are indicated at partition heads giving min. vertical deflection allowance of 25mm. Extra deep flange channels and packing to be provided in accordance with manufacturers

7.All necessary beads etc. to be provided.

General Internal Suspended Ceiling [Newbuild]:

British Gypsum Casoline MF ceiling system finished with 1 no. 12.5mm Wallboard in 'dry areas' and 12.5mm moisture resistant wallboard in 'wet areas'. Gypframe MF8 strap hangers to be fixed to u/s of concrete soffit with Gypframe M12 soffit cleats. Proprietary primary and secondary support grids to be provided at centres in accordance with manufacturers standard details. All perimeter channels etc. to be provided in accordance with manufacturers standard details. All joints to be taped and jointed, giving a smooth

FOR CONSTRUCTION

DR'N CH'KD DATE REVISION KrC/NV TW 31/01/2017 C1 Issued for Construction



KIDDERPORE AVENUE

Bay House Level MZ Proposed GA Plan

> SCALE 1:50, 1:55.56 @ A1 DATE January 2017 DRAWN BY DRAWING No. 15 230

9000-DRG-03BH-MZ010 c1

A&Q PARTNERSHIP (LONDON) LTD THE LUX BUILDING, 2-4 HOXTON SQUARE, LONDON N 1 6 NU Tel: 020 7613 2244 Fax: 020 7613 2642 Email:london@aqp.co.uk ARCHITECTURE DESIGN MASTERPLANNING INTERIORS