Existing high level mains water pipe connected to building at basement level. New pipework will be connected to this.

Existing gas pipe

Proposed water pipework location. All penetrations will be of 150mm diameter.

Existing cabling

Existing timber blank

Vault BB96

Proposed blanks to vaults to be tanked

Vault BB97

No works to be completed to these vaults

50mm diameter penetrations for drainage

All vaults have a cast iron gate which is not shown in this drawing. Timber blank will be fixed to the inside face of the cast iron gate as in the existing example.

0m 1m 2m 4m

DO NOT SCALE

Use only written dimension. All dimension must be verified prior to works being put into hand and any discrepancies reported to the originator.

Health and Safety Information

	Details	Sign	Date
Asbestos Survey			
Structural Check/Lifting & Handling			
Site Survey			
Access and Egress/Site Compound			
Hazards Identified			

General Notes

REV	Details of Revision	Date	Sign

UCL

FAITHFUL GOULD

Euston Tower, 186 Euston Road, London, NW1 3AT

Tel: +44(0)207 121 2121

Project: UCL 119-125 Gower Street

Title: 119-125 Gower Street Vaults Proposed Works

Drawing No: UCL/ATH/002

Scale	Drawn	Checked	Co-ord chk
1:30	CB	AS	AS
Drawing size: A3	Date: 29/03/2017	Date: 29/03/2017	Date: 29/03/2017

Status: PLANNING ISSUE

©FAITHFUL+GOULD COPYRIGHT : REPRODUCTION IN WHOLE OR PART BY ANY MEANS IS PROHIBITED WITHOUT THE PRIOR WRITTEN PERMISSION OF FAITHFUL+GOULD