


300_105
ELE Window Detail - Type D
Elevation

300_105
SEC Window Detail - Type D
Section



300_105
PLN Window Detail - Type D
Plan

Key Plan, Scale 1:250

Demolition Key:

- Existing structure / ground
- Proposed removal of existing structure (in section)
- Proposed removal of existing structure/finishes (in elevation)
- Proposed removal of existing structure (in section)
- Hatch denotes removal of existing concrete slab
- Hatch denotes proposed removal of existing structure (in elevation)

Proposed finishes legend:

- Proposed straight-plank hardwood floor finish on specified floor build-up
- Proposed slate floor finish on specified floor build-up
- Portland stone
- Timber decking
- Natural stone floor tiles
- Proposed slate roof finish on existing and new roof structure

General Notes:

- Refer to the Door and Window Schedules for a detailed summary of each door and window.
- All existing floor finishes and existing ply to be carefully removed.
- Existing floorboards to be carefully removed and reused where possible.
- New/Existing floorboards to be installed.
- New furring/joints are to be installed to the top of the existing joists in order to level. See Structural Engineer's Information, Low profile UPM without.
- New drainage and concrete slab to be laid at basement level.
- Existing slate roof finish to be carefully removed and stored, and new roof felt installed. Existing slate to be replaced, new slate to match existing to replace any damaged slate. See Structural Engineer's Information, Low profile UPM without.
- Existing slate roof finish to be carefully removed and stored, and new roof felt installed. Existing slate to be replaced, new slate to match existing to replace any damaged slate. See Structural Engineer's Information, Low profile UPM without.
- Joists are to be grouted and strengthened where required to support increased loads, to Structural Engineer's details.
- Existing internal walls are to be skinned and prepared to take new wall finishes as required. All defective existing plaster to be removed and replaced.
- All existing panning, mouldings and cornices to have existing paint finish removed for new paint decoration.
- Existing structural timber beams to be exposed and treated with wood preservative. Ends to be wrapped in DPC and rotten timber to be replaced.

Proposed legend notes:

| | |
|--|---|
| 01 Existing walling to be refurbished and redecorated. | 22 Proposed condensers in attenuated enclosure, refer to M&E design |
| 02 Existing window replaced with double glazed, timber framed sash window. | 23 Reinstated stair to basement level with completed, traditionally detailed. |
| 03 Non-orthogonal fireplace to be removed and replaced with traditionally-detailed fireplace. | 24 New, single glazed, timber framed window to be installed, fitted with secondary glazing internally. |
| 04 Non-orthogonal skirting/trunking to be removed. | 25 Existing fireplace to be protected and covered. |
| 05 Traditionally detailed, compliant, timber balustrade to reduce existing. | 26 Reconfiguration of existing stair. |
| 06 Existing sash windows refurbished and fitted with secondary glazing internally. | 27 New dummy window. |
| 07 New, double-glazed, timber framed sash windows. Refer to design & access statement. | 28 New double-glazed, traditionally detailed French door. |
| 08 New, double-glazed, timber framed sash windows. Refer to design & access statement. | 29 Linking to party wall. |
| 09 New, double-glazed, timber framed sash windows. Refer to design & access statement. | 30 Proposed lead dormer arrangement to line through with existing windows. Reinstatement of existing non-orthogonal dormer windows. |
| 10 Damaged window sills replaced on a Bar-for-Kiss basis. | 31 Terrace to flat 01, with new planting and Yorkstone paving. |
| 11 Lightwell to be lowered by 100mm, new, painted metal stairs, accommodate level change. | 32 Existing joists to be trimmed out. |
| 12 Existing rear extension retained. New, contemporary brick-clad rear extension to replace existing. | 33 Single, sunken, cast-iron spade to ground floor stair to be preserved and maintained. |
| 13 Proposed bin store. | 34 Single, sunken, cast-iron spade to ground floor stair to be preserved and maintained. |
| 14 New, double-glazed, angled aluminium, restricted lift, framed windows, with etched glass louvers fitted externally. | 35 Existing structural timber beams to be exposed and treated with wood preservative. Ends to be wrapped in DPC and rotten timber to be replaced. |
| 15 New, fixed, double-glazed, angled aluminium framed sliding panels. | 36 Slate to be removed, retained and new membrane installed. Existing slate to be re-laid and any new slates. |
| 16 New, fixed, double-glazed, angled aluminium framed sliding panels. | 37 Facade Refurbishment. |
| 17 New, double-glazed, walk-on rooflight. | 38 Existing facade to be re-rendered and redecorated. |
| 18 New, double-glazed, conservation rooflight. | 39 Etched glass partition. |
| 19 Partial demolition of existing roof, new ridge proposed, matching height and width of existing. | 40 New Railings. |
| 20 New, automatic-opening vent to communal stair. | 41 Fixed & obscure proposed windows. |
| 21 Terrace to the roof of proposed rear extension, with timber decking new planting and walk-around glass balustrade. | 42 Proposed roof. |
| 22 Proposed condensers in attenuated enclosure. | 43 Paint to be removed from brickwork and redecorated as required. |

- Notes
- Guaged Brickwork over window head
 - Painted Hardwood box sash window
 - Painted concrete window cill
 - Outline of window frame behind brickwork
 - Brickwork dressed to front of existing masonry wall
 - Selected brickwork - Reclaimed dark London multi stock matching brick to front of 7 Warwick Court
 - Flat recessed lime mortar pointing
 - Mastic weather seal
 - Historic paneling to be reinstated internally
 - Wall tie fixing new leaf of brickwork to existing structure
 - Render layer to face of existing structure

| | | |
|-------|------------|-------------------------------------|
| Rev B | 28.04.2017 | Issued for Discharge of Condition 3 |
| Rev A | 26.09.2016 | Issued for Planning |
| Rev - | 16.09.2016 | Issued for Planning |

PLANNING

Project No. 14029

Client: GFZ Developments

Date: April 2017

Scale: 1:100 @ A3 / 1:50 @ A1

Project: 7 Warwick Court

Drawing Title: Window Detail - Type E

Drawing No. 300_105 Rev. A

| | | |
|-------|----------|--------|
| Drawn | Approved | Signed |
| DG | TB | AB |

Marek Wojciechowski Architects Ltd.

66-68 Margaret Street W1W 8SR T. 020 7580 9336 www.mwa.co.uk

Copyright Marek Wojciechowski Architects Limited. No limited license exists. This drawing should not be used to calculate areas for the purposes of valuation. All dimensions to be checked on site by the contractor and such dimensions to be their responsibility. No scale drawings shall be used for construction without the written consent of the architect. Drawing errors and omissions to be reported to the architect.