STANHOPE STREET

REFER TO DRAWING NSD335-AL-SW-1-001
REFER TO DRAWING NSD335-AL-SW-1-002

5 No. Angelica sylvestris (As)
7 No. Rudbeckia fulgida Dearnii (Rf)
Bulbs:
55 No. Allium aflatunense
50 No. Allium 'Christophii'

14 No. Iris pallida 'Blue Eyed Brunette' (Ip)
14 No. Perovskia altriplicfolia 'Blue Spire' (Pa)
40 No. Pleiobastus pumilis (Pp)

8 No. Verbena bonariensis (Vb)
Bulbs:
55 No. Allium aflatunense
60 No. Allium 'Christophii'

9 No. Betula jacquemontii (EHS, 18-20cm girth)

REFER TO DRAWING NSD335-AL-SW-1-001
REFER TO DRAWING NSD335-AL-SW-1-002

C05

11 No. Parthenocissus quinquifolia

Habitat Walk:
60 No. Ajuga repens
40 No. Fragaria vesca
30 No. Gallium odoratum
Planted at 400mm staggered centres
175 No. Silene dioica. Planted in swathes through bed
10 No. Polypodium vulgare (Pp)
27 No. Dryopteris filix-mas (Df)

Swale:
230 No. Iris ensata 'Barr Purple East'
85 No. Juncus inflexus
115 No. Caltha palustris

Sensory Planting:
120 No. Lavandula angustifolia 'Hidcote'
21 No. Alchemilla mollis (Am)
18 No. Rudbeckia fulgida Dearnii (Rf)
Bulbs:
145 No. Allium aflatunense
145 No. Allium 'Christophii'

8 No. Stipa gigantea (Sg)
125 No. Stipa tenuissima
30 No. Sedum 'Anthus Joy' (Sa)
32 No. Verbena bonariensis (Vb)
Bulbs:
155 No. Allium aflatunense
155 No. Allium 'Christophii'

130 No. Pleiobastus pumilis
40 No. Iris pallida 'Blue Eyed Brunette' (Ip)
30 No. Perovskia altriplicfolia 'Blue Spire' (Pa)

OPTIONS:
1 No. Eucalyptus debeuzevillei (SM, 20-25cm girth)
1 No. Pinus sylvestris (SM, 20-25cm girth)
1 no. Betula pendula (MS, 20-25cm min. girth)

Pond:
16 No. Butomus umbellatus (15%)
22 No. Caltha palustris (20%)
23 No. Filipendula ulmaria (15%)
18 No. Juncus inflexus (20%)
16 No. Luzula sylvatica (15%)
23 No. Lythrum salicaria (15%)

Shade Garden:
25 No. Ajuga repens
25 No. Gallium odoratum. Planted at 400mm staggered centres
7 No. Luzula sylvatica (Ls)
7 No. Dryopteris filix-mas (Df)
Bulbs:
220 No. Galanthus nivalis, scattered throughout bed
Climbers:
2 No. Hygrandea petiolaris (Hp)

115 No. Fagus sylvatica (2x, 8-10cm girth)

C05

Planted Fragrant Boundary:
35 No. Pachysandra terminalis, planted at 300mm staggered centres
Climbers:
2 No. Clematis armandii (Ca)
1 No. Hydrangea petiolaris (Hp)
2 No. Rosa 'Madame Alfred Carriere' (RM)
Bulbs:
90 No. Allium schoeneprasum scattered throughout the bed
65 No. Tulip 'Queen of the Night' scattered throughout the bed

Planted Fragrant Boundary:
90 No. Pachysandra terminalis, planted at 400mm staggered centres
Climbers:
2 No. Clematis armandii (Ca)
2 No. Hydrangea petiolaris (Hp)
2 No. Rosa 'Madame Alfred Carriere' (RM)
Bulbs:
100 No. Allium schoeneprasum scattered towards front of beds
125 No. Tulip 'Queen of the Night' scattered throughout the bed
1 No. Amelanchier lamarckii (MS, 300cm high)

Orchard Garden:
150 No. Cardemime pratensis
150 No. Primula veris
Bulbs (throughout bed):
2800 No. Narcissus sp.

Habitat Walk:
265 No. Ajuga repens
160 No. Fragaria vesca
105 No. Galium odoratum
Planted at 400mm staggered centres
680 No. Silene dioica. Planted in swathes through bed
20 No. Angelica sylvestris (As)
43 No. Carex pendula (Cp)
18 No. Athyrium filix-femina (Af)
30 No. Dryopteris filix-mas (Df)

7 no. Nymphaea alba
12 No. Gunnera manicata
20 No. Iris ensata 'Barr Purple East'

1 No. Salix alba (Std, 16-18cm girth)

Climber Beds:
3 No. Clematis armandii
3 No. Rosa 'Madame Alfred Carriere'
30 No. Pachysandra terminalis,

5 No. Malus domestica 'Laxton's Fortune'
5 No. Malus domestica 'Egremont Russet'

3 No. Prunus avium 'Plena'

Habitat Walk:
440 No. Ajuga repens
265 No. Fragaria vesca
175 No. Galium odoratum
Planted at 400mm staggered centres
1130 No. Silene dioica. Planted in swathes through bed
20 No. Angelica sylvestris (As)
21 No. Carex pendula (Cp)
10 No. Polypodium vulgare (Pp)
18 No. Dryopteris filix-mas (Df)
Bulbs:
2300 No. Galanthus nivalis, scattered in swathes through bed
Climbers:
3 No. Clematis montana (Cm)
6 No. Parthenocissus quinquifolia (Pq)

2 No. Salix alba (Std, 16-18cm girth)

Woodland & Wetland Garden:
325 No. Ajuga repens
320 No. Gallium odoratum
Planted at 500mm staggered centres
20 No. Angelica sylvestris (As)
27 No. Luzula sylvatica (Ls)
24 No. Dryopteris filix-mas (Df)
Bulbs:
3220 No. Allium ursinum, scattered throughout bed
3000 No. Galanthus nivalis, scattered in swathes throughout bed.
Climbers:
3 No. Clematis montana (Cm)
9 No. Parthenocissus quinquifolia (Pq)

1 m 5 m 10 m

GENERAL NOTES:
1. ALL DIMENSIONS AND LEVELS SHALL BE CHECKED ON SITE PRIOR TO CONSTRUCTION WORK COMMENCING.
2. ALL LANDSCAPE DRAWINGS TO BE READ IN CONJUNCTION WITH ALL RELEVANT ENGINEER'S AND ARCHITECT'S DRAWINGS AND SPECIFICATIONS.
3. ALL DRAWINGS TO BE READ IN CONJUNCTION WITH THE LANDSCAPE SPECIFICATION.
4. ANY DISCREPANCY CONCERNING THE DRAWINGS SHOULD BE REFERED TO THE CA IMMEDIATELY.
5. ALL DIMENSIONS IN MILLIMETRES UNLESS NOTED OTHERWISE
6. ALL LEVELS IN METRES.
7. DO NOT SCALE OFF THIS DRAWING.
8. EXISTING SERVICE ALIGNMENTS SHALL BE CHECKED ON SITE BY THE CONTRACTOR PRIOR TO CONSTRUCTION WORK COMMENCING.

Legend:

- Proposed tree planting. Refer to Plant Schedule 1.0 for full details.
- Hedgerow Planting. Refer to Plant Schedule 2.1 for full details.
- Woodland & Wetland Garden. Refer to Plant Schedule 2.2 for full details. Note: Garden to be with Woodland Edge Mix grass seed, refer to Landscape Specification Q30/317. Individual planting positions noted on drawing.
- Sensory Planting Beds. Refer to Plant Schedule 2.3 for full details. Individual planting positions noted on drawing.
- Productive Beds to Roof Garden. Refer to Plant Schedule 2.4 for full details.
- Stanhope Street Boundary Beds. Refer to Plant Schedule 2.5 for full details. Individual planting positions noted on drawing.
- Habitat Walk. Refer to Plant Schedule 2.6 for full details. Individual planting positions noted on drawing.
- Orchard Garden. Refer to Plant Schedule 2.7 for full details. Note: Garden to be sown with Tussock Grass Seed Mix, refer to Landscape Specification Q30/317.
- Swale. Note separate planting strips are identified within the swale as shown on the drawing. Refer to Plant Schedule 2.8 for full details.
- Pond. Note separate beds are identified within the pond as noted on the drawing. Refer to Plant Schedule 2.9 for full details.
- Willow Tunnel. Refer to Plant Schedule 2.10 for full details.
- Shade Garden. Refer to Plant Schedule 2.11 for full details. Individual planting positions noted on drawing.
- Roof Garden: Planting in proprietary planter bags. Refer to Landscape Specification Q31/296A.

NOTES:

Please read in conjunction with drawings:

NSD335-AL-TZ-1-001 & 002
NSD335-AL-SW-3-001 & 002

& Landscape Specification relevant Sections and Appendix 2: Plant Schedules

Rev.	Date	Description	Drawn	Ch'd
C05	15/07/2014	FOR CONSTRUCTION	CH	AH
C04	12/06/2014	FOR CONSTRUCTION	CH	AH
C03	28/03/2014	FOR CONSTRUCTION	CH	AH
C02	13/05/2013	FOR CONSTRUCTION	RW	AH
C01	01/03/2013	FOR CONSTRUCTION	RW	AH
02	12/10/2012	FOR STAGE 2 (CONTRACTORS PROPOSALS)	RW	AH
01	19/07/2012	For Tender	AT	CH
00	11/06/2012	For Tender	IR	CH

grant associates
Landscape Architecture, Urban Design, Creative Ecology
22 Milk Street, Bath BA1 1DT
T: +44 (0) 1225 332664, F: +44 (0) 1225 420803
E: info@grant-associates.uk.com

CLIENT
BAM CONSTRUCTION

PROJECT
THE NETLEY DEVELOPMENT
NETLEY SCHOOL

TITLE
SOFTWORKS PLAN
SHEET 2 OF 2

C05 AMENDMENTS FOR CONSTRUCTION:.
1. Client changes to F2 fence extents; swale re-positioned.
2. Climber plants re-positioned along Stanhope Street where clouded to align with current PTEa boundary fence layout.

Status:	Drawn:	Checked:
CONSTRUCTION	IR	CH
Scale: 1:125 at A1	Date: 06/06/2012	Approved: PC
Drawing Number: NSD335-AL-SW-1-002		Rev: C05

WILLIAM ROA

FOR CONSTRUCTION