


- FINISHES KEY:**
- Existing concrete flag paving
  - Proposed concrete flag paving Q25/120
  - Existing asphalt
  - Proposed asphalt - Refer to civil engineer's drawing 22479-700, det 1
  - Proposed in-situ concrete paving Q21/110
  - Proposed concrete kerb Refer to civil engineer's drawing 22479-700, det 3
  - Proposed concrete edging Refer to civil engineer's drawing 22479-700, det 4
  - Proposed brass inset strip Q25/120
  - Existing level retained (level shown as example; see plan for spot heights)
  - Existing level (e) revised (level shown as example; see plan for spot heights)

**NOTES:**  
 This drawing does not show reinstatement of public highway pavements inside contractor's hoarding line. Allow for full making good/ replacement of paving and protection/ retention of all existing features within hoarding line and beyond as needed to make a satisfactory continuation to local authority requirements.



B 7.10.15 Issued for TENDER  
 A 28.08.15 Billing issue  
 \* 17.08.15 For billing information (levels)  
 Rev Date Status/Notes

**Tim Ronalds Architects**  
 108 Weston Street, London SE1 3QB  
 tel: 020 7490 7704  
 office@timronalds.co.uk

**Royal Central School of Speech & Drama - Phase 5**  
 Buckland Crescent, Swiss Cottage  
**External Works Plan**

Scale (at A0) Drawn GK Checked AG  
 1:50

**CSD 260 B**