



- Existing brickwork retaining wall below
- Vegetation & tree to be removed
- Guardrail to be removed
- Strip back 300mm of concrete steps, brickwork infill & retaining wall
- Existing concrete post & timber fence to be removed
- Cast iron pipe to be removed and connected to underground drainage
- Bike rack to be relocated
- Existing tree to be removed
- Floor gully to be relocated
- Gas meter to be repositioned
- Existing tree to be removed
- Timber fence & posts to be removed
- Timber kerbs to be removed
- Existing concrete retaining wall in neighbour's property to be kept
- Floor gully to be relocated

REVISION HISTORY			
REV	DESCRIPTION	DATE	DRAWN

- KEY:**
- Items to be removed - - - - -
 - Building footprint
 - Boundary line - . - . -

© Copyright Curl la Tourelle Architects

NOTES:
 All dimensions to be checked on site, not scaled from this drawing.

Any discrepancies on this drawing with other contract documents to be reported immediately to the Contract Administrator for clarification.

CONSTRUCTION

Client
Fitzjohns Primary School

Curl la Tourelle Architects

80 Lambie Street, London NW5 4AB
 tel +44 (0)20 7267 0055
 www.cltarchitects.co.uk

Job
New Office

**86A Fitzjohn's Ave, Hampstead
 NW3 6NP London**

Drawing Title
Demolition site plan

Scale	1:50 @ A1
	1:100 @ A3
Date	Drawn Issued Checked
12.12.2015	AM AM NA
Drg. No.	Rev.
705E	103

