

Notes

1. This drawing shall be read in conjunction with all Mechanical and Electrical drawings, Schedules and Specification.

2. Contractor to allow for on site co-ordination with the structure and other services and the production of fully dimensioned working drawings prior to installation.

3. All equipment to be installed in accordance with the

manufacturers instructions.

4. All Apartment ventilation installations shall be installed in accordance with the building regulation (in particular Parts B, F&L1A), NHBC, BS5588, BS 5925, BS EN 13465.

5. All Apartment ventilation ductwork shall comprise white coloured rigid PVC flat ducting and components in standard sizes of 220x90mm or 204x60mm which correspond to 150mmØ and 100mmØ respectively. Flat duct systems shall be interchangeable with white coloured rigid PVC circular ducting via appropriate adaptors.

6. All changes of direction shall utilize 45° bends wherever possible in order to reduce system resistance and noise due to turbulence. If, 90° bends are utilized they shall not be installed in close proximity to each other and double bend sets shall be avoided. All ductwork shall be secured to the structure via the appropriate channel clips or brackets.

7. Connections to external louvres shall be via bespoke transition pieces manufactured from either rigid PVC sections or galvanised sheet steel, ensuring angle of taper is not greater than 30° and includes at least one internal splitter to even air flow across full face of louvre. All louvre transitions must be thermally insulated and vapour sealed.

8. All ductwork component joists shall be solvent welded socket & spigot arrangements using a suitable PVC solvent adhesive, being sealed completely air tight with white coloured silicone duct sealant and having duct tape applied around the full joint / seam upon completion. All ductwork must be installed to "Class A" pressure slassification as stipulated in HVCA Specification DW144 and achieve an "Intermediate Level" cleanliness standard as defined in HVCA Specification DW/TM2, being tested upon completion and prior to commissioning.

9. Ensure that any rectangular or circular rigid PVC duct passing through a designed fire barrier is provided with an intumescant "Fire Wrap" sleeve having metal collar, capable of fully compressing the ductwork to completely seal the opening and prevent the passage of air. Fire sleeves/collars shall be installed within the opening using the surrounding structure to provide lateral support on all side in operation. All openings for fire sleeves & collars shall be made good with intumescant duct sealant ensuring gaps are completely filled to their full depth or thickness.

10. Kitchen specialist to supply and fit kitchen extract canopy with sufficient duty to meet Part F Building Regulations.

11. FCU plenum and supply ductwork to be internally acoustically treated with pyro foam in accordance with the requirements of the acoustic consultant.

12. All supply & extract ductwork from the MVHR unit to atmosphere shall be insulated.

13. All penetrations through FCU return air plenum are to be hermetically sealed.

Typical Extract Air Valve / Grille

Project Title

Oct'16

Sep'16

T2

KIDDERPORE AVENUE LONDON

Tender Issue. Amendments clouded

Tender Issue

Description

May'16 | Tender Issue

Copyright - This drawing and the designs it represents

are the property of MKP Consultants Ltd and shall not be copied, circulated or issued other than is necessary

to fulfil contractual requirements of the project.

DO NOT scale from this drawing - site measure only.

Attenuator

Extract grille Extract fan

Extract louvre

Mechanical ventilation heat recovery unit

Denotes boundary of ceiling void plenum

Denotes ductwork to be acoustically

Fan coil unit

Set down

Supply grille

Supply louvre

Set up

Supply ductwork Extract ductwork

Fresh air ductwork

Exhaust duckwork

Insulated ductwork

Supply air path

Return air path

Linear slot grille

Legend

EG

EL

FCU

LSG

SD

SU

 $\overline{}$

✓ -

MVHR

Architects layouts do not tie up with Bowler James document: BJB 160518_Skeel_Concept Design Package

Awaiting fire strategy drawing

Drawing Title

SKEEL HOUSE LEVEL 02 **VENTILATION LAYOUT**

MKPCONSULTANTS

ENGINEERING EXCELLENCE

Warren Farm Barn, Andover Road, Micheldever Station, Winchester, SO21 3FL


Tel. 01962 774665, www.mkpg.com

Grille locations to be co-ordinated with reflected

ceiling plans when available

Drawing based on A & Q drawing no.

9000-DRG-03SK-MZ010 - Rev - T1



	Ι	T
Drawn	Date	Checked
LS	MAY'16	GS
Scale	Size	Issue
	1 0 44 0 46	

○ A4 ○ A3 │ ○ Preliminary ● Tender ● A1 ○ A0 │ ○ Construction ○ Contract

9200-DRG-39SK-02001



Approved PΚ