Summary Of Structural Assessment And Strengthening Works Required

The capacity of the existing structural elements have been checked against the required loadings to the Eurocodes. Below is a summary of the assessment identifying any elements which require strengthening as part of the refurbishment works:

Existing Timber Spine Beam Assessment:

The spine wall has been re-supported at 1st floor level on a 203UC steel beam, from analysis this beam is insufficient to support the full height of spine wall and floor beams above so the existing timber floor beams at each level have been assessed.

Bending Stresses @ 230% capacity => strengthening required Deflection @ 200% limit => strengthening required

Refer to Z3-S100.1&2-Detail 1&2

Existing Timber Floor Joist Assessment:

The existing floor joists vary in both depth and width, typically they are 160x60 at 380 c/c. They have been assessed for their maximum span.

Bending Stresses @ 98% capacity Deflection @ 160% limit => strengthening required

Refer to Z3-S100.1-Detail 1

Existing Stair Beam Assessment:

The stair wall is not supported below first floor level so the existing timber floor beams at each level have been assessed.

Bending Stresses @ 140% capacity => strengthening required Deflection @ 200% limit => strengthening required

Refer to Z3-S100.7-Detail 9

Existing Floor Beam Assessment:

The existing timber floor beam at each level have been assessed.

Bending Stresses @ 110% capacity => strengthening required Deflection @ 200% limit => strengthening required

Refer to Z3-S100.5-Detail 6

Existing Floor Movements:

From survey spot levels the existing floor structure has settled/deflected by up to 100mm at each floor level. Strengthening Works are required to ensure to further settlement occurs





+44 (0)20 7089 5760

Tower Bridge Road London SE1 3JB

project name					
9 Denmark Street					
sketch title	^{date} 15 09 2017				
Поро	15.05.2017				
project no 879	sketch no Z3-S-100.0	rev -	ĸ		

₽

Option A:

-This option provides the required strengthening to the existing spine beam while minimising impact on the historic finishes. -This option does require the existing floor beams to be trimmed and

re-supported on the new steelwork

- Option A is considered to have the least impact on the historic building

fabric while achieving the required structural strengthening



Detail 1: Spine Beam & Joist Strengthening Requirements, 1:10 Option A

Structural Strengthening Requirements:

- The existing spine wall beam can not be justified to support the required residential loadings to current standards therefore strengthening is required. - The existing floor joists require strengthening due to comply with current standards and allow for levelling of existing floors

- Generally all structural strengthening proposed will reduce deflections and movements within the building to protect the historic structure and materials form further damage

- Steel beams to bear onto padstones in masonry party walls



engenuiti



Detail 3: Spine Beam & Joist Service Penetration, 1:10

Structural Strengthening Requirements:

NOTES

- The strengthening is required to allow the waste pipe from the proposed kitchen island unit to run through the floor zone. The island unit is required to avoid any damage to historic wall finishes

- The service run for the kitchen waste pipe will effect a maximum of 3 joists and the spine beam at each level





₽



-

Tower Bridge Road London SE1 3JB United Kingdom

engenuiti

+44 (0)20 7089 5760 www.engenuiti.com

NOTES





NOTES



₽





∠ waitings Place Tower Bridge Road London SE1 3JB United Kingdom

+44 (0)20 7089 5760 www.engenuiti.com





Figure 7, Typical Cracked Masonry Repair - Third Floor Party Wall Shown

Structural Repair Works:

NOTES

- Cracked bricks to be replaced with bricks and mortar to match existing construction

- Helibar crack repair bars to be installed to bed joints at every 5th course to avoid future cracking

- Timber within masonry walls to be removed and bricked in to avoid future settlement or decay



Figure 8, Typical Masonry Reveal Repair - First Floor Half Landing Shown

- Masonry to be made good with bricks and mortar to match existing construction

Structural Repair Works:



RK

879

Z3-S-100.8



+44 (0)20 7089 5760 www.engenuiti.com



Figure 10, Location Of Panelling To Be Removed - Second Floor Stair Wall

Structural Investigation Requirements:

- The existing staircase has settled significantly and we need to inspect the connection of the staircase to the stair wall and assess whether additional strengthening is required



Figure 11, Location Of Panelling To Be Removed - Second Floor Spine Wall Structural Investigation Requirements:

- The base and head of the existing timber stud wall needs to be inspected to confirm whether any remedial works are required

engenuiti

+44 (0)20 7089 5760 www.engenuiti.com

2 Maltings Place Tower Bridge Road London SE1 3JB United Kingdom

NOTES

9 Denmark Street						
sketch title Propos	^{date} 25.08.2017					
project no 879	sketch no Z3-S-100.9	rev -	^{by} RK			

Existing Non-Structural Additions To Be Removed





Figure 12, Third Floor Non-Structural Additions

Non-Structural Items To Be Removed:

- By inspection it is apparent that almost all of the white painted timber joinery inside the plaster finish line is a decorative add-on and non-structural in nature. As such this can be removed.

- The only exception are the posts supporting each end of the roof beam high lighted above.

Figure 13, Third Floor Non-Structural Additions Non-Structural Items To Be Removed:

- The white timber work to the ceiling has splice joints which have rotated and are not designed to be load-bearing



Figure 14, Third Floor Non-Structural Additions Non-Structural Items To Be Removed:

non-structural

ower Bridge Road London SE1 3JB



+44 (0)20 7089 5760 www.engenuiti.com

- The apparent main white timber beam to the underside of the ceiling is formed of timber sheets and is hollow, by inspection this element is

project name						
9 Denmark Street						
Proposed Structural Works			^{date} 25.08.2017			
project no 879	sketch no Z3-S-100.10	rev -	RK			