

Tree Work Specification For
St Michael's Vicarage
London, N10

T1	Ash	Fell to ground level & grind out stump Reason for work: This tree is an inappropriately located sapling
T4	Cherry	Fell to ground level & grind out stump Reason for work: Tree has a poor union at 1.6m and compromised/Suppressed form
T5	Cherry	Crown thin 10% Remove deadwood Reason for work: Maintenance works in line with good Arboricultural practice
T6	Plum	Fell to ground level & grind out stump Reason for work: <i>Tree is sited on boundary, fallen / rested on fence and is heavily suppressed with poor form</i>
T11	Bay Laurel	Remove all basal epicormic growth retaining / highlighting main stems Crown lift remaining low growth to 3m Crown thin 10% Remove previously stacked debris at base of tree Crown reduce height 30% (max 3m branch lengths) Crown reduce spread 20% (max 2m branch lengths) Remove any remaining deadwood Reason for work: Maintenance works in line with good Arboricultural practice
T15	Weeping Ash	Reduce over-extended lateral to south over driveway 20% (branch lengths of up to 2.5m) to balance Reduce height 15% to suitable points / weeping layer (branch lengths of up to 1.6m) to provide more compact shape Crown thin 20% Remove deadwood Reason for work: Maintenance works in line with good Arboricultural practice
T17	Yew	Prune lateral spread to garden by up to 1-1.2m to Retain pleach / hedge form Reason for work: Maintenance works in line with good Arboricultural practice

- | | | |
|-----|-----|--|
| T18 | Yew | Prune lateral spread to garden by up to 1-1.2m to Retain pleach / hedge form
Reason for work: Maintenance works in line with good Arboricultural practice |
| T19 | Yew | Prune lateral spread to garden by up to 0.8-1.0 to Retain pleach / hedge form
Reason for work: Maintenance works in line with good Arboricultural practice |
| T21 | Ash | Fell to ground level & grind out stump
Reason for work: Situated adjacent to the garage, the tree is inappropriately located for the species |