



| Door Schedule | | | | | | | | | | | |
|---------------|------------|----------|--------|-----------|--------------|------------|----------------|------------|-------------|------------|-----|
| Mark | Leaf Size | Openings | | | | Door Frame | | | Fire Rating | | |
| | | Width | Height | Thickness | SO Width | SO Height | Door Operation | Slab Style | Jamb Thick | Jamb Depth | Min |
| D-L2-01 | 826 x 2058 | 44.0 | 910 | 2100 | Swing Simple | Solid | 35 | 100 | | | |
| D-L2-02 | 726 x 2058 | 44.0 | 810 | 2100 | Swing Simple | Solid | 35 | 120 | | | |
| D-L2-03 | 726 x 2058 | 44.0 | 810 | 2100 | Swing Simple | Solid | 35 | 120 | | | |
| D-L2-04 | 826 x 2058 | 44.0 | 910 | 2100 | Swing Simple | Solid | 35 | 100 | | | |
| D-L2-05 | 826 x 2058 | 44.0 | 910 | 2100 | Swing Simple | Solid | 35 | 100 | | | |
| D-L2-06 | 910 x 2100 | 44.5 | 910 | 2100 | Swing Simple | Solid | 35 | 120 | | | |
| D-L2-07 | 910 x 2100 | 44.5 | 910 | 2100 | Swing Simple | Solid | 35 | 120 | | | |

- Wall Types**
- Glazed Screen (K30/I30) + (K30/I131)
 - Metal stud partition (K10/I25)
 - Existing wall to be made good and redecorated
- Floor Finishes**
- New Carpet Tile (M50/I30)
 - Vinyl (M50/I50)

CDM Information
 The following information is provided in pursuance of the CDM Regulations. The information is to be read in conjunction with the Designers Hazard Log.

- Used to warn of significant design hazards and site risks
- Used to avoid or prevent a particular action
- Used to encourage a particular action
- Used to convey some relevant CDM information

Risk No. Description of Residual Hazard & Risk

The purpose of this schedule is to identify significant risks, not necessarily those that involve the greatest risks, but those (including health risks) that are not likely to be obvious, are unusual, or likely to be difficult to manage effectively.

General Asbestos is present in the building. Refurbishment survey to be undertaken prior to any investigations or works.

- 2.1 Low ceiling in study desk area: Head Injury
- 2.10 Lone working in basement level: Risk of shelving tipping over, Serious injury.
- 2.11 Installation of free standing lockers: Risk of lockers tipping over, Serious injury.
- 2.12 Working in close proximity to exposed pipes and electrical services: Serious Injury, death

| Revision | Date | Amendment | Notes |
|----------|----------|----------------------|-------|
| / | 10.11.17 | Planning Issue | |
| A | 22.11.17 | Final Planning Issue | |

| | | | |
|------------|----------------------------|------------------------|------------|
| Client | UoL | Burwell Deakins | |
| Project | IALS Refurbishment Project | | |
| Drawing | Proposed L2 Floor | | |
| Scale | 1:100 @ A1 | Drawn | GB |
| Date | November 2017 | | |
| Project N° | 739 | Drawing N° | 739-PL-031 |
| | | Revision | A |

info@burwellarchitects.com
www.burwellarchitects.com

Unit 0.01
California Building
London SE13 7SF
+44 (0) 2083 056010

First Floor
8 Southendway
West Exeter EX1 1JG
+44 (0) 1392 423981

NO DIMENSIONS ARE TO BE SCALED FROM THIS DRAWING. THE CONTRACTOR/MANUFACTURER IS RESPONSIBLE FOR CHECKING ALL DIMENSIONS AND QUERING ANY DISCREPANCIES. THIS DRAWING IS THE PROPERTY OF IDA ARCHITECTS LTD. COPYRIGHT IS RESERVED BY THEM AND THE DRAWING IS ISSUED ON CONDITION THAT IT IS NOT COPIED, REPRODUCED, RETAINED OR DISCLOSED TO ANY UNAUTHORISED PERSON, EITHER WHOLLY OR IN PART, WITHOUT WRITTEN CONSENT.