

Photographic Schedule – Pioneer House



Front elevation – Existing railings on left and timber fencing on right. Both types of fencing are to be removed and replaced with metal railings with a height of 1200mm.



Left side elevation – Existing railings with a height of 1000mm are to be removed and replaced with like for like railings with an increased height of 200mm. Total new railing height is 1200mm. The brick piers heights are to be increased by approximately 280mm.



Detail of existing railing and pier



Right side elevation – Timber fence panels are to be replaced with metal railings as per the front elevation.