








Legend


-  Red Line Boundary
-  Architects Plan
-  200mm Halestern Edge by EverEdge or Equivalent Approved
-  Green Roof
-  Pedestal Mounted Marshalls 450x450mm Rivero Urban Silver Paving Slabs
-  Log Pile- Refer To Ecologists Biodiversity Enhancement Plan for more details
-  Detail Tags- Refer to Drawing CS093348-L-300 and CS093348-L-301 for more Detail

Notes

1. Roof substrate specification:
 - 30% washed South Cemey gravel with stones (15cm diameter) placed regularly across the surface
 - 20% finely crushed clean brick (less than 5 cm diameter) (no engineering brick)
 - 10% shale
 - 30% standard grade grit sand
 - 10% well-rotted leaf compost

Depth: uneven 200mm average depth (150mm minimum)
2. Engineered lightweight soil specification

Soil to be in accordance with BS 3882:2015 and to include a 60-85% fine to medium sand content and be peat free.



Rev | Date | By | Notes

Client
Stadium Capital Holdings

Project
Midland Crescent

Drawing Title
**Fifth Floor
General Arrangement Plan**

Drawing Status
FOR PLANNING

Scale	Date	Drawn
1:200 @A1	Sep' 2017	CC
Drawing No	Checked	Approved
CS093348-L-008		NM

CAPITA

Property and infrastructure
T+44 (0)121 423 6060
1st Floor, Eleven Brindleyplace, 2 Brunswick Square
Birmingham, B1 2LP www.capita.co.uk/property
Capita Property and Infrastructure Ltd