



KEY:				
	Proposed Yorkstone paving to be installed on 50mm sand/mortar and 100mm ST1 concrete base except around perimeter of loading bays where site engineer will specify extents of 150mm ST1 concrete base.		EG Existing gullies to be removed.	
	5 colour mix granite sets (250x150x150mm) built on 50mm thick sand/mortar and a bed of 200mm thick base.			PG Proposed new gullies to be connected to the existing gullies
	Loading bay: grey granite sets (200x100x150mm) 50mm thick sand/mortar and a bed of 200mm thick base			Existing service covers to be raised to match new levels. Inset covers for footways' covers. D400 covers for the carriageways.
	Proposed new 150x300mm flat granite kerbs to be flush			Area to be replaced by ASP paving slabs.
	Proposed new 150x300mm edge granite kerbs			Refer to drawing No:
	Proposed new dropped kerb			Area falls under the Cambridge Circus scheme by WCC

Camden
 Design Team
 Transport Strategy Service
 London Borough of Camden
 Town Hall, Argyle Street
 London WC1H 8EQ
 Tel 020 7278 4444, Fax 020 7974 6952
 DX 2106 Euston, Minicom 020 7974 6866

Project
**EARLHAM STREET WEST
 PROPOSED PUBLIC REALM IMPROVEMENTS**

Drawing Title
**DETAILED DESIGN
 GENERAL ARRANGEMENT PLAN
 SHEET 1 OF 2**

Scale	NTS	Date	June 2017
Drawn By	J.M.	File Ref	
Checked By		Dwg Name	
Drawing Location			
Drawing Number	TS1311/200/2017	Rev.	-
Rev	By	Date	Amendments

T:\Cot_Schms\2014-15\CN\Earlam Street\13 - Detail Design\drawing