Job Number: 170823



14 February 2018

Addendum

The retaining walls for the permanent structure will have a high level of stiffness.

This can be achieved by propping the wall at the head by the ground floor structure:

- Steel beams at the head of the retaining walls provide the propping required.
- The distance between the adjoining steel beams are considered small enough to allow the retaining walls to span between them and transfer horizontal loads to the ground floor steelwork
- The steel arrangement is shown on revised drawings (SL-10-Rev2 and SL-20-Rev2)


An alternative design solution is to design the walls to be stiff enough to reduce the deflections to an acceptable minimum, without the need for propping at the head. The following calculations show that the deflection resulting ground movements will be close to negligible.

For both options, the predicted Damage Category will be 0 or 1.

	Project				Job Ref.	
	6 Parsifal road				170823	
Croft Structural Engineers Rear of 60 Saxon Rd	Section			Sheet no./rev.		
	Structural calculation for BIA				14	
Selhurst	Calc. by	Date	Chk'd by	Date	App'd by	Date
SE25 5EH	EP	14/02/2018				

RETAINING WALL DEFLECTION

Simlar loads will be applied as shown in the previously submitted calculations walls, ie



For permanent structure, there is structural continuity between the base of the wall and the basement slab. The wall is now analysed as a cantilevered beam. Calculations below are for SLS to find deflections.

CONCRETE BEAM ANALYSIS

Concrete beam dimensions:-

Beam width b = 1000 mm

Beam depth h = 300 mm

Cross-section area $A = b \times h = 300000 \text{ mm}^2$


Major axis second moment of area $I_{xx} = b \times h^3 / 12 = 2.25 \times 10^9 \text{ mm}^4$


 $f_{cu} = 35 \text{ N/mm}^2$

 $E = 20 \text{ kN/mm}^2 + 200 \times f_{cu} = 27.0 \text{ kN/mm}^2$

 $\rho = \rho_{C.norm} = \textbf{2400} \text{ kg/m}^3$

Ref BS8110:1985:Pt 2 - Eq 17





CONTINUOUS BEAM ANALYSIS - INPUT

BEAM DETAILS

Number of spans = 1

Material Properties:

Modulus of elasticity = **27** kN/mm² Material density = **2400** kg/m³

Support Conditions:

Support A Vertically "Restrained" Rotationally "Restrained"

Support B Vertically "Free" Rotationally "Free"

Span Definitions:

Span 1 Length = 2900 mm Cross-sectional area = 300000 mm² Moment of inertia = 2.25×10⁹ mm⁴

LOADING DETAILS

Beam Loads:

Load 1 VDL Live load 40.0 kN/m to 1.2 kN/m

LOAD COMBINATIONS

Load combination 1

Span 1 $1 \times Dead + 1 \times Live$

CONTINUOUS BEAM ANALYSIS - RESULTS

Support Reactions - Combination Summary

Support AMax react = -59.7 kNMin react = -59.7 kNMax mom = -59.4 kNmMin mom = -59.4 kNmSupport BMax react = 0.0 kNMin react = 0.0 kNMax mom = 0.0 kNmMin mom = 0.0 kNm

Beam Max/Min results - Combination Summary

Maximum shear = 59.7 kN Minimum shearF_{min} = 0.0 kN Maximum moment = 0.0 kNm Minimum moment = 0.0 kNm Minimum deflection = 0.0 mm Minimum deflection = 0.0 mm

Span Max/Min results - Combination Summary


Span 1 Maximum shear = 59.7 kN at 0.000 m Minimum shear = 0.0 kN at 2.900 m


Maximum moment = **0.0** kNm at **2.900** m

Maximum deflection = **1.7** mm at **2.900** m


Minimum moment = **-59.4** kNm at **0.000** m


Minimum deflection = **0.0** mm at **0.000** m






Deflection at top of wall is less than 1.7mm. This does not account for the vertical load applied to the top of the retaining wall, which would limit the deflection further. By inspection, the deflection of a 300mm thick reinforced concrete wall will not give rise to ground movements and resulting damage categories greater than Category 1.





Section 1-1 Scale 1:50



Section 2-2 (Scale 1:50)

Planning issue Not for construction

Job Number	Date
170823	Oct '17
Dwg Number	Rev
SL-10	2
Drawn	Ch'kd
SB	l EP
Scale As show	vn
@ A3	

Client: Stephan Wilcke	
Project: 6 Parsifal Rd	
Title: Basement Plan	


and Section

2	14/02/18	Minor amendment to Section 2-2 to show wall propping option
1	16/10/17	minor amendments to Architects comments
-	06/10/17	First issue preliminary to Architect
Rev	Date	Amendments



London, SE25 5EH. 020 8684 4744 www.croftse.co.uk





Planning issue
Not for construction

2	14/02/18	Steel work altered to show wall propping option
1	16/10/17	minor amendments to Architects comments
-	06/10/17	First issue preliminary to Architect
Rev	Date	Amendments

Job Number	Date
170823	Oct '17
Dwg Number SL-20	Rev 2
SB, GW	EP, GW
Scale As show	vn

@ A3

Client: Stephan Wilcke
Project: 6 Parsifal Rd

1 Tojosti o i aromarita

Title : Ground Floor Plan

Croft
Structural
Engineers

Clockshop Mews, r/o 60 Saxon Rd, London, SE25 5EH. 020 8684 4744 www.croftse.co.uk

