

Project UCLH Birkbeck University MRI			Status Information	
Date 22/02/2018	Job no. 70038590	Section	Sheet no. 1 of 1	Rev 01
By NP				
Checked MB				
Rev 01	Date 22/02/2018	Details		
Part Plant Compound Steelwork				



REF OUTPUT

Text

Section

Baseplate

NOTE
COMPOUND STEELWORK TO BE GALVANISED

MAXIMUM SPACING OF COLUMNS TO BE 3500mm

420x420x20THK BASEPLATE
4No. M24 RESIN ANCORS.
250mm EMBEDMENT
100mm PREJECTION