

Current 43



Proposed 43



Patio + alleyways between flower beds:

Preparing the base for over 22sqm:

- Excavation to formation level (250mm under damp proof course);
- Laying down a geo-membrane;
- Additional Tp1 sub-base;
- Laying down the slates;
- Slates to be laid on a concrete base;
- Slates to be pointed with EasyJoint;
- High channels to be installed;
- Domestic soak away to be installed for drainage of rainwater (in compliance with SUDS);

Remove the excess height to bring to one level



Terraced flower beds to be built using sleepers;