

# Technical Note

---

Project:	<b>Mount Pleasant – Phoenix Place</b>	Job No:	<b>60556156</b>
Subject:	<b>Approval In Principle to Camden Highways</b>	Revision:	<b>02</b>
Prepared by:	<b>Rob Mattimoe</b>	Date:	<b>02/03/2018</b>
Checked by:	<b>David Cuckow</b>	Date:	<b>02/03/2018</b>
Approved by:	<b>Darran Leaver</b>	Date:	<b>02/03/2018</b>

---

This document relates to the permanent works associated with the above project only, with periodic reference to the temporary works where prompted and as necessary. A separate AIP for the temporary works will be issued by the Principle Contractor.

The proposed development, in the permanent condition, should not adversely affect the surrounding highways. Both the substructure and superstructure is arranged within the site boundary, with the foundations set back from said boundary to allow for construction tolerances, temporary works and protection of the existing highway as necessary. The key aspect of the development that will pose a risk to the highway is the 2 storey basement and the key consideration in the design and construction of this basement will be to prevent the surrounding ground from being undermined or made unstable – that is one of the primary reasons that a secant piled wall has been proposed for the basement box, as it acts as a permanent formwork to a basement space.

Structural and Geotechnical Design has been progressed to a RIBA Stage 3 level of information and through the next design stage further analysis of the secant pile wall in particular will be made so that horizontal movements can be accurately predicted. At present the maximum horizontal deflection of the secant pile wall (at capping beam level) is 15mm. Since this value is less than typical construction tolerances for foundations it is deemed to be acceptable. The outer face of the secant piles and of the capping beam at their head is further than 3m from the kerb line of each of the three highways that bound the site.

The below headings have been extracted from the Camden Highways AIP template, with responses given in **bold** text. Whilst the template seems to be generic, in that it can be used for new bridges over the highway etc. as well as new developments adjacent the highway, every effort has been made to complete all sections clearly.

## 1. HIGHWAY DETAILS

### 1.1 Type of Highway

#### **Gough Street (to the West of the site)**

- Southern section of the highway (between junctions with Coley Street and Mount Pleasant) is a one-way, single lane carriageway with traffic heading south (towards the junction with Mount Pleasant).
- There is an existing vehicular crossover onto the site which has been blocked off with large concrete blocks and a security gate.
- Northern section (above junction with Coley Street) of the highway is a wider two-way carriageway.
- There are parking bays along the East kerb, alongside the entirety of the site boundary (except for at the junction with Coley Street which occurs approximately half way along the site boundary).
- To the South of the junction with Mount Pleasant the highway becomes Laystall Street.
- The highway terminates in a 'dead end' where it meets Calthorpe Street to the North.

#### **Mount Pleasant (to the South of the site)**

- Two-way carriageway.
- There are 2no. existing vehicular crossovers onto the site. Neither are in use and both have been blocked off with large concrete blocks or security gates.
- There are parking bays along the North kerb, alongside the entirety of the site boundary.
- There are several parking bays for solo motorcycles on the South kerb.
- To the West of the junction with Gough Street the highway becomes Elm Street (a one-way carriageway heading west becoming a two-way carriageway).
- To the East of the junction with Phoenix Place the highway continues as Mount Pleasant.

#### **Phoenix Place (to the East of the site)**

- Two-way carriageway.
- There are 3no. existing vehicular crossovers onto the site. All are gated and in use by Royal Mail Group to access the site (entire site is currently used for parking Royal Mail Group vehicles).
- In addition to the crossovers mentioned above there are 2 no. redundant vehicular crossovers onto the site where the boundary wall has been permanently bricked up.
- There are parking bays along the West kerb, alongside the entirety of the site boundary.
- To the South of the junction with Mount Pleasant the highway becomes Warner Street
- To the North of the junction with Calthorpe Street the highway becomes Pakenham Street

### 1.2 Permitted Traffic Speed

**AECOM understand that all roads maintained by Camden Council have a 20pmh speed limit. Since there is no evidence of the roads surrounding the site being private roads or Transport for London Road Network (TLRN) 'red routes' it is assumed that the permitted traffic speed on Gough Street, Mount Pleasant and Phoenix Place is 20mph.**

### 1.3 Existing Restrictions

- **There is a Waiting Restriction in place along Mount Pleasant, Phoenix Place and on the one-way section of Gough Street (between junctions with Coley Street and**

Mount Pleasant). The restriction is due to a local School and is active between 6:30pm and 8:00am for goods vehicles over 5 tonnes and for buses and coaches.

- In addition to the above restriction there is a waiting restriction on all vehicles along Mount Pleasant and Phoenix Place between 8:30am and 6:30pm on Monday to Friday and between 8:30am and 1:30pm on Saturday.
- There is a No Loading Restriction in place along Phoenix Place. The restriction is active between 8:30am and 6:30pm on Monday to Friday and between 8:30am and 1:30pm on Saturday.

## 2. SITE DETAILS

### 2.1 Obstacles Crossed

**The site does not cross any active highways. It is bound by Gough Street to the West, Mount Pleasant to the South and Phoenix Place to the East.**

## 3. PROPOSED STRUCTURE

### 3.1 Description of structure and design working life

**The proposed structure is a residential development varying in height from 4 to 13 storeys with 2 storey basement car park. Residential units arranged in a horseshoe configuration around a central landscaped podium, with pedestrian access out onto the highway via the two ends of the horseshoe. Basement car park will be accessed via a ramp on Gough Street. The new build structure has been designed and specified to meet a minimum 50 year design life (subject to approval from NHBC).**

### 3.2 Structural type

**Reinforced concrete frame with flat slab (to be constructed in-situ).**

### 3.3 Foundation type

**Secant pile wall forming basement box (along Highways on 3 sides) with bearing piles under columns and stability cores within footprint of basement.**

### 3.4 Span arrangements

**Columns in basement areas are arranged to suit a car park layout (typically on a 6m x 8m grid).**

### 3.5 Articulation arrangements

**The secant pile walls that form the basement run within the site boundary, along Gough Street to the West, Mount Pleasant to the South and Phoenix Place to the East. Secant piles will be designed as propped cantilevers. The outside face of the secant piles is positioned more than 3m away from the nearest kerb line in all cases.**

### 3.6 Road restraint systems requirements

**Refer to Landscape Architect, Transportation Engineer and Highways Engineers layouts for requirements and details of road restraint systems. Under the conditions as outlined in the Building Regulations (Part A) the proposed building will be class 2B since it will be greater than 4 stories in height. As such, the structure will be designed so that effective vertical ties are provided in all concrete columns and an assessment will be made into the removal of key structural elements (from vehicular impact etc.).**

### 3.7 Proposed arrangements for future maintenance and inspection/Inspection for Assessment:

#### 3.7.1 Traffic management

**N/A – Structure does not cross the Highway and therefore no inspection of the superstructure or substructure will be necessary from the Highway.**

#### 3.7.2 Arrangements for future maintenance and inspection of structure

Access arrangements to structure

**N/A – Structure does not cross the Highway. All access to the structure for inspections will be from within the site boundary.**

3.7.3A Intrusive or further investigations proposed

**None**

3.8 Environment and sustainability

**AECOM have reviewed the constituents of a standard concrete mix with a view to offer suitable alternatives that would satisfy the requirements of a BREEAM, Code for Sustainable Homes (CfSH) or Home Quality Mark (HQM) assessment. The following mix design is proposed;**

<b><u>Constituent</u></b>	<b><u>Proposed Measure</u></b>
<b>Cement</b>	<b>Up to 50% GGBS Substitution (i.e. CEM IIIA)</b>
<b>Coarse Aggregate</b>	<b>Minimum 10% Stent Substitution</b>
<b>Fine Aggregate</b>	<b>Glass Sand Substitution</b>

3.9 Durability. Materials and finishes/Materials strengths assumed and basis of assumptions.

**Concrete in contact with the ground will require a high resistance to attack arising from the salinity levels within the ground water. Concrete Grade to be used throughout the substructure and superstructure:**

<b><u>Location</u></b>	<b><u>Grade</u></b>	<b><u>Special Requirements</u></b>
<b>Foundations</b>	<b>C35/45</b>	<b>Sulphate resisting cement</b>
<b>Slabs in contact with the ground</b>	<b>C35/45</b>	<b>Sulphate resisting cement Waterproof concrete</b>
<b>Slabs generally</b>	<b>C35/45</b>	<b>None</b>

3.10 Risks and hazards considered for design. Execution, maintenance and demolition.

Consultation with and/or agreement from CDM co-ordinator

**Refer to AECOM Designers Risk Assessment appended to this document**

3.11 Estimated cost of proposed structure, together with other forms considered (including where appropriate proprietary manufactured structure), and the reasons for their rejection (including comparative whole life costs with dates of estimates)

**Construction costs are to be advised by Principle Contractor. Refer to AECOM's Basement Walls Options Study (appended to this document) which compares different construction techniques.**

3.12 Proposed arrangements for construction

**To be advised by Principle Contractor**

3.12.1 Construction of structure

**Final construction methodology is to be advised by the Principle Contractor. AECOM have made assumptions as to the build sequence for the secant pile wall and the basement box that it confines. These assumptions are appended to this document.**

3.12.2 Traffic management

**To be advised by Principle Contractor**

3.12.3 Service diversions

**To be advised by Building Services Engineer and Principle Contractor**

3.12.4 Interface with existing structures

**N/A. At the time of writing, the site has been cleared of buildings, leaving some boundary walls and a number of ground levels linked by ramps as a legacy of a past use as a carpark. Existing walls within the site boundary are to be demolished prior to construction of the substructure and replaced with a suitable hoarding. The Fleet River Culvert which runs beneath Phoenix Place to the east of the site.**

- 3.13 Year of Construction  
**Construction works planned to commence in 2018**
- 3.14 Reason for assessment  
**To confirm that the construction of the two storey basement will have negligible, if any, impact on the adjacent highways that bound the site.**
- 3.15 Part of structure to be assessed  
**Secant pile wall**

4 DESIGN/ASSESSMENT CRITERIA

4.1 Actions

4.1.1 Permanent actions

**No vertical loads to be applied to the highway. Quasi Permanent loads within the boundary, on ground floor podium slab = 11.0 kN/m<sup>2</sup> (including saturated topsoil, planting, paving, waterproofing, insulation and suspended services) but these loads will be transmitted into the secant pile wall.**

**A ground surcharge force of 10.0 kN/m<sup>2</sup> has been assumed to act on the secant pile wall (SLS).**

**The ground earth pressure has been taken as 59.9 kN/m<sup>2</sup> at +7.10 mOD.**

**The ground water pressure has been taken as 56.5 kN/m<sup>2</sup> at 7.10 mOD.**

4.1.2 Snow, wind and thermal actions

**There will be no net uplift in snow, wind and thermal actions on the highway as a result of the proposed development.**

4.1.3 Actions relating to normal traffic under AW regulations and C&U regulations

**N/A**

4.1.4 Actions relating to General Order Traffic under STGO regulations

**N/A**

4.1.5 Footway or footbridge variable actions

**Footway loading = 5.0 kN/m<sup>2</sup>**

4.1.6 Actions relating to Special Order traffic, provision for exceptional abnormal indivisible loads including location of vehicle track on deck cross-section

**N/A**

4.1.7 Accidental actions

**Accidental loading = 20.0 kN surcharge**

4.1.8 Actions during construction

**It is assumed that the secant pile wall will be fully propped in the temporary construction case, until the permanent slabs are constructed that will provide restraint in the permanent case.**

**Principle Contractor to advise is mobile cranes (and their associated outriggers) or other heavy construction vehicles will be positioned close to the secant pile wall during construction.**

4.1.9 Any special action not covered above

**Vibration from construction activity: It is proposed that the secant pile wall be constructed with a CFA or rotary bored auger rig i.e. those of a non-vibratory nature. Driven piles, impact hammer or vibrating hammer piles will not be used.**

4.2 Heavy or high load route requirements and arrangements being made to preserve the route, including any provision for future heavier loads or future widening

**To be advised by Principle Contractor**

4.3 Minimum headroom provided

**N/A – no structures proposed over the highway.**

4.4 Authorities consulted and any special conditions required

**London Borough of Camden have confirmed that the maximum horizontal deflection at ground level = 25mm.**

4.5 Standards and documents listed in the Technical Approval Schedule

- **BS EN 1990-2002 - Eurocode 0 - Basis of structural design**
- **BS EN 1991-1-1:2005 – Eurocode 1: Densities, Self-weight and Imposed Loads**
- **BS EN 1991-1-2:2005 – Eurocode 1: Actions on Structures Exposed to Fire**
- **BS EN 1991-1-3:2005 – Eurocode 1: Actions on Structures – Snow Loads**
- **BS EN 1991-1-4:2005 – Eurocode 1: Actions on Structures – Wind Actions**
- **BS EN 1991-1-5:2005 – Eurocode 1: Actions on Structures – Thermal Actions**
- **BS EN 1991-1-6:2005 – Eurocode 1: Actions on Structures – Actions During Execution**
- **BS EN 1991-1-7:2005 – Eurocode 1: Actions on Structures – Accidental Actions**
- **BS EN 1992-1-1:2004 – Eurocode 2: Design of Concrete Structures: Common rules for building and civil engineering structures**
- **BS EN 1992-1-2:2004 – Eurocode 2: Design of Concrete Structures: General Structural Fire Design**
- **BS EN 1997-1 -2004 – Eurocode 7: Geotechnical: General Rules**
- **BS 8002:1994 (2001) – Code of Practice for Earth Retaining Structures.**
- **BS 8102:2009 - Code of practice for protection of below ground structures against water from the ground**
- **CIRIA C760: Guidance on embedded retaining wall design**
- **CIRIA Report 143 (1995). The Standard Penetration Test (SPT): Methods and Use**
- **Institution of Civil Engineers Specification for Piling and Embedded Retaining Walls (SPERW) dated 2016, third Edition:**
  - Section B1 General Requirements for Piling Work**
  - Section B11 Secant Pile Walls**
  - Section B15 Integrity Testing**
  - Section B19 Instrumentation for Piles and Embedded Retaining Walls**

4.6 Proposed Departures relating to departures from standards given in 4.5

**N/A**

4.7 Proposed departures relating to methods for dealing with aspects not covered by 4.5

**N/A**


## 5. STRUCTURAL ANALYSIS

5.1 Methods of analysis proposed for superstructure, substructure and foundations.

**Secant pile wall has been modelled and analysed using Wallap software. Superstructure has been modelled and analysed using SCIA Engineer finite element software**

5.2 Description and diagram of idealised structure to be used for analysis

**Typical section through secant pile wall illustrating the assumed arrangement of temporary works:**



### 5.3 Assumptions intended for calculation of structural element stiffness

- **The perimeter of the basement box will be formed by a 750mm diameter secant wall using hard-firm piles with a 150mm interlock i.e. at 600mm centres. The inside face of the secant wall will receive a waterproof membrane that will be protected by a waterproof concrete lining wall. The central part of the basement will be supported on internal 750mm diameter bearing piles arranged in caps under columns and stability cores.**
- **Secant wall along Gough Street will be supported by 2 levels of temporary props at +11.00 mOD and +14.50 mOD until the lower and upper ground floor slabs have been constructed.**
- **Secant walls along Mount Pleasant and Phoenix Place will be supported by a single level of temporary props at approx. +13.00 mOD until the Lower Ground floor slab has been constructed.**
- **Formation level has been assumed between 7.95 mOD – 8.90 mOD along the Phoenix Place elevation (i.e. 1m below the basement SSL).**
- **Formation level has been assumed between 6.80 mOD – 8.25 mOD along the Mount Pleasant elevation (i.e. 1m below the basement SSL).**
- **Formation level has been assumed between 6.80 mOD – 7.13 mOD along the Gough Street elevation (i.e. 1m below the basement SSL).**
- **Drained Parameters have been assumed for both short- and long-term conditions in view of the anticipated large construction period.**
- **Secant pile wall will be load bearing in the long-term and as such friction  $\delta=0$  was assumed for the retained material over the retained height (only for long-term) in accordance with CIRIA C760.**
- **The unit weight of the concrete of the base slab was added as a surcharge of 25kN/m<sup>2</sup> at the formation level.**
- **Groundwater level is assumed at +12.75m (SLS) / +13.75m (ULS)**
- **Water in the long-term was assumed to have a piezometric level equal to the initial water table, starting from the formation level. To eliminate negative**

effective stresses at formation level, a surcharge equal to the uplift applied on the slab was considered acting downwards. The partial factor on it was taken equal to 1.

- Overdig of 0.5m was considered for the ULS cases

5.4 proposed range of soil parameters to be used in the design/assessment of earth retaining elements

**Simplified stratigraphy used in the analysis (depth to top of stratum):**

- **Made Ground** **0**
- **Alluvium** **6.8**
- **River Terrace Deposits** **Absent**
- **London clay** **7.9**
- **Harwich Formation** **11.5**
- **Lambeth Group (cohesive)** **12**
- **Lambeth Group (granular)** **23**
- **Thanet Sand** **30**

## 6. GEOTECHNICAL CONDITIONS

6.1 Acceptance of recommendations of the Geotechnical Design Report to be used in the design/assessment and reasons for any proposed changes.

**All recommendations in the Ground Investigation report have been accepted.**

See below excerpt from RSK Interpretative Geotechnical Report (June 2017) regarding retaining wall design parameters:

*'The proposed development will include a basement across the majority of the site footprint. In order to facilitate basement construction it may be necessary to construct some form of embedded wall. On the basis of the ground investigation information, the following soil parameters in Table 24 may be used for preliminary retaining wall design purposes.'*

Table 24: Retaining wall design parameters

Soil type	Unit weight $\gamma_k$ (kN/m <sup>3</sup> )	Short Term Parameters		Long Term Parameters		Earth Pressure Coefficients	
		$c_{u,k}$ (kN/m <sup>2</sup> )	$\phi'_{cv,k}$ (°)	$c'_{v,k}$ (kN/m <sup>2</sup> )	$\phi'_{cv,k}$ (°)	$k_{o,k}$	$k_{a,k}/k_{p,k}$
Made Ground	18.0	N/A <sup>1)</sup>	28	0	28	0.53	0.35/3.41
Alluvium	18.5	35	-	0	23	0.56	0.37/3.10
Hackney Gravel	19 (moist) 21 (sat.)	N/A <sup>1)</sup>	12	0	34	0.44	0.25/6.90
London Clay Formation	20.0	75 + 7.14z	-	0	22	1.00	0.39/2.95
Lambeth Group - cohesive	20.0	100 + 5.88z	-	0	24	1.0 – 0.8	0.26/6.30

**Groundwater was encountered at levels of between 9.54mAOD and 14.99mAOD therefore allowance should be made for hydrostatic pressures acting behind retaining structures. Furthermore, any new basement construction must be designed to be fully sealed to prevent any future groundwater ingress.**

**In order to prevent damage to adjacent structures, the design of the retaining wall must address the risk of excessive deformation of the wall. Bracing, both in the temporary and permanent condition will therefore be required, to ensure that the horizontal and vertical soil movement around and below the excavation remain within acceptable levels.'**



**In response to the above;**

**The soil parameters provided in the RSK report have been used in the Wallap analysis of the secant pile wall.**

**The basement walls have been designed with 2 waterproofing measures i.e. to achieve a Grade 3 level of waterproofing protection to the internal spaces.**

**Bracing has been assumed in the temporary case by way of raking props (see section 5.3 and the Simplified Basement Construction Sequence which is appended to this document). In the permanent condition the secant wall will be propped by the ground floor, lower ground floor and basement slabs.**

- 6.2 Summary of design for highway structure in Geotechnical Design Report  
**N/A**
- 6.3 Differential settlement to be allowed for in the design/assessment of the structure  
**At basement level (i.e. 5-8m below street level) the maximum horizontal wall deflection is predicted to be 76mm on the Gough Street elevation and 60mm on the Mount Pleasant and Phoenix Place elevations. However, at street level the maximum horizontal wall deflection is predicted to be 15mm. These values are based on the assumptions listed in section 5.3 above and the methodology appended to this document.**
- 6.4 If the Geotechnical Design Report is not yet available, state when the results are expected and list the sources of information used to justify the preliminary choice of foundations.  
**Refer to the Basement Walls Options Study which is appended to this document. A secant pile wall has been proposed for the basement construction as vibration will be minimised compared to other techniques, there is good groundwater cut-off and a higher axial load can be supported on the wall compared to alternative systems.**
7. CHECK
- 7.1 Proposed Category  
**Category 2**
- 7.2 If Category 3, name of proposed independent Checker  
**N/A**
- 7.3 Erection proposals or temporary works for which Types S and P Proposals will be required, listing structural parts of the permanent structure affected with reasons  
**To be completed by Camden Highways**
8. DRAWINGS AND DOCUMENTS
- 8.1 List of Drawings (including numbers) and documents accompanying the submission
- |  |                                 |
|--|---------------------------------|
| <b>Piling GA</b>                                       | <b>MPL-ACM-XX-B1-DR-S-01001</b> |
| <b>Secant Pile Wall GA</b>                             | <b>MPL-ACM-XX-B1-DR-S-01020</b> |
| <b>Basement Level GA</b>                               | <b>MPL-ACM-XX-B1-DR-S-01003</b> |
| <b>Lower Ground Floor GA</b>                           | <b>MPL-ACM-XX-GF-DR-S-01004</b> |
| <b>Upper Ground Floor GA</b>                           | <b>MPL-ACM-XX-GF-DR-S-01005</b> |
| <b>Part Plan showing Fleet River Culvert Alignment</b> | <b>MPL-ACM-XX-XX-DR-S-02001</b> |
| <b>Substructure Sections Sheet 1</b>                   | <b>MPL-ACM-XX-ZZ-DR-S-04001</b> |
| <b>Substructure Sections Sheet 2</b>                   | <b>MPL-ACM-XX-ZZ-DR-S-04002</b> |
- 8.2 List of construction and record drawings (including numbers) to be used in the assessment.  
**N/A. See point 3.12.4 above.**

8.3 List of pile driving or other construction records  
**N/A. See point 3.12.4 above.**

8.4 List of previous inspection and assessment reports  
**N/A. See point 3.12.4 above.**

9. THE ABOVE IS SUBMITTED FOR ACCEPTANCE

We confirm that details of the temporary will be/have been passed to the permanent works designer for review.

Signed \_\_\_\_\_

Name \_\_\_\_\_  
Design/ Team Leader - Temporary works

Engineering Qualifications \_\_\_\_\_

Name of Organisation \_\_\_\_\_

Date \_\_\_\_\_

9a. THE ABOVE IS SUBMITTED FOR ACCEPTANCE

We confirm that details of the temporary works design will be/have been reviewed by the permanent works designer

Signed  \_\_\_\_\_

Name DAVID CUCKOW  
Design/ Team Leader - Permanent Works

Engineering Qualifications M1 Struct E \_\_\_\_\_

Name of Organisation AECOM \_\_\_\_\_

Date 2-3-2018 \_\_\_\_\_

10. THE ABOVE IS REJECTED/AGREED SUBJECT TO THE AMENDMENTS AND CONDITIONS SHOWN BELOW

Signed \_\_\_\_\_

Name \_\_\_\_\_

Position held \_\_\_\_\_

Engineering Qualifications \_\_\_\_\_


TAA \_\_\_\_\_

Date \_\_\_\_\_


## **APPENDIX**

- 1 Simplified Basement Construction Sequence**
- 2 Basement Walls Options Study**
- 3 Designers Risk Assessment**
- 4 Structural Drawings**


**Simplified Basement Construction Sequence:**




- Install upper piling mat and pile secant wall from or near pavement level




- Excavate centre of site to grade leaving berms to inside face of secant walls




- Install lower piling mat and pile central area from grade, construct central pilecaps



- Install first row of raking props (1:3) connecting secant wall and central pilecaps




- Excavate site leaving secondary berm on Gough Street elevation




- Construct adjacent row of pilecaps and install second row of raking props (1:3)






- Complete excavation and install remaining pilecaps to perimeter columns (inbound of secant wall)



- Construct lower ground floor slab, removing first row of temporary props once complete



- Construct upper ground floor slab, removing remaining temporary props once complete

# Retaining System

Different types of wall have been considered for the construction of the two-level basement for Plot P1 of the Phoenix Place Site at Mount Pleasant. However, in view of the high groundwater table (the majority of the excavation will take place below GWT) and the water-tightness requirements, and the column loads the retaining wall is envisaged to carry, the contiguous and sheet pile wall options have been discarded. The table below presents the most suitable options that were further considered for the retaining system.

**Table 1: Retaining System Options**

Foundation Option	Category	Advantages	Disadvantages
Secant Piled Wall (Hard-Firm)	Construction considerations (applications, access, dewatering)	<ul style="list-style-type: none"> <li>✓ In a hard / firm construction the female (primary) piles are unreinforced “firm” whilst the male (secondary) piles are reinforced “hard” and are installed to intersect the softer female piles.</li> <li>✓ It provides water-tightness to structure.</li> <li>✓ Male piles can carry structural loads from columns.</li> <li>✓ Slab to wall connection can be achieved with drilled in bars and couplers cast in wall.</li> </ul>	<ul style="list-style-type: none"> <li>✗ Less bending resistance compared to the hard/ hard secant pile walls and diaphragm walls.</li> <li>✗ Depth is limited due to rig capabilities and vertical tolerance that needs to be achieved. Piles to be installed to a maximum tolerance of 1 in 75mm in any direction.</li> <li>✗ Potential for water ingress at the joints between primary and secondary piles and between slab and wall connections.</li> <li>✗ Potentially reduced durability depending on the concrete mix used for the female piles.</li> <li>✗ Guniting or concrete facing is required if a drained cavity former is used.</li> </ul>
	Cost	<ul style="list-style-type: none"> <li>✓ It can be constructed with CFA rig, thus resulting in time and cost savings.</li> <li>✓ Easier, faster and less expensive to construct than hard/ hard secant and/ or diaphragm wall.</li> <li>✓ Female piles can be shorter, thus resulting in concrete savings.</li> </ul>	<ul style="list-style-type: none"> <li>✗ Penetration through hard strata may cause delays in the programme.</li> </ul>
	Settlements	<ul style="list-style-type: none"> <li>✓ Depending on the construction sequence and the temporary support considered for the basement excavation (i.e. top-down vs bottom-up with props/ berms vs bottom-up with anchors) deflections can vary between 0.1%H to 0.6%H, where H is the maximum excavation depth.</li> </ul>	

Foundation Option	Category	Advantages	Disadvantages
	Environment (noise, vibration, spoil)	<ul style="list-style-type: none"> <li>✓ Minimum environmental impact with regards to noise and vibration.</li> </ul>	<ul style="list-style-type: none"> <li>✗ Penetration through hard strata may cause vibration and noise.</li> </ul>
<b>Diaphragm Wall</b>	Construction considerations (applications, access, dewatering)	<ul style="list-style-type: none"> <li>✓ Panel lengths range typically between 2.4m and 6.0m length with shorter panels used when working close to adjacent structures. Wall panel thickness varies between 600mm and 1500mm.</li> <li>✓ Greater wall depths can be achieved compared to other wall types.</li> <li>✓ Penetration through hard strata can be achieved.</li> <li>✓ There are fewer joints compared to the secant wall hence reduced risk for water ingress. Panels also have stop ends with integral water bars on either of their sides.</li> <li>✓ Vertical tolerance to be achieved is 1 in 100mm, increasing with depth.</li> <li>✓ A uniform wall cross section can be achieved with a smooth finish in clays, resulting in easier application of finishes to a flat wall if required.</li> <li>✓ Connection of floors to wall is simpler than secant or contiguous piling. Box outs can be left in the wall face with either couplers or bend out bars.</li> </ul>	<ul style="list-style-type: none"> <li>✗ More difficult to construct compared to other wall types.</li> <li>✗ Bentonite storage and recirculation plant is required on site hence greater space requirements.</li> <li>✗ If bend out bars are used for slab-wall connection, the limitation on bar diameter would be 16mm in order to facilitate bending the bars out. Couplers are a more effective method of connecting the slabs to the wall however they are more expensive</li> <li>✗ Shadowing and matting effects may take place.</li> </ul>
	Cost		<ul style="list-style-type: none"> <li>✗ It is more expensive compared to other wall types.</li> <li>✗ Downtime for teeth replacement is likely to impact the programme.</li> <li>✗ The cost of setting up the bentonite plant is only justifiable for large projects.</li> </ul>
	Settlements	<ul style="list-style-type: none"> <li>✓ Lower deflections can usually be achieved compared to other wall types.</li> </ul>	
	Environment (noise, vibration, spoil)	<ul style="list-style-type: none"> <li>✓ Minimum environmental impact with regards to noise and vibration.</li> </ul>	<ul style="list-style-type: none"> <li>✗ Loss or spillage of bentonite slurry is a potential risk</li> </ul>



# Buildability

Issues to be reviewed with Bouygues:

- Propping level(s) vs pile diameter.
- Raking props vs flying propos.
- Props founded on piles vs raft vs separate pads.
- Piling rig level.
- Fleet River movements.

## Summary/Recommendation

In summary our initial analysis indicates that a pure raft solution will be so deep as to uneconomic and potentially result in excavation depths that exceed the recommended limit governed by groundwater pressures. In addition the uplift under the podium results in an excessive thickness of raft, unless tension piles are adopted to resist the uplift.

Item	Advantages	Disadvantages	Recommendation
<b>Construction</b>			
Contig piling	Lowest construction cost	Not considered Poor groundwater cu-off	
Secant piling	Good groundwater cut-off	Difficult to maintain plumb when encountering buried obstructions.	Yes
Sheet piling	Good groundwater cut-off	Low axial load capacity, thus perimeter columns required down to foundations. Inability to be able to punch thru buried obstructions.	
Diaphragm	Good groundwater cut-off	Highest cost, due to equipment and requirement for Bentonite	
<b>Waterproofing</b>			
Membrane plus drained cavity	Low cost. Ability to locate seepages.	Overall wall thickness	
Membrane plus liner wall	Minimum space take.	Waterproof treated concrete. Need to seal cracks	Yes

Our recommendation is to adopt a secant piled solution, with membrane and liner walls.



Phoenix Place - Stage 3	<b>Health, Safety and Environment</b> <b>SAFETY IN DESIGN WORKSHEET</b>	Document Number: DESIGNERS RISK ASSESSMENT - P1.DOC
-------------------------	--	---

Ref.	Design aspect or activity (see note 3)	Description of constraints, hazards and associated risks (see note 4)	Designer's interventions to eliminate or reduce risk (see note 5)	Residual risk, and information to be provided to enable project partners to manage the risk (see note 6)
1.0	<b>EXISTING SITE</b>			
1.1	Access / Traffic Restrictions.	Site traffic causing congestion to local road network and danger to public due to large reversing vehicles.	An approved Traffic Control Officer/Banksman (to be appointed by the contractor) situated permanently at site entrance to control traffic flows and protect the public during works.  <u>Information to be provided to the contractor:</u> Site plan.	<u>Residual Risks:</u> Cannot be eliminated
2.0	<b>DEMOLITION</b>			
2.1	Demolition of Existing Structures / Hard Standings	Dust and airborne contaminants	Operators to be masked and areas likely to produce dust kept wetted to reduce airborne particles.	<u>Residual Risks:</u> None
2.2	Hazardous Demolition Materials	Disposal of contaminated or hazardous waste can be a danger to the environment if not assessed and disposed of correctly.	Where contaminated waste is encountered, follow strict instructions outlined in the Demolition Specification and consult the Geotechnical Report for information on the soil classifications found.	Disposal of all contaminated waste is carried out by an approved removal specialist.
2.3	Removal of Demolition Spoil	Unsecured loose material in working areas.	Avoid excessively overloading trucks carrying away spoil and debris to reduce hazards.	Contractor should produce a carefully considered program to avoid difficulties in removing spoil.

Ref.	Design aspect or activity (see note 3)	Description of constraints, hazards and associated risks (see note 4)	Designer's interventions to eliminate or reduce risk (see note 5)	Residual risk, and information to be provided to enable project partners to manage the risk (see note 6)
3.0	<b>CONSTRUCTION</b>			
3.1	General works- Disturbance to Residential Environment.	The site is located close to a number of residential buildings. Residents may file complaints with the local borough against high noise levels, dust, disturbances and ground borne vibrations which may affect the construction programme.	<p>Risk cannot be eliminated but can be reduced by requesting the contractor to:</p> <ul style="list-style-type: none"> <li>· Comply with noise requirements of planning authority.</li> <li>· Monitor areas of possible high noise and vibration.</li> <li>· Avoid or minimise use of high- percussive equipment.</li> <li>· Carryout works only within the times and days permitted by the client/project manager.</li> </ul> <p><u>Information to be provided to the contractor:</u></p> <ul style="list-style-type: none"> <li>- Information on local borough imposed restrictions applicable to construction works including specific working hours, noise levels etc.</li> </ul>	<u>Residual Risks:</u> None
3.2	Excavation - Removal of Asbestos and hazardous materials.	Asbestos could potentially be found in the ground. Any found should be disposed by a specialist.	<p>Asbestos testing carried out during the site investigation found no traces of asbestos. However, the SI is not an asbestos survey and traces of asbestos could be left of the site.</p> <p>Risk cannot be eliminated but can be reduced by:</p> <ul style="list-style-type: none"> <li>· Employing specialists to remove and dispose any asbestos.</li> <li>· Inspecting any areas highlighted in</li> </ul>	<u>Residual Risks:</u> Traces of asbestos could be left in the site.

Ref.	Design aspect or activity (see note 3)	Description of constraints, hazards and associated risks (see note 4)	Designer's interventions to eliminate or reduce risk (see note 5)	Residual risk, and information to be provided to enable project partners to manage the risk (see note 6)
			<p>the site investigation as a potential risk, by an asbestos specialist prior to commencement of works.</p> <ul style="list-style-type: none"> <li>· Ensuring that employees wear full PPE and receive an induction outlining the areas of risk.</li> </ul> <p><u>Information to be provided to the contractor:</u></p> <ul style="list-style-type: none"> <li>- Ground Investigation Reports (Factual).</li> <li>- Contamination &amp; Remedial Strategy Report.</li> </ul>	
3.3	Excavation - removal of excavation spoil from site.	Disposal of contaminated or hazardous waste (if found from the on-going ground investigation survey works). The ground beneath the site is expected to be contaminated from previous uses.	<p>Risk reduced by designing foundation thicknesses so that the need to dig below the human separation layer is significantly less.</p> <p>Risk cannot be eliminated but can be reduced by requesting the contractor:</p> <ul style="list-style-type: none"> <li>· To adopt appropriate Health and Safety measures (minimise risks from contaminated ground through ingestion and inhalation by ensuring that operatives do not smoke, eat or drink - except in designated areas).</li> <li>· To inform the contractor of the potential hazards and report any observations of suspect material.</li> <li>· To use suitable PPE.</li> <li>· To prepare method statement for disposal of materials without forming</li> </ul>	<p><u>Residual Risks:</u> Traces of contaminated material could be left in the site.</p>

Ref.	Design aspect or activity (see note 3)	Description of constraints, hazards and associated risks (see note 4)	Designer's interventions to eliminate or reduce risk (see note 5)	Residual risk, and information to be provided to enable project partners to manage the risk (see note 6)
			dust. <ul style="list-style-type: none"> <li>· To remove materials using licensed tip and using registered haulage contractor.</li> </ul> <p><u>Information to be provided to the contractor:</u></p> <ul style="list-style-type: none"> <li>- Ground Investigation Reports (Factual).</li> <li>- Contamination &amp; Remedial Strategy Report.</li> </ul>	
3.4	Excavation and Piling - Disruption of existing mechanical and electrical services running adjacent to, or through the site.	Unknown buried services may be affected through the activities of excavation, piling and applying unforeseen surcharging. Depending on the service, this could lead to flooding, electrocution or explosion.	Risk cannot be eliminated but can be reduced by: <ul style="list-style-type: none"> <li>· Carrying out all necessary CAT/SCAN or GPR surveys to identify locations of services prior to demolition/excavation works.</li> <li>· Where required, existing services to be protected.</li> <li>· All workers to be made aware of the existing services and their locations clearly identified.</li> <li>· Requesting all operators to wear appropriate PPE.</li> </ul> <p><u>Information to be provided to the contractor:</u></p> <ul style="list-style-type: none"> <li>- STATS searches and records.</li> <li>- Any available records, drawings showing existing services.</li> <li>- M&amp;E engineers specification related to services disconnection.</li> </ul>	<u>Residual Risks:</u> None.

Phoenix Place - Stage 3	<b>Health, Safety and Environment</b>	Document Number: DESIGNERS RISK ASSESSMENT - P1.DOC
<b>SAFETY IN DESIGN WORKSHEET</b>		

Ref.	Design aspect or activity (see note 3)	Description of constraints, hazards and associated risks (see note 4)	Designer's interventions to eliminate or reduce risk (see note 5)	Residual risk, and information to be provided to enable project partners to manage the risk (see note 6)
3.5	Excavation and Piling -Potential damage to buried assets belonging to Thames Water.	Excavation and piling within close proximity to, Thames Water buried assets.	Risk cannot be eliminated but can be reduced by: <ul style="list-style-type: none"> <li>· Requesting the contractor to liaise with Thames Water at earliest possible opportunity so that the necessary agreements and approvals can be obtained prior to piling and excavation.</li> </ul> <u>Information to be provided to the contractor:</u> <ul style="list-style-type: none"> <li>- Any available Thames Water documents giving guidelines for third parties to carry out construction works close to Thames Water assets.</li> </ul>	<u>Residual Risks:</u> Cannot be eliminated.
3.6	Excavation and Piling- Discovery of Unexploded Bombs (UXO's) from WWII.	Possibility of buried UXO's in the site. Piling and excavation activities may cause deadly explosions.	Risk cannot be eliminated but can be reduced by: <ul style="list-style-type: none"> <li>· Carrying out relevant UXO surveys.</li> </ul> <u>Information to be provided to the contractor:</u> <ul style="list-style-type: none"> <li>- Any available UXO reports.</li> </ul>	<u>Residual Risks:</u> UXO's can still remain buried deep within the site.
3.7	Excavation and Piling - Highways	Undermining of adjacent highways and potential for collapse.	Ensure temporary propping is provided in any instance where permanent propping to the highways supporting retaining walls is removed. A Highways Approval in Principle (AIP) must be agreed with the local authority.	Monitoring of level at intervals as noted with appropriate trigger values. Temporary works proposals to be submitted to and approved by the Structural Engineer.
3.8	Excavation and construction of sub- structure- Encountering	There is a possibility of ground water being encountered during	Shallow ground water was encountered during site <b>investigation</b> works.	<u>Residual Risks:</u> Risk cannot be eliminated.



Phoenix Place - Stage 3	<b>Health, Safety and Environment</b> <b>SAFETY IN DESIGN WORKSHEET</b>	Document Number: DESIGNERS RISK ASSESSMENT - P1.DOC
-------------------------	--	---

Ref.	Design aspect or activity (see note 3)	Description of constraints, hazards and associated risks (see note 4)	Designer's interventions to eliminate or reduce risk (see note 5)	Residual risk, and information to be provided to enable project partners to manage the risk (see note 6)
	ground water.	excavations.	<p>Risk cannot be eliminated but can be reduced by:</p> <ul style="list-style-type: none"> <li>· Making the contractor and the workers aware of the situation.</li> <li>· Contractor to allow provisions for suitable arrangements to pump water, if encountered.</li> <li>· Contractor to allow for temporary discharge license</li> </ul> <p><u>Information to be provided to the contractor:</u></p> <ul style="list-style-type: none"> <li>- Site investigation reports and data which will include ground water monitoring records.</li> </ul>	
3.9	Temporary works to substructure construction	<p>Temporary works are required to stabilize the basement perimeter piled walls during excavation works.</p> <p>Temporary Works are complex, expensive and fundamental to the stability of partially completed structures. Risk of exceeding target costs and programme duration.</p>	<p>Basement perimeter walls have been designed as piled secant walls, propped by the Basement, Lower and Upper Ground floor slabs.</p> <p>Contractor's temporary works proposals to be submitted to the Engineer in time to enable perimeter wall piles to be checked for the implications propping schemes more onerous than assumed in the design.</p>	<p><u>Residual Risks:</u> Temporary propping proposals may require an increase in pile sizes/rebar.</p>
3.10	Temporary works will be required during the entire construction phase to support partially completed structures.	Temporary Works are required to support insitu concrete super structure elements such as columns, slabs and walls.	<p>Main structural shear walls designed to minimize the need of temporary works during the construction phase.</p> <p>Pre-fabricated bolt-on steel balconies</p>	<p><u>Residual Risks:</u> None.</p>

Phoenix Place - Stage 3	<b>Health, Safety and Environment</b>	Document Number: DESIGNERS RISK ASSESSMENT - P1.DOC
<b>SAFETY IN DESIGN WORKSHEET</b>		

Ref.	Design aspect or activity (see note 3)	Description of constraints, hazards and associated risks (see note 4)	Designer's interventions to eliminate or reduce risk (see note 5)	Residual risk, and information to be provided to enable project partners to manage the risk (see note 6)
		Temporary Works are complex, expensive and fundamental to the stability of partially completed structures. Risk of exceeding target costs and programme duration.	are proposed where possible.  Risk cannot be eliminated but can be reduced by: <ul style="list-style-type: none"> <li>· Using pre-fabricated elements where possible as shown in the drawings.</li> </ul> <u>Information to be provided:</u> <ul style="list-style-type: none"> <li>- All drawings and specification for the proposed structure.</li> </ul>	
3.11	Multi-storey construction.	Injury or death from falling objects from height.	Risk cannot be eliminated but can be reduced by using: <ul style="list-style-type: none"> <li>· Mechanical methods for the movement of debris.</li> <li>· Protective measures such as "safety nets" around the working areas.</li> </ul> <u>Information to be provided:</u> <ul style="list-style-type: none"> <li>- Drawings and specification of the proposed structure.</li> </ul>	<u>Residual Risks:</u> Risk will remain.
3.12	Construction of insitu cast reinforced concrete structure.	Reinforcement storage and access. General obstacles for material movement, imposing a danger for workers and the public.	Large diameter bars (i.e. H40 and H50) have been avoided to increase the manageability in handling reinforcing bars.  Risk cannot be eliminated but can be reduced by: <ul style="list-style-type: none"> <li>· Contractor should look into the logistics of reinforcement deliveries and storage. Possibly exploring out-of-hours rebar deliveries.</li> </ul>	<u>Residual Risks:</u> None.

Phoenix Place - Stage 3	<b>Health, Safety and Environment</b>	Document Number: DESIGNERS RISK ASSESSMENT - P1.DOC
<b>SAFETY IN DESIGN WORKSHEET</b>		

Ref.	Design aspect or activity (see note 3)	Description of constraints, hazards and associated risks (see note 4)	Designer's interventions to eliminate or reduce risk (see note 5)	Residual risk, and information to be provided to enable project partners to manage the risk (see note 6)
			<u>Information to be provided:</u> <ul style="list-style-type: none"> <li>- All drawings and specification for the proposed structure.</li> <li>- Rebar mark-ups for the contractor to prepare rebar schedules.</li> </ul>	
3.13	Construction of insitu cast reinforced concrete structure.	Working in wet conditions and construction of concrete onto wet material (natural ground water level may cause problems during the excavation of the ground, and rainwater is likely to accumulate whilst the ground is exposed).	Risk cannot be eliminated but can be reduced by: <ul style="list-style-type: none"> <li>· Planning ahead by preparation of suitable dewatering proposals by the contractor.</li> </ul> <u>Information to be provided:</u> <ul style="list-style-type: none"> <li>- All drawings and specification for the proposed structure.</li> <li>- All available ground investigation reports with ground water monitoring records.</li> </ul>	<u>Residual Risks:</u> None.
3.14	Construction of insitu cast reinforced concrete structure.	Cracking and displacement of concrete on removal of formwork and propping.	Risk cannot be eliminated but can be reduced by: <ul style="list-style-type: none"> <li>· Contractor to ensure that propping/back propping and shuttering shall only be removed after a minimum period after pour time to allow the concrete to gain near optimum compression capacity.</li> <li>· The contractor must forward onto the Structural Engineer the cube/cylinder test results as per the Concrete Specification. These will be reviewed and approved by the SE to ensure that the concrete properties are acceptable.</li> </ul>	<u>Residual Risks:</u> None.

Ref.	Design aspect or activity (see note 3)	Description of constraints, hazards and associated risks (see note 4)	Designer's interventions to eliminate or reduce risk (see note 5)	Residual risk, and information to be provided to enable project partners to manage the risk (see note 6)
			<u>Information to be provided:</u> - All structural engineers drawings and specification.	
3.15	On-site welding of steel.	Risk of fire.	<p>Site welding will not be acceptable without prior approval. Steel-to-steel connections are to be bolted together and steel-to-concrete connections are to be cast in or anchored in to reduce the requirement for site welding.</p> <p>Risk can eliminated but can be reduced by:</p> <ul style="list-style-type: none"> <li>- Pre-fabrication of steel elements where possible and using only bolted connections as shown in structural engineers drawings.</li> </ul> <p><u>Information to be provided:</u></p> <ul style="list-style-type: none"> <li>- Structural engineers drawings and specification.</li> </ul>	<u>Residual Risks:</u> None.



Notes

- General Notes
1. Work to figured dimensions only.
  2. This drawing is to be read in conjunction with the structural specification and all relevant drawings issued by the Architect, the Building Services Engineer and specialist sub-contractors.
  3. All dimensions are in mm except levels which are in m.
- Notes
1. Concrete Grades as follows:  
Slab: C35/45  
Columns: C35/45  
Girders: C35/45  
Reinforcement Grade: B500B
  2. Concrete finishes to be in accordance with the specification.
  3. Clearances to concrete elements to be in accordance with the specification.
  4. Concrete members are positioned centrally about the grid unless noted otherwise.
  5. R.C. walls 250mm thick U.D.
  6. Allow for 25mm thick c.c. dampers to all flat roofs.
  7. All cast-in-place concrete to be cast in accordance with the specification.
  8. All cast-in-place concrete to be cast in accordance with the specification.
  9. All external steelwork to be galvanized in accordance with the specification.
  10. Precast concrete slabs by specialist subcontractor. Half landings to 200mm thick precast slabs spanning between core walls.

**NOTE:**  
UPLIFT PRESSURES (INCLUDING WATER PRESSURES AND HEAVE) MAY REQUIRE THE USE OF TENSION PILES UNDER LARGE SLAB SPANS. REQUIREMENTS TBC.

**NOTE:**  
ADDITIONAL PILES MAY BE REQUIRED TO SUPPORT WATER TANK ADJACENT RAMP STRUCTURE. REQUIREMENTS TBC.

**NOTE:**  
ALL BEARING PILES ARE TO BE DESIGNED TO RESIST UPLIFT (TENSION) IN THE TEMPORARY CASE.

**NOTE:**  
FOR PILING SCHEDULES REFER TO DRAWING No's. DR-S-6001, DR-S-6002, DR-S-6003 & DR-S-6004.

**LEGEND**

ALL PILES ARE ASSUMED TO BE 750mm DIAMETER

- DENOTES BEARING PILE
- ⊕ DENOTES TENSION PILE



Issue/Revision

Rev	Date	Description
T3		DIFFERENTIAL STAGE 3 - REVISIONS AS CLOUDED
T2		TAILORING STAGE 3
T1		REDCITY INTERIM STAGE 3

Key Plan

Purpose Of Issue

STAGE 3

Project Number  
60556156


Sheet Title  
General Arrangement of Piles

Sheet Number

MPL-ACM-XX-B1-DR-S-01001


Scale: 1:200@A0

Rev: T3






- General Notes:**
1. Work to figure dimensions only.
  2. The drawings to be read in conjunction with the structural specification and all relevant drawings issued by the Architect, the Building Services Engineer and specialist sub-contractors.
  3. All dimensions are in mm except levels which are in m.
- Notes:**
1. Concrete Grades as follows:  
Slabs: C35/45  
Columns: C35/45  
Coping Drains: C35/45  
Piles: C35/45
  2. Reinforcement Codes: S3202
  3. Concrete finishes to be in accordance with the specification.
  4. Concrete to provide elements to be in accordance with the specification.
  5. Concrete members are positioned centrally about the grid unless noted otherwise.
  6. R.C. walls 200mm thick U.K.C.I.
  7. Allow for 200mm thick r.c. parapets to all flat roofs.
  8. Allow for r.c. cantilevered slab tops and service penetrations at roof level.
  9. All steelwork to be Grade S275, 60 (hot rolled sections) or S355, HR (fabricated sections).  
S11.0: All external network to be galvanneal in accordance with the specification.
  10. Precast concrete slabs by specialist subcontractor. Half loadings to 200mm thick in situ slabs spanning between core walls.





TYPICAL PILE HEAD DETAIL  
1:20



TYPICAL FEMALE PILE TOE DETAIL  
1:20

**NOTE:**  
FOR PILING SCHEDULES REFER TO  
DRAWING No's. DR-S-6005 & DR-S-6006.



Rev	Date	Description

**Key Plan**

**Purpose Of Issue**

STAGE 3 - FOR TENDER

**Project Number**

60556156

**Sheet Title**

General Arrangement of  
Secant Pile Wall

**Sheet Number**

MPL-ACM-XX-B1-DR-S-01020

Scale: As indicated@A0 Rev: T1

ISO A0 841mm x 1189mm  
 Drawn by: CB  
 Approved: DC  
 Checked: RM  
 Designer: RM  
 Project Management Initials:

This drawing has been prepared for the use of AECOM's client. It may not be used, modified, reproduced or relied upon by third parties, except as agreed by AECOM or as required by AECOM or as required by law. AECOM accepts no responsibility, and denies any liability whatsoever, to any party that uses or relies on this drawing without AECOM's express written consent. Do not scale this document. All measurements must be obtained from the stated dimensions.



- General Notes:
- Work to figure dimensions only.
  - The drawings to be read in conjunction with the structural specification and all relevant drawings issued by the Architect, the Building Services Engineer and specialist sub-contractors.
  - All dimensions are in mm except levels which are in m.
- Notes:
- Concrete Grades as follows:  
Slabs: C35/45  
Columns: C35/45  
Walls: C35/45  
Reinforcement Grade: B500C
  - Concrete finishes to be in accordance with the specification.
  - Concrete to provide elements to be in accordance with the specification.
  - Concrete members are positioned centrally about the grid unless noted otherwise.
  - R.C. walls 200mm thick U.C.C.
  - Allow for 25mm thick r.c. concrete to all flat roofs.
  - Allow for r.c. columns to be cast and concrete operations at roof level.
  - All steelwork to be Grade S275, 40 (hot rolled sections) or S275, 40 (fabric sections).
  - U.C.C. All external elements to be galvanized in accordance with the specification.
  - Precast concrete slabs by specialist subcontractor. Half sandings to 200mm risk in situ slabs spanning between core walls.

**INSITU R.C COLUMN SCHEDULE**

Column Ref	Column Size
C1	400x400 R.C. COL.
C2	500x500 R.C. COL.
C3	600x600 R.C. COL.
C4	600x600 R.C. COL.
C5	800x800 R.C. COL.
C6	700x700 R.C. COL.
C7	700x700 R.C. COL.
C8	700x700 R.C. COL.
C9	800x800 R.C. COL.
C10	1000x1000 R.C. COL.
C11	1000x1000 R.C. COL.
C12	1000x1000 R.C. COL.
C13	1000x1000 R.C. COL.
C14	1000x1000 R.C. COL.
C15	1000x1000 R.C. COL.
C16	1000x1000 R.C. COL.
C17	2000x1000 R.C. COL.
C18	2000x1000 R.C. COL.
C19	800x800 R.C. COL.



NOTE:  
SETTING OUT AND SIZE OF ALL SERVICE PENETRATIONS TO BE CONFIRMED BY THE BUILDING SERVICES ENGINEER.

NOTE:  
REFER TO DRAWING No. DR-S-05001 & DR-S-05002 FOR TYPICAL PILECAP DETAILS

NOTE:  
BASEMENT SLAB LEVELS ARE BASED ON SWECO RAMP DESIGN ISSUED BY ARCHITECT ON 19.12.17. ANY SUBSEQUENT CHANGES TO SLAB LEVELS MADE AFTER 26.01.18 (i.e 2 WEEKS PRIOR TO STAGE 3 ADDENDUM ISSUE) HAVE NOT BEEN REFLECTED.

**LEGEND:**

- Denotes structural slab level in metres AOD.
- Denotes insitu R.C column.
- Denotes insitu R.C column under.
- Denotes two way spanning insitu R.C flat slab.
- Denotes step in slab.
- Denotes horizontal movement joint of 40mm nominal width (50mm maximum width with heavy load conditions at maximum centres (ANCON H.L. HALF NHD OR SIMILAR APPROVED) AND WITH JOINT FILLER CAPABLE OF 20mm COMPRESSION PROMAT PROMASEAL OR SIMILAR APPROVED).
- Denotes horizontal movement joint as above but with 30mm nominal width, 70mm maximum width and capable of 10mm compression.



**Issue/Revision**

Rev	Date	Description
T4	11 FEB 2018	BASEMENT LEVELS REVISED IN ACCORDANCE WITH ARCHITECT'S STAGE 3 ISSUE
T3	05 FEB 2018	STAGE 2 - REVISIONS ARE CLOUSED
T2	15 JAN 2018	STAGE 2
T1	05 DEC 2017	INTERIM STAGE 3

**Key Plan**

**Purpose Of Issue**

STAGE 3  
Project Number  
60556156  
Sheet Title  
General Arrangement at Basement Level

**Sheet Number**

MPL-ACM-XX-B1-DR-S-01003  
Scale: As indicated@A0 Rev: T4




Notes

- General Notes:
- Work to figured dimensions only.
  - This drawing is to be read in conjunction with the structural specification and all relevant drawings issued by the Architect, the Building Services Engineer and specialist sub-contractors.
  - All dimensions are in mm except levels which are in m.
- Notes:
- Concrete Grades as follows:  
Slabs: C35/45  
Columns: C40/50  
Girders: C35/45
  - Reinforcement Grade: B500B
  - Concrete finishes to be in accordance with the specification.
  - Clearances to concrete elements to be in accordance with the specification.
  - Concrete members are positioned centrally about the grid unless noted otherwise.
  - R.C. walls 250mm thick U.D.
  - Allow for 25mm thick r.c. sweeps to all flat roofs.
  - Allow for r.c. cantilever to all rooms and service penetrations at roof level.
  - All steelwork to be Grade S275 (2) (per rated sections) or S235 (per tubular sections). U.N.D. All external steelwork to be galvanized in accordance with the specification.
  - Precast concrete stairs by specialist subcontractor. Half landings to 200mm thick in situ slabs spanning between core walls.

LEGEND:





- Denotes STRUCTURAL SLAB LEVEL IN METRES A.O.D.
- Denotes INSITU R.C COLUMN.
- Denotes INSITU R.C COLUMN UNDER.
- Denotes TWO WAY SPANNING INSITU R.C FLAT SLAB.
- Denotes STEP IN SLAB.
- Denotes HORIZONTAL MOVEMENT JOINT OF 40mm NOMINAL WIDTH (50mm MAXIMUM WIDTH) WITH SHEAR LOAD CONNECTORS AT MAXIMUM CENTRES (ANCON H.L.D. HALFEN HSD OR SIMILAR APPROVED) AND WITH JOINT FILLER CAPABLE OF 50mm COMPRESSION (SHEAR) (PROBASEAL OR SIMILAR APPROVED).
- Denotes HORIZONTAL MOVEMENT JOINT TO ACHIEVE 80% WITH 50mm NOMINAL WIDTH, 70mm MAXIMUM WIDTH AND CAPABLE OF 15mm COMPRESSION.



Column Ref	Column Size
C1	400x400 RC COL
C2	500x500 RC COL
C3	600x600 RC COL
C4	600x300 RC COL
C5	600x200 RC COL
C6	700x200 RC COL
C7	750x400 RC COL
C8	800x500 RC COL
C9	800x500 RC COL
C10	1000x500 RC COL
C11	1000x500 RC COL
C12	1000x500 RC COL
C13	1600x500 RC COL
C14	1800x500 RC COL
C15	1875x500 RC COL
C16	2000x500 RC COL
C17	2300x500 RC COL
C18	2600x500 RC COL
C19	800x200 RC COL

Beam Ref	Beam Dimensions	
	Depth	Width
TB1	200 mm	200 mm
TB2	300 mm	1000 mm
TB3	300 mm	1200 mm
TB4	150 mm	1300 mm
TB5	150 mm	1500 mm
TB6	120 mm	1500 mm
TB7	120 mm	1600 mm
TB8	120 mm	1700 mm
TB9	120 mm	1700 mm

NOTE:  
SETTING OUT AND SIZE OF ALL SERVICE PENETRATIONS TO BE CONFIRMED BY THE BUILDING SERVICES ENGINEER.



Issue/Revision

Rev	Date	Description
T3		DIFFERENTIAL STAGE 3 - REVISIONS AS CLOUDED
T2		TOTAL STAGE 3
T1		ISSUED FOR STAGE 3

Key Plan

Key Plan	Description
1	Overall Site Location
2	Site Boundary
3	Building Footprint
4	Structural Grid Lines
5	Column Locations
6	Beam Locations
7	Slab Levels
8	Retaining Walls
9	Stair Locations
10	Service Penetrations
11	Future Block A
12	Future Block B
13	Future Block C


Purpose Of Issue

Project Number  
60556156

Sheet Title  
General Arrangement at Lower Ground Floor Level

Sheet Number  
MPL-ACM-XF-GF-DR-S-01004

Scale: As indicated@A0 Rev: T3



Project Management: DC  
 Designer: RM  
 Checked: DC  
 Drawn by: G. Boyd  
 ISO A0 841mm x 1189mm


This drawing has been prepared for the use of AECOM's client. It may not be used, modified, reproduced or relied upon by third parties, except as agreed by AECOM or as required by law. AECOM accepts no responsibility, and denies any liability whatsoever, to any party that uses or relies on this drawing without AECOM's express written consent. Do not scale this document. All measurements shall be obtained from the sheet.



- General Notes:
- Work to figured dimensions only.
  - The drawings to be read in conjunction with the structural specification and all relevant drawings issued by the Architect, the Building Services Engineer and specialist sub-contractors.
  - All dimensions are in mm except levels which are in m.
- Notes:
- Concrete Grades as follows:  
 Slabs: C35/45  
 Columns: C35/45  
 Walls: C35/45
  - Reinforcement Grade: B500S
  - Concrete finishes to be in accordance with the specification.
  - Concrete to provide elements to be in accordance with the specification.
  - Concrete members are positioned centrally about the grid unless noted otherwise.
  - R.C. walls 200mm thick U.C.C.
  - Allow for 25mm thick r.c. parapets to all flat roofs.
  - Allow for r.c. cantilever slab tops and service penetrations at roof level.
  - All steelwork to be Grade S275 (if hot rolled sections) or S355 (if tubular sections).
  - U.C.C. All external elements to be galvanneal in accordance with the specification.
  - Precast concrete slabs by specialist subcontractor. Half sandings to 200mm thick in situ slabs spanning between core walls.

**LEGEND:**


- Denotes structural slab level in metres AOD.
- Denotes INSTU R.C. COLUMN.
- Denotes INSTU R.C. COLUMN UNDER.
- Denotes two way spanning INSTU R.C. flat slab.
- Denotes STEP IN SLAB.
- Denotes HORIZONTAL MOVEMENT JOINT OF 40mm NOMINAL WIDTH (95mm MAXIMUM WIDTH WITH SHEAR LOAD CONNECTIONS AT MAXIMUM CENTRES (W/CONC. R.C. HALF-HIGH OR SIMILAR APPROVED) AND WITH JOINT FILLER CAPABLE OF 20mm COMPRESSION PROXIMATE PROXIMAL OR SIMILAR APPROVED).
- Denotes HORIZONTAL MOVEMENT JOINT AS ABOVE BUT WITH 35mm NOMINAL WIDTH, 70mm MAXIMUM WIDTH AND CAPABLE OF 15mm COMPRESSION.



Column Ref	Column Size
C1	400x400 R.C. COL.
C2	600x200 R.C. COL.
C3	600x200 R.C. COL.
C4	600x200 R.C. COL.
C5	600x200 R.C. COL.
C6	700x200 R.C. COL.
C7	700x200 R.C. COL.
C8	700x200 R.C. COL.
C9	800x200 R.C. COL.
C10	1000x200 R.C. COL.
C11	1000x400 R.C. COL.
C12	1200x200 R.C. COL.
C13	1600x200 R.C. COL.
C14	1600x200 R.C. COL.
C15	1700x200 R.C. COL.
C16	2000x200 R.C. COL.
C17	2300x200 R.C. COL.
C18	2400x200 R.C. COL.
C19	800x200 R.C. COL.

Beam Ref	Beam Dimensions
TB1	600mm x 250mm
TB2	1000mm x 1000mm
TB3	1000mm x 1200mm
TB4	1100mm x 1500mm
TB5	1200mm x 1200mm
TB6	1250mm x 1600mm
TB7	1300mm x 1700mm
TB8	1300mm x 1500mm

NOTE:  
 SETTING OUT AND SIZE OF ALL SERVICE PENETRATIONS TO BE CONFIRMED BY THE BUILDING SERVICES ENGINEER.



Issue/Revision

Rev	Date	Description
T3		ISSUE/STAGE 3 - REVISIONS AS CLOUSED
T2		ISSUE/STAGE 3
T1		ISSUE/STAGE 3

Key Plan

Purpose Of Issue

STAGE 3

Project Number

60556156

Sheet Title


General Arrangement at Upper Ground Floor Level

Sheet Number

MPL-ACM-XX-GF-DR-S-01005

Scale:

As indicated@A0 Rev: T3




This drawing has been prepared for the use of AECOM's client. It may not be used, modified, reproduced or relied upon by third parties, except as agreed by AECOM or as required by law. AECOM accepts no responsibility, and denies any liability whatsoever, to any party that uses or relies on this drawing without AECOM's express written consent. Do not scale the drawing. All measurements must be obtained from the stated dimensions.




- General Notes:**
1. Work to figured dimensions only.
  2. This drawing is to be read in conjunction with the structural specification and all relevant drawings issued by the Architect, the Building Services Engineer and specialist sub-contractors.
  3. All dimensions are in mm except levels which are in m.

- Notes:**
1. Concrete Grades as follows:  
Slabs C35/45  
Columns C35/45  
Cores C35/45
  2. Reinforcement Grade: B500B.
  3. Concrete finishes to be in accordance with the specification.
  4. Tolerances to concrete elements to be in accordance with the specification.
  5. Concrete members are positioned centrally about the grid unless noted otherwise.
  6. R.C. walls 250mm thick U.N.O.
  7. Allow for 25mm thick r.c. parapets to all flat roofs.
  8. Allow for r.c. upstand to all risers and service penetrations at roof level.
  9. All steelwork to be Grade S355 J0 (hot rolled sections) or S355 JHR (tubular sections) U.N.O. All external steelwork to be galvanized in accordance with the specification.
  10. Precast concrete slabs by specialist subcontractor. Half landings to 200mm thick in-situ slabs spanning between core walls.


Rev.	Date	Description
T3	16FEB18	FLEET RIVER CULVERT PROFILE UPDATED; BASEMENT LEVELS REVISED TO SUIT ARCHITECTS STAGE 3 ISSUE.
T2	09FEB18	STAGE 3 - REVISIONS AS CLOUDED
T1	19JAN18	STAGE 2




**PART PLAN AT PROPOSED BASEMENT LEVEL SHOWING FLEET RIVER CULVERT ALIGNMENT**  
1: 200




**SECTION 1.1**  
1: 100




**SECTION 2.2**  
1: 100




**SECTION 3.3**  
1: 100



**SECTION 4.4**  
1: 100



**SECTION 5.5**  
1: 100



Project

Phoenix Place  
Mount Pleasant

Client

Taylor Wimpey  
Central London

Consultant

AECOM  
Aldgate Tower  
2 Leman Street  
London E1 8FA  
United Kingdom  
Tel +44 (0) 20 7061 7000  
www.aecom.com

Notes

- General Notes:**
- Work to figured dimensions only.
  - This drawing is to be read in conjunction with the structural specification and all relevant drawings issued by the Architect, the Building Services Engineer and specialist sub-contractors.
  - All dimensions are in mm except levels which are in m.
- Notes:**
- Concrete Grades as follows:  
Slabs C35/45  
Columns C35/45  
Cores C35/45
  - Reinforcement Grade: B500B.
  - Concrete finishes to be in accordance with the specification.
  - Tolerances to concrete elements to be in accordance with the specification.
  - Concrete members are positioned centrally about the grid unless noted otherwise.
  - R.C. walls 250mm thick U.N.O.
  - Allow for 225mm thick r.c. parapets to all flat roofs.
  - Allow for r.c. upstand to all risers and service penetrations at roof level.
  - All steelwork to be Grade S355 J0 (hot rolled sections) or S355 JHR (tubular sections) U.N.O. All external steelwork to be galvanized in accordance with the specification.
  - Precast concrete stairs by specialist subcontractor. Half landings to 200mm thick in-situ slabs spanning between core walls.

Issue/Revision

Rev.	Date	Description
T2	16FEB18	BASEMENT LEVELS REVISED IN ACCORDANCE WITH ARCHITECT'S STAGE 3 ISSUE
T1	19JAN18	STAGE 3

Key Plan

Purpose Of Issue

STAGE 3

Project Number

60556156

Sheet Title


Cross Sections Through Substructure

Sheet Number


MPL-ACM-XX-ZZ-DR-S-04001

Scale: 1:200@A1


Rev: T2




CROSS SECTION 1.1  
1:200



CROSS SECTION 2.2  
1:200



CROSS SECTION 3.3  
1:200



This drawing has been prepared for the use of AECOM's client. It may not be used, modified, reproduced or relied upon by third parties, except as agreed by AECOM or as required by law. AECOM accepts no responsibility, and denies any liability whatsoever, to any party that uses or relies on this drawing without AECOM's express written consent. Do not scale this document. All measurements must be obtained from the stated dimensions.




General Notes:


1. Work to figured dimensions only.
2. This drawing is to be read in conjunction with the structural specification and all relevant drawings issued by the Architect, the Building Services Engineer and specialist sub-contractors.
3. All dimensions are in mm except levels which are in m.

Notes:


1. Concrete Grades as follows:  
Slabs C35/45  
Columns C35/45  
Cores C35/45
2. Reinforcement Grade: B500B.
3. Concrete finishes to be in accordance with the specification.
4. Tolerances to concrete elements to be in accordance with the specification.
5. Concrete members are positioned centrally about the grid unless noted otherwise.
6. R.C. walls 250mm thick U.N.O.
7. Allow for 25mm thick c.c. parapets to all flat roofs.
8. Allow for r.c. upstand to all risers and service penetrations at roof level.
9. All steelwork to be Grade S355 J0 (hot rolled sections) or S355 JHR (tubular sections). U.N.O. All external steelwork to be galvanized in accordance with the specification.
10. Precast concrete stairs by specialist subcontractor. Half landings to 200mm thick in-situ slabs spanning between core walls.




SECTION 4.4  
1: 100




SECTION 5.5  
1: 100



SECTION 6.6  
1: 100



SECTION 7.7  
1: 100



Rev.	Date	Description
T1	19JAN18	STAGE 3

This drawing has been prepared for the use of AECOM's client. It may not be used, modified, reproduced or relied upon by third parties, except as agreed by AECOM or as required by law. AECOM accepts no responsibility, and denies any liability whatsoever, to any party that uses or relies on this drawing without AECOM's express written consent. Do not scale this document. All measurements must be obtained from the stated dimensions.