

New steps to light well to replace non original steps to allow space below for better access to the Vault

Existing ceiling to be retained where practicable, existing cornice to be retained if original

Fireplace and mantelpiece to be renovated, new hearth

New timber floor finish, existing sub floor to be retained if original fabric

Existing ceiling to be retained where practicable, existing cornice to be retained if original

Existing kitchen units to be removed and replaced with new

New timber floor finish, existing sub floor to be retained if original fabric

Proposed roof light with internal blind

New stone finish to rear garden

W00.03

Table 2100  
x 1000

Dining-  
001

Kitchen-  
002

Roof Light  
W00.04

Garden-  
004

A D E

D00.01

Coir Matting

Hall-  
000

D00.02

D00.04

D00.03

WC  
003

D00.04

W00.02

Existing non original glazed doors to be replaced, door head to be raised to picture rail height- doors to be two panel bi-fold door leaves with recessed details to match the window shutters

New timber floor finish, existing sub floor to be retained if original fabric

Existing ceiling to be retained where practicable, existing cornice to be retained if original

Door width to be increased, door head to be raised to line with picture rail, non original wall

New four panelled door to match existing to be fixed and non openable

Alterations to stair to level treads

Existing glass balustrade to be removed and replaced with timber panelling

Existing door to be removed, opening adjusted with studwork and plasterboard to form new door opening, new door

Window opening to be enlarged, new timber framed casement window

New timber framed, glazed door and fanlight to replace existing

