

**TECHNICAL DATA SHEET** 

# Bauder Xero Flor XF301 Sedum Blanket

#### **DESCRIPTION**

The Bauder Xero Flor XF301 vegetation blanket is a unique sedum mat product developed for use directly over the waterproofing system without the need for a secondary substrate growing medium, making XF301 the lightest selfcontained sedum blanket system available.

It incorporates a polypropylene mesh bonded to a vapour permeable base carrier sheet. This ensures that the blanket substrate is contained, doesn't compact and helps to maintain the vegetation in optimum condition.



Date: 19 -11-12

The product also has an integral moisture retention fleece that can absorb and retain up to 5 L/m² of water. The vegetation within this product is a mix of hardy sedum species with some grasses and moss also present.

## **TECHNICAL DATA:**

Composition

Mineral component selected porous aggregate Organic component composted green waste

## **Technical Performance**

6.5 - 7pH value

Vegetation support layer geo-textile carrier filter layer with bonded UV resistant

nylon loops

Moisture retention fleece recycled fibres (80%man-made, 20% organic)

Weights and sizes

Standard roll width 1 m Standard roll length 2 m

Non-standard lengths up to 10m (cut only in increments of 1m) installed with

a crane attachment that is available from Bauder Ltd.

Thickness: ca. 28mm (excluding vegetation)

44Kg/m<sup>2</sup> Saturated weight:

Fire Rating

Ext. F. AA Ext. S. AA BS 476 Part 3:2004

Rolls of blanket to specified lengths (as above) **Supply Form** 

**UNITED KINGDOM** 

**Bauder Ltd** 

70 Landseer Road Ipswich Suffolk England IP3 0DH T: +44 (0)1473 257671 E: info@bauder.co.uk

bauder.co.uk

**IRELAND** 

**Bauder Ltd** 

O'Duffy Centre Cross Lane Carrickmacross Co. Monaghan Ireland T: +353 (0)42 9692 333 E: info@bauder.ie

bauder.ie



## **DELIVERY INFORMATION**

- Deliveries of the Bauder XF301 Sedum Blanket are made from Tuesday to Friday.
- In exceptional weather we are unable to harvest the product for delivery until
  conditions improve. We are only able to advise the day before delivery if such a
  problem occurs.
- Order no more blanket to be delivered to site than can be installed within 24 hours of delivery.
- Should the blanket be considered faulty it is imperative that the Bauder sales office is informed on the day of delivery.
- If, for any reason, it is not possible to install the blanket on the day of delivery, the product should be rolled out on a flat, level surface, lightly watered and left out overnight before re-rolling for use early the following morning.

## **INSTALLATION INSTRUCTIONS - 2 X 1M ROLLS**

- Ensure that the waterproofing has first been given and passed Final inspection by the Bauder Site Technician and that all waterproofing attached accessory items such as edge trims or retention stripes are installed.
- If large areas are to be installed then watering and installation should be done in sections of as much area as can be completed within four hours.
- It is important to ensure that width rolls are used at all roof perimeters i.e. no thin strips or small pieces that would otherwise present a wind uplift risk. Any 'cutting in' of thinner strips must be made in the field area, with the cut being made opposite to the selvedge to maintain continuity during installation.
- Working from the bottom left hand corner of the roof and taking care not to stand on the vegetated surface, unroll the blanket apply firmly onto the waterproofing, ensuring that the selvedge is unfolded and cleaned to remove any over-growing vegetation. This is important to ensure that the blankets are installed tightly butted together with no gaps.
- The blanket is fully inserted in to SS40 edge retention trim where this is installed.
- Continue on up the slope with the next roll, taking care to ensure that the junction between the two rolls is tightly butted. Full any gaps with the extra substrate provided.
- When the first row of blankets are installed and the selvedges unfolded, the contractor is to use a short piece of 50 x 50mm or similar softwood timber to run up and down the selvedge, lightly pressing up against the substrate and vegetation adjacent to remove all surplus material and leave a clean edge to butt the next blanket up to. The surplus substrate and vegetation is to be collected and set aside for future use.



- Upon completion of the area, the previously collected surplus substrate is to be used to dress into and make good any joints where the blanket edges are not tightly butted. Excess vegetation spouts removed from cleaning the selvedge can be applied to filled gaps/joints or any bare areas and these will usually root and establish within a couple of weeks.
- In order to keep all joints correctly spaced and well-made it is recommended that no more than three rolls should be installed before adjacent rolls are added to the installation.
- Commence the next row of blankets with a ½ roll, to create a staggered brick-bond laying pattern with the row previously installed.
- At abutments and penetrations the blanket may be cut using a sharp knife and straight edge. It is generally easier to cut up through the carrier on the underside of the blanket than to cut through the vegetation. Alternatively, a disc cutter can be used (using the appropriate safety equipment i.e. gloves and eye protection). Before cutting using this method, ensure that protection is applied to the waterproofing beneath using a timber plank or plywood sheet.
- In situations where the vegetation barrier secures the blanket edges against wind uplift, the 20/40 mm pebble loading must extend onto the leading edge of the blanket by a minimum of 100mm.
- Upon the completion of an area installed over a maximum 4 hour period the installation is to be heavily watered to ensure that the blanket and substrate are saturated before moving on to the next area.
- Upon completion of the installation apply Bauder organic slow release fertilizer at a rate of 80g/m2 using the approved applicator trolley and thoroughly watered in.
- Care is to be taken to avoid the blanket being walked or stood upon unnecessarily or trafficked by other trades during and after the installation, as this will have an adverse effect on the vegetation.

## **INSTALLATION OF LONG ROLLS**

- The Bauder XF301 blanket can be supplied in long rolls in 1m increments from 3m to 10m.
- It is the contractor's responsibility to ensure that adequate unloading facilities and storage space on site will be available before the product is ordered.
- It is the contractor's responsibility to ensure that the appropriate crane with sufficient reach, load capacity and the Bauder crane attachment are present on site at the time of delivery.



- In addition to the crane driver, a workforce of 3 or 4 is required to carry out the installation efficiently. One of the operatives on the roof will need to give directions to the crane driver.
- If you have not previously carried out a Bauder long roll installation, please ensure that the Bauder Site Technician responsible for the project is informed at least 2 weeks before installation is due to commence, to ensure that the correct level of site support is provided.
- The general principals of installation for long rolls are the same as for 2 x1m rolls, with the exception that the roll ends must be staggered a minimum 1m in length instead of ½ roll, to ensure staggered joints.

#### **ESTABLISHMENT MAINTENANCE**

- After completion of the installation it will be necessary to keep the substrate and blanket damp for a period of at least 4 weeks immediately afterwards, and it may be necessary to irrigate for longer than this if installation is followed by a warm, dry spell of weather.
- Please do not over-water! It is equally important to ensure that the green roof substrate does not become totally saturated by either excessive watering through periods of cool, wet weather. Further information on watering requirements for this product is available to view or download from the Bauder web site <a href="https://www.bauder.co.uk">www.bauder.co.uk</a>. Log in and visit our Technical Centre and review the document "Watering Requirement Guidelines for Extensive and Biodiverse Green Roof installations"
- To encourage the plants to survive without too much irrigation and to harden them off in readiness to survive winter, it is important to start cutting back on watering from early September.
- The maintenance requirement in the following years will depend upon the weather experienced through the winter and early spring of each year and should follow our standard biodiversity green roof maintenance guidelines.

#### **SUPPORT**

- Modern extensive and bio-diverse green roof installations will normally require only minimal maintenance. Bauder is happy to offer advice on any issues concerning your green roof and enquiries should be forwarded to our Green Roof Technical Department at the address below.
- We believe our products and systems are of the highest standard and are always prepared to discuss any queries or concerns that may arise. Providing photographs or drawings to accompany your queries will help speed our response.

Please note: In the event of any query arising which it is thought may affect the condition of the system, then Bauder Ltd should be contacted at the address below. We cannot accept responsibility for any problem or failure due to use outside those parameters for which the system was designed or 'acts of god' beyond our control e.g. extreme weather conditions or damage through pests.